

State of Vermont

Division of Policy, Planning and Intermodal Development

219 North Main Street Barre, VT 05641 [fax] 802-828-3983 vtrans.vermont.gov [ttd] 800-253-0191

Agency of Transportation

MEMO

To: Abbie Sherman

> **Executive Director Vermont Economic Progress Council** Vermont Agency of Commerce & Community Development

2/25/2022 Joe Segale, PE/PTP JS From:

Policy, Planning and Research Bureau Director

Killington TIF District Application Re:

February 25, 2022 Date:

Per your request, I have reviewed the transportation related infrastructure costs that support the Town of Killington's January 2022 TIF District Application.

The transportation improvements are described in the Killington Road Master Planning Study (VHB, August 26, 2021) and generally include the full-depth reconstruction of Killington Road including new culverts, retaining walls and ditching; sidewalks and shared use paths along the length of Killington Road; new crosswalks including two with flashing beacons; intersection modifications including the installation of two traffic signals; and changing the profile of the Killington Road approach to US 4.

VHB estimated the total cost of the improvements to be \$21,660,000. We reviewed the line items in the construction cost estimate table presented in Appendix 4 of the Killington Road Master Planning Study relative to the Agency's bid history for similar line items and other standard practices. Appendix 4 is attached for reference. For the reasons described below, I recommend increasing the cost estimate to a total of \$25,640,000.

- There is a math error in the subtotal of construction costs in Appendix 4. The subtotal for construction costs of \$15,361,450 should be \$15,756,500. When combined with the percentage-based contingency, mobilization, engineering, and resident engineer costs, the total difference is \$556,820.
- The "Full Depth Roadway Construction" line item is low compared to the Agency's cost/mile bids for rural road reconstruction projects. The cost difference appears to be due to a lack of a sand borrow layer on the roadway typical section. Given the altitude and mountainous terrain of Killington Road, adding a sand layer is recommended to reduce damage to pavement during freeze/thaw cycles.
- The retaining wall unit price of \$80/square foot is significantly lower than the Agency's bid prices which range from \$158/sf to \$280/sf (average \$220/sf).
- The assumed rate for mobilization of 6% is lower than the Agency's practice of at least 8%, and often 10%.

The attached table shows the revised cost estimate with these modifications.



Killington TIF District Application February 25, 2022 Page 2 of 2

Right-of-way acquisition and traffic control are two cost uncertainties to monitor as the design is refined. There may be additional costs for acquiring right-of-way because the design appears to encroach on some adjacent parcels. Based on the Agency's experience constructing many projects, the total cost for traffic control of \$100,000, which admittingly is difficult to estimate, may only be adequate to cover changing the profile on the Killington Road approach to US 4. The contingency of almost \$2.7 million will help mitigate these cost risks to some extent.

Please feel free to contact me with any questions or comments at <u>joe.segale@vermont.gov</u> or at 802-477-2365.



Killington Road Master Planning Study (VHB, August 26, 2021)

Appendix 4 – Conceptual Cost Estimate

Construction Costs

	Description		Unit Cost	Quantity	Total Cost
1	Reprofile 1000' of Killington Road at US-4 intersection		Lump Sum	1	\$1,615,000
2	Full Depth Roadway Construction – Typical 3 Lane Section		\$322 / LF	13,975 LF	\$4,500,000
3	Full Depth Roadway Construction – 4 Lanes Section (+1 turn lane, bus lane, etc)		\$410 / LF	5,275 LF	\$2,161,50
4	East Mountain Road	ast Mountain Road		1,300 LF	\$395,000
5	Cement Concrete 6' Sidewalks bituminous 8' Shared Use Path		\$125 / LF	5,682 LF 14,862 LF	\$710,25 \$ 1486,20
6			\$100 / LF		
7	Retaining Walls		\$80 / SF	3,282 SF	\$262,55
8	Bus Shelters		\$10,000 / EA	17	\$170,00
9	Pedestrian Flashing Beacons (RRFBs)		\$10,000 / EA	4	\$40,00
10	Street Lighting	Lump Sum Lump Sum		n/a	\$2,516,00
11	Culverts & Drainage Ditches			n/a	\$1,000,00
12	Traffic Control		Lump Sum	n/a	\$100,00
13	Signing and Striping		Lump Sum	n/a	\$100,00
14	Landscaping		Lump Sum	n/a	\$100,00
15	Traffic Signal Systems		\$300,000 / EA	2	\$600,00
	Subtotal	T		—	\$15,361,45
	15% Contingency	Total should be \$15,756,50	0		\$2,304,20
	6% Mobilization				\$921,70
	10% Engineering & Design				\$1,536,20
	10% Resident Engineer				\$1,536,20
			TOTAL (ROUNDED)		\$21,660,00
					X

Total should be \$22,216,820

Killington Road Master Plan Construction Cost Estimate with VTrans Recommended Modifications

February 25, 2022

Item	Description	Unit Cost	Quantity	Item Total	Modifications	
1	Reprofile 1000' of Killington Road at US-4 intersection	1 Lump Sum	n/a	\$1,615,000		
2	Full Depth Roadway Construction – Typical 3 Lane Section	\$404 /LF	13,975	\$5,641,708	Added \$81.70 per If to account sand borrow	
3	Full Depth Roadway Construction – 4 Lanes Section (+1 turn lane, bus lane, etc)	\$519 /LF	5,275	\$2,737,725	Added \$109 per If to account sand borrow	
4	East Mountain Road	\$303 /LF	1,300	\$393,900		
5	Cement Concrete 6' Sidewalks	\$125 /LF	5,682	\$710,250		
6	Bituminous 8' Shared Use Path	\$100 /LF	14,862	\$1,486,200		
7	Retaining Walls	\$220 /SF	3,282	\$722,040	Changed unit cost from \$80/sf to \$220/sf	
8	Bus Shetlers	\$10,000 /EA	17	\$170,000		
9	Pedestrian Flashing Beacons (RRFBs)	\$10,000 /EA	4	\$40,000		
10	Street Lighting	1 Lump Sum		\$2,516,000		
11	Culverts & Drainage Ditches	1 Lump Sum	n/a	\$1,000,000		
12	Traffic Control	1 Lump Sum	n/a	\$100,000		
13	Signing and Striping	1 Lump Sum	n/a	\$100,000		
14	Landscaping	1 Lump Sum	n/a	\$100,000		
15	Traffic Signal Systems	\$300,000 EA	2	\$600,000		
Sub-Total				\$17,932,823		
15%	Contingency			\$2,689,923		
8%	Mobilization			51.434.676	Changed mobilization from 6% to 8%	
10%	Engineering & Design			\$1,793,282		
10%	Residential Engineer			\$1,793,282		
		\$25,643,936				