

TODD FROST, ROOFING
407 BASIN ROAD, VERNON, VT 05354
TEL: 802-579-5822

9/20/16

Centre Congregational Church
193 Main Street
Brattleboro, VT 05301
Attn.: Roger Miller, Buildings and Grounds

Dear Mr. Miller,
Per your request, here is my quote for replacing the failing flat roof at Centre Congregational Church with a new membrane roof.

QUOTE:

1. Install ½" X 4" Nailer around perimeter
2. Remove existing new drain inserts
3. Install approximately 40 square ½" ISO Board using 3 inch plates and screws over existing roof
4. Install approximately 40 square TPO Rubber, mechanically fastened 1 ½ " plates and screws
5. Install new wall flashings/curb flashings
6. Re-install drain inserts
7. Install new perimeter drip edge
8. Install 6" pressure tape over drip edge

For the sum of \$19,500

Thank you for the opportunity to quote the church on the installation of a new roof.

Sincerely,

Todd Frost