



MIKE ERAMO MASONRY

3522 N Hollow Rd
Granville, VT 05747
T 802.767.3569
F 802.767.6030

10/3/16

The Corner School Resource Center of Granville, Inc.

75 Post Office Hill Rd.
Granville, VT 05747
T. 802.767.9703

PROPOSAL

Elevate Building:

1. Elevate existing building and crib in place.
2. After all foundation work is completed, lower building, anchor to new foundation.

Labor and material: \$ 10,170.00

Excavation:

1. Remove existing foundation and dispose of.
2. Remove silt in crawl space.
3. Excavate for new foundation footing.

Labor and material: \$ 2,500.00

Foundation:

1. Form and pour new footing.
2. Form and pour new foundation using Insulated Concrete Forms.
3. Foundation to be 6' height from footing to sill.
4. Backfill new foundation, finish grade, seed and hay disturbed soils.

Labor and material: \$ 12,075.00

Summary:

Elevate building: \$ 10,170.00

Excavation: \$ 2,500.00

Foundation: \$ 12,075.00

Total of all areas: \$ 24,745.00