

# Town of North Hero

PO Box 38

North Hero, VT 05474

[www.northherovt.com](http://www.northherovt.com)

April 2, 2013

To: Planning Commission Chair of Isle La Motte, Alburgh, Grand Isle, St. Albans and Swanton  
Catherine Dimitruk, Executive Director – NRPC, 155 Lake St., St. Albans, VT 05478  
✓ DEHCD, National Life Building, Drawer 20, Montpelier, VT 05620-0501

Enclosed please find a copy of the following:

- 1.) North Hero Planning Commission Public Hearing Notice
- 2.) North Hero Bylaw Amendment Report
- 3.) North Hero Development Regulations

We are providing copies to adjoining municipalities for your review and comment, either in writing or in person, at our public hearing.

Sincerely,



Pete Johnson  
Town Clerk/Treasurer – North Hero



# PUBLIC HEARING

## PROPOSED AMENDMENTS TO TOWN OF NORTH HERO DEVELOPMENT REGULATIONS

Scheduled for Monday, April 29<sup>th</sup>, at 7:00 p.m., at the North Hero  
Town Office Meeting Room

Notice is hereby given to the residents of the Town of North Hero that the Planning Commission will hold a hearing on Monday, April 29<sup>th</sup> at 7:00pm at the North Hero Town Office Meeting Room to receive public comment on the following proposed amendments to the North Hero Development Regulations, pursuant to Chapter 117 of Title 24, Section 4384 and 4441, Vermont Statutes Annotated.

The Town of North Hero revised the following provisions of the North Hero Development Regulations:

- *The entire document was reorganized and reformatted.*
- *The Village District size was reduced to reflect actual village area. The proposed boundary matches the designated village center boundaries.*
- *Zoning District purpose statements were developed to assist in determining whether a project conforms to the character of the area.*
- *Allowed uses were incorporated into a table and reviewed and modified as needed for consistency and clarification. Definitions for all uses were developed.*
- *Dimensional standards were incorporated into a table.*
- *The density reserve provision was eliminated, which was difficult to understand and administer.*
- *The certificate of occupancy and certificate of compliance process was revised.*
- *Development that requires a zoning permit and development that is exempt was clarified.*
- *The conditional use review standards were revised and expanded.*
- *Site plan review standards were incorporated into conditional use review to streamline the process.*
- *Setback exceptions and waiver procedures were revised for clarity.*
- *The Special Flood Hazard Area review standards were updated to conform with the National Flood Insurance Program.*
- *The planned unit development review standards were updated and expanded.*
- *The deeded access to the lake provisions were revised for clarity; they are now permitted as residential marine associations.*
- *The subdivision review standards were updated and expanded.*
- *Stormwater management and erosion control standards were added.*
- *Lighting standards were added.*
- *Sign standards were added.*

- *Landscaping and screening standards were added.*
- *Road and driveway standards were added.*
- *Shoreline protection and shoreline stabilization standards were added.*
- *Accessory dwelling unit review standards were revised.*
- *Standards for off-grid solar arrays and wind towers were added.*
- *The telecommunication facilities standards were revised to conform to Vermont Statute.*
- *Standards for earth resource extraction were revised.*
- *Standards for lake access structures were revised for clarity.*
- *Standards for home occupations were revised to allow for exempt home businesses.*
- *Standards for marinas and yacht clubs were revised.*
- *Review of pre-existing small lots was revised to reflect current practice.*
- *Definitions were incorporated as needed.*

Complete copies of the proposed revisions to the Development Regulations are available at the Town Office or at [www.northherovt.com](http://www.northherovt.com).

## NORTH HERO BYLAW AMENDMENT REPORT

### April 2013

---

The North Hero Planning Commission has prepared a comprehensive rewrite of the North Hero Zoning Bylaws. The rewritten document is renamed the North Hero Development Regulations. *This report has been prepared in conformance with 24 V.S.A. Section 4441. The revision was funded in part with a Municipal Planning Grant from the Vermont Department of Economic, Housing and Community Development with assistance from the Northwest Regional Planning Commission.*

The purpose of the North Hero Development Regulations is to provide for orderly community growth and to further the purposes established in the North Hero Town Plan and in the Vermont Planning and Development Act, Title 24 V.S.A. Chapter 117.

A summary of substantive changes made to the existing regulations is listed below. Full copies of the revised regulations are available at the North Hero Town Clerk's Office.

- The entire document was reorganized and reformatted.
- The Village District size was reduced to reflect actual village area. The proposed boundary matches the designated village center boundaries.
- Zoning District purpose statements were developed to assist in determining whether a project conforms to the character of the area.
- Allowed uses were incorporated into a table and reviewed and modified as needed for consistency and clarification. Definitions for all uses were developed.
- Dimensional standards were incorporated into a table.
- The density reserve provision was eliminated, which was difficult to understand and administer.
- The certificate of occupancy and certificate of compliance process was revised.
- Development that requires a zoning permit and development that is exempt was clarified.
- The conditional use review standards were revised and expanded.
- Site plan review standards were incorporated into conditional use review to streamline the process.
- Setback exceptions and waiver procedures were revised for clarity.
- The Special Flood Hazard Area review standards were updated to conform with the National Flood Insurance Program.
- The planned unit development review standards were updated and expanded.
- The deeded access to the lake provisions were revised for clarity; they are now permitted as residential marine associations.
- The subdivision review standards were updated and expanded.
- Stormwater management and erosion control standards were added.
- Lighting standards were added.
- Sign standards were added.
- Landscaping and screening standards were added.
- Road and driveway standards were added.

- Shoreline protection and shoreline stabilization standards were added.
- Accessory dwelling unit review standards were revised.
- Standards for off-grid solar arrays and wind towers were added.
- The telecommunication facilities standards were revised to conform to Vermont Statute.
- Standards for earth resource extraction were revised.
- Standards for lake access structures were revised for clarity.
- Standards for home occupations were revised to allow for exempt home businesses.
- Standards for marinas and yacht clubs were revised.
- Review of pre-existing small lots was revised to reflect current practice.
- Definitions were incorporated as needed.

The North Hero Development Regulations conform to and further all the goals and policies contained in the North Hero Town Plan. The land use districts in the proposed Development Regulations are compatible with those contained in the Town Plan. Listed below are some examples of how these proposed regulations implement the goals of the Plan.

- 1) To preserve the unique rural and small town character of North Hero.
- 2) To protect the quality of the environment and the lake.
- 3) To maintain the visual character and aesthetic setting of North Hero.
- 4) To maintain the community and to enhance the sense of community in North Hero.
- 5) To foster quality growth and controlled development in North Hero.
- 6) To engage in a continued, coordinated and comprehensive planning process and to encourage active citizen participation throughout the process.
- 7) To assure the safe and efficient use of both town and state road networks.
- 8) To maintain a comprehensive mapping system of North Hero.
- 9) To regularly review public and private incentives, grants, and other incentives as tools to promote Town goals and address local needs.
- 10) To promote safe, healthy and affordable housing located conveniently to employment, services, retail centers, and educational and recreational facilities as well as park and ride.
- 11) To promote increased awareness and use of renewable energy resources as well as the conservation of existing energy resources.

Copies of the proposed North Hero Development Regulations are available from the North Hero Town Clerk's Office and may also be downloaded from the Town's website:

<http://www.northherovt.com>. A public hearing will be held at the North Hero Town Meeting Room on April 29, 2013 at 7pm. Comments should be forwarded in writing to the North Hero Planning Commission, PO Box 38, North Hero, VT 05474



# **NORTH HERO DEVELOPMENT REGULATIONS**

## **Final Draft**

**Adopted by the North Hero Selectboard on \_\_\_\_\_**

*Prepared by the North Hero Planning Commission, with assistance from the  
Northwest Regional Planning Commission.*

*This project was funded in part by the Municipal Planning Grant Program  
administered by the Vermont Department of Economic, Housing, and  
Community Development.*

***Table of Contents –FOR PURPOSES OF THIS REVIEW YOU WILL SEE REFERENCES TO SECTIONS IN PARENTHESES. THESE REFER TO THE SECTIONS OF THE PREVIOUS SET OF BYLAWS.***

---

<b><i>Article 1: Authority and Purpose</i></b>	<b>2</b>
Section 1.1: Enactment (Section 110)	2
Section 1.2: Purpose (Section 120)	2
Section 1.3: Application of Regulations (Section 130)	2
Section 1.4: Statutory Exemptions (Section 401)	2
Section 1.5: Interpretation (Section 140)	3
Section 1.6: Severability (Section 160)	3
Section 1.7: Amendments (Section 150)	3
Section 1.8: Application Under Pending Amendment to these Regulations	3
Section 1.9: Effective Date (Section 180)	4
<b><i>Article 2: Administration and Enforcement</i></b>	<b>5</b>
Section 2.1: Administration	5
Section 2.2: Fees (Section 322)	5
Section 2.3: Zoning Permits Issued by the Zoning Administrator (Section 323)	5
Section 2.4: Applications before the DRB (Section 380)	6
Section 2.5: Appeals (Section 385)	8
Section 2.6: Violations and Enforcement (Section 335)	9
<b><i>Article 3: Zoning Districts</i></b>	<b>10</b>
Section 3.1: Establishment of Zoning Districts (Section 200)	10
<b><i>Article 4: Zoning Permits and Certificates of Occupancy</i></b>	<b>13</b>
Section 4.1: Zoning Permits (Section 325)	13
Section 4.2: Certificate of Occupancy and Certificate of Compliance (Section 328)	14
Section 4.3: Temporary Uses and Structures (Section 326)	15
Section 4.4: Abandoned and Destroyed Structures (Section 330)	16
<b><i>Article 5: Land Uses, Density and Setback Standards</i></b>	<b>17</b>
Section 5.1: Land Uses	17
Section 5.2: Density, Setback and Other Dimensional Standards.	19
Section 5.3: Uses and Structures Per Lot (Section 420)	20

Section 5.4:	Frontage (Section 423)	21
Section 5.5:	Setbacks (Section 500)	21
Section 5.6:	Height (Section 422)	22
Section 5.7:	Lot Coverage (Section 413)	23
<b>Article 6: DRB Approvals</b>		<b>24</b>
Section 6.1:	Conditional Use Review (Section 327)	24
Section 6.2:	Setback Waiver	27
Section 6.3:	Variances (Section 329)	28
Section 6.4:	Planned Unit Development (PUD) (Section 352)	29
Section 6.5:	Subdivision (Section 340)	32
<b>Article 7: Development Standards</b>		<b>41</b>
Section 7.1:	Application of Standards	41
Section 7.2:	Fences (Section 426)	41
Section 7.3:	Landscaping and Screening (Section 436)	41
Section 7.4:	Outdoor Lighting	42
Section 7.5:	Parking Areas/Lots (Off Road Parking) (Section 438)	43
Section 7.6:	Performance Standards for Uses (Section 440)	44
Section 7.7:	Road, Driveways and Access Standards	44
Section 7.8:	Shoreline Protection	46
Section 7.9:	Signs (Section 430)	47
Section 7.10:	Storage of Seasonal Vehicles and Equipment (Section 490)	49
Section 7.11:	Stormwater Management and Erosion Control	49
Section 7.12:	Wastewater System (Septic) and Potable Water Supply (Section 480)	50
Section 7.13:	Handicapped Access	50
<b>Article 8 Specific Use/Structure Standards</b>		<b>51</b>
Section 8.1:	Application of Standards	51
Section 8.2:	Accessory Dwelling Units (Section 401)	51
Section 8.3:	Agricultural Housing	52
Section 8.4:	Campgrounds, Mobile Home Parks and Travel Trailer Camps/Parks (Section 446)	52
Section 8.5:	Earth Resource Extraction (Section 448)	53
Section 8.6:	Family Child Care Home or Facility	54
Section 8.7:	Gasoline Stations and Motor Vehicle Service Stations (Section 450)	55
Section 8.8:	Group Homes	55
Section 8.9:	Home Based Businesses (Section 452)	55

Section 8.10: Lake Access Structures _____	57
Section 8.11: Light Industry and Commercial Activity _____	58
Section 8.12: Marinas, Yacht Clubs and Residential Marine Associations (Section 456)___	58
Section 8.13: Public Facilities (Section 404) _____	60
Section 8.14: Shoreline Stabilization Measures _____	60
Section 8.15: Small Off-Grid Energy Generation Systems _____	61
Section 8.16: RV and Travel Trailers (Section 464) _____	62
Section 8.17: Wireless Telecommunication Facilities _____	64
<b>Article 9: Nonconformities</b> _____	<b>68</b>
Section 9.1: Nonconforming Lots _____	68
Section 9.2: Non-Conforming Structures and Uses(Section 375) _____	68
<b>Article 10: Flood Hazard Regulations</b> _____	<b>71</b>
Section 10.1 Land to Which these Standards Apply _____	71
Section 10.2 Development Permits in the Flood Hazard Overlay District _____	71
Section 10.3 Application Requirements _____	72
Section 10.4 Flood Hazard Area Development Standards _____	73
Section 10.5 Standards for Review of Nonconforming Structures. _____	75
Section 10.6 Variances to the Development Standards. _____	76
Section 10.7 Recording Requirements _____	76
Section 10.8 Violation of Flood Hazard Area Regulations _____	77
Section 10.9 Flood Hazard Definitions _____	77
<b>Article 11: General Definitions</b> _____	<b>82</b>

## **List of Maps, Figures and Tables**


### Zoning Map

Figure 1.1	How to Get a Zoning Permit: At a Glance
Figure 4.1	Definitions of Structure and Land Use
Figure 5.3	Definitions of Principal Use/Structure and Accessory Use/Structure
Figure 5.5	Measuring Setbacks
Figure 5.6	Measuring Height
Figure 6.5(a)	Definition of Subdivision
Figure 6.5(b)	Plan and Survey Plat Specifications
Figure 7.3	Native and Invasive Plant References
Figure 7.9	Examples of Total Sign Area
Figure 9.2	Increasing the Degree of Nonconformity for Structures
Table 5.1	Land Uses
Table 5.2	Density and Dimensional Standards
Table 6.5	Subdivision Sketch Plan/Site Plan Requirements
Table 7.5	Off-Street Parking Space Requirements

### **Reference Materials**

- 1) The Vermont Municipal and Regional Planning and Development Act, Title 24, Chapter 117 V.S.A (The Act).
- 2) Accepted Agricultural and Best Management Practices as adopted in rules by the Agency of Agriculture.
- 3) Vermont Rail Garden Plant List
- 4) Elmore Roots Vermont Native Plant List
- 5) The Vermont Invasive and Exotic Plant Committee's List
- 6) Vermont Stormwater Management Manual
- 7) Vermont Handbook for Soil Erosion and Sediment Control on Construction Sites
- 8) Shoreline Stabilization Handbook for Lake Champlain and other Inland Lakes
- 9) VT Lakeshore Protection Series #3 Plants and Plantings on Lakeshores

1 **Figure 1.1 How to Get a Zoning Permit: At a Glance**



2

1 **ARTICLE 1: AUTHORITY AND PURPOSE**

---

2  
3 **SECTION 1.1: ENACTMENT (SECTION 110)**

4  
5 The North Hero Development Regulations set forth in the following text and map are  
6 hereby established pursuant to the Vermont Municipal and Regional Planning and  
7 Development Act, 24 V.S.A., Chapter 117 (hereinafter referred to as the "Act").  
8

9 **SECTION 1.2: PURPOSE (SECTION 120)**

10  
11 The intent of these Regulations is to provide for orderly community growth and to further  
12 the purposes established in the North Hero Town Plan and in the Act.  
13

14 **SECTION 1.3: APPLICATION OF REGULATIONS (SECTION 130)**

15  
16 No land development shall take place unless in compliance with the North Hero  
17 Development Regulations.  
18

19 Land Development is defined as the division of a parcel into two (2) or more parcels; the  
20 new construction, reconstruction, conversion, structural alteration, relocation, or  
21 enlargement of any building or other structure; any mining or earth resource extraction;  
22 or any change in the use of any building, other structure, or land, or extension of the use  
23 of land.  
24

25 **SECTION 1.4: STATUTORY EXEMPTIONS (SECTION 401)**

26  
27 The following uses and structures are specifically exempted from municipal land use  
28 and development regulations by Vermont State law. In accordance with the Act  
29 [§4413], no municipal Zoning Permit or approval under these Regulations shall be  
30 required for:  
31

- 32 1) Accepted agricultural and best management practices (AAPs, BMPs) as adopted in  
33 rules by the Agency of Agriculture (see [www.vermontagriculture.com](http://www.vermontagriculture.com)), including farm  
34 structures, as defined by the Secretary of Agriculture, Food and Markets in  
35 accordance with the Act (Title 6 §4810). However, written notification, including a  
36 sketch plan of the farm structure showing setback distances from road rights-of-way,  
37 property lines, and surface waters shall be made to the ZA prior to any construction  
38 as required under the AAPs. Agricultural practices that are governed by the AAPs  
39 include, but are not limited to the following:  
40 a) The confinement, feeding, fencing, and watering of livestock.  
41 b) The handling of livestock wastes and by-products.  
42 c) The collection of maple sap and production of maple syrup.  
43 d) The preparation, tilling, fertilization, planting, protection, irrigation and harvesting  
44 of crops.

- e) The ditching and subsurface drainage of farm fields and the construction of farm ponds.
  - f) The stabilization of farm field streambanks constructed in accordance with the United States Department of Agriculture Natural Resources Conservation Service standards and specifications or other standards approved by the Commissioner.
- 2) Accepted management practices (AMPs) for silviculture (forestry) as defined by the Commissioner of Forests, Parks, and Recreation, pursuant to the Act.
  - 3) Public utility power generating plants and transmission facilities that are regulated by the Vermont Public Service Board [under 30 V.S.A. §248], including net-metered wind generation facilities and solar panels.
  - 4) Hunting, fishing or trapping on public or private land as specified by the state [under 24 V.S.A. §2295]. This excludes facilities that may support such activities, such as firing ranges, rod and gun clubs, and fish and game clubs, which are subject to these Regulations.

**SECTION 1.5: INTERPRETATION (SECTION 140)**

These Regulations shall not repeal, abrogate or impair any other applicable land use controls (including statutes, regulations, rules, ordinances, permits, easements, deed restrictions, covenants or similar devices). However, in their interpretation and application, the provisions of these Regulations shall be held to be minimum requirements which shall take precedence over any concurrent and less restrictive such control. It is also hereby stated that in any conflict or dispute involving these Regulations, that the intent shall be considered in resolving any ambiguity.

**SECTION 1.6: SEVERABILITY (SECTION 160)**

If any portions of these Regulations are held unconstitutional or invalid by a court of competent jurisdiction, the unaffected portions shall remain in force, and for this purpose the provisions of the Regulations are severable.

**SECTION 1.7: AMENDMENTS (SECTION 150)**

These Regulations may be amended according to the requirements and procedures established in 24 V.S.A. §4441 and §4442 of the Act.

**SECTION 1.8: APPLICATION UNDER PENDING AMENDMENT TO THESE REGULATIONS**

In accordance with 24 V.S.A. §4449(d), once the North Hero Selectboard has issued a public notice to amend these regulations, the Zoning Administrator shall review any new application under both the proposed amendment and applicable existing regulations. If the new bylaw or amendment has not been adopted or rejected within 150 days of that notice or, if the bylaw is rejected, the application shall be reviewed under the existing regulations. An application that has been denied under a proposed bylaw or

1 amendment that has not been adopted, or had been rejected, shall be reviewed again  
2 at no cost under the existing regulations at the request of the applicant.

3

4 **SECTION 1.9: EFFECTIVE DATE (SECTION 180)**

5

6 These Regulations take effect upon adoption in accordance with the procedures  
7 contained in the Act.

8

9

10

11

1 **ARTICLE 2: ADMINISTRATION AND ENFORCEMENT**  
2

---

3 **SECTION 2.1: ADMINISTRATION**  
4

5 **A) Zoning Administrator (ZA) (Section 320).** The Selectboard shall appoint, from  
6 nominations submitted by the Planning Commission, a Zoning Administrator (ZA) for  
7 a term of three (3) years in accordance with the Act §4448. The ZA is a municipal  
8 employee, reporting to the Planning Commission. An acting or assistant ZA may  
9 also be appointed by the Selectboard pursuant to the Act. The ZA shall literally  
10 administer and strictly enforce the provisions of these Regulations.  
11

12 **B) Development Review Board (DRB).** The DRB shall be appointed by the  
13 Selectboard in accordance with 24 V.S.A. §4460. The DRB shall work as  
14 cooperatively with applicants as possible and shall hear and decide applications for:  
15

- 16 1) Appeals of ZA decisions;
- 17 2) Conditional Use Review;
- 18 3) PUD approval;
- 19 4) Subdivision approval;
- 20 5) Access by right-of way to lots without frontage;
- 21 6) Development in the Flood Hazard Area Overlay District;
- 22 7) Variances;
- 23 8) Setback Waivers.  
24

25 **SECTION 2.2: FEES (SECTION 322)**  
26

27 The Selectboard will establish fees for Zoning Permits, Certificates of Occupancy,  
28 Certificates of Compliance, and DRB review. Such fee(s) shall include the costs of  
29 public notice, public hearings, and site visits. Fees must be paid for applications to be  
30 considered complete. Fees are non-refundable.  
31

32 **SECTION 2.3: ZONING PERMITS ISSUED BY THE ZONING ADMINISTRATOR**  
33 **(SECTION 323)**  
34

35 **A)** Within thirty (30) days of receipt of a completed application for land development,  
36 including all application materials and fees, the ZA shall issue or deny a Zoning  
37 Permit in writing, return the application for completion, or refer the application to the  
38 DRB for their review and action. In the case of a referral, the ZA shall issue or deny  
39 a Zoning Permit in conjunction with the issuance of a DRB decision. If a Zoning  
40 permit is denied, the ZA shall so notify the applicant in writing, stating the reasons  
41 for denial. If the ZA fails to act on a complete application by issuance, denial or  
42 referral within the 30 day period, the permit shall result in deemed approval.  
43

- 44 1) When the ZA issues a Zoning Permit, the applicant shall post a permit notice, on  
45 a form provided by the Town of North Hero, within view of the public right-of-way

1 most nearly adjacent to the subject property until the applicable time for appeal  
2 has passed (see Section 2.5). The notice shall contain a statement of the appeal  
3 period and information noting where a full description of the project and approval  
4 can be found.

5 2) Within three (3) days following the issuance of a Zoning Permit, the ZA shall post  
6 a copy of the permit in the Town Clerk's Office until the expiration of the appeal  
7 period and deliver a copy of the permit to the Listers.

8 3) Within 30 days after a Zoning Permit has been issued or within 30 days of the  
9 issuance of any notice of violation, the appropriate municipal official shall:

- 10 a) deliver the original or a legible copy of the municipal land use permit or notice  
11 of violation generally in the form set forth in 24 V.S.A. §1154(c) of this title to  
12 the Town Clerk for recording as provided in 24 V.S.A. §1154(a); and  
13 b) file a copy of that municipal land use permit in the offices of the municipality in  
14 a location where all municipal land use permits shall be kept.  
15

## 16 SECTION 2.4: APPLICATIONS BEFORE THE DRB (SECTION 380)

17  
18 **A) Public Hearing/Public Notice Requirements for DRB Decisions.** A public  
19 hearing in accordance with Section 4463(a) and 4464(a) of the Act is required before  
20 the DRB may issue any decision. Notice for public hearings shall be given not less  
21 than 15 days prior to the date of the public hearing in the following ways:  
22

- 23 1) **Publication** of the date, place, and purpose of the hearing in a newspaper of  
24 general circulation in the Town of North Hero and **posting** of the same  
25 information in three or more public places within the Town in conformance with  
26 location requirements of 1 V.S.A. § 312(c)(2), including posting within view from  
27 the public right-of-way most nearly adjacent to the property for which an  
28 application is made.  
29

30 All public notices will be created by the Town of North Hero. Town personnel will  
31 be responsible for all public notice postings.  
32

- 33 2) Written notification to the applicant and to owners of all properties adjoining the  
34 property subject to development. Adjoining properties include those that are  
35 divided by a highway or other public right-of-way. Written notification shall  
36 include a description of the proposed project and shall be accompanied by  
37 information that clearly informs the recipient where additional information may be  
38 obtained, and that participation in the local proceeding is a prerequisite to the  
39 right to take any subsequent appeal.  
40

41 Written notification to the applicant and abutters shall be completed by the Town  
42 of North Hero.  
43

44 **B) Continued Public Hearings.** The DRB may continue a hearing on any application  
45 or appeal pending the submission of additional information affecting the approval  
46 under question, provided that the next hearing date, time, and place are announced

1 at the hearing. If a hearing is adjourned, postponed or continued with no date  
2 certain, or if a hearing date is changed, the hearing will be reconvened with full  
3 notice of the hearing according to 2.4(A) above.  
4

5 **C) DRB Decisions.** The DRB shall prepare a written decision for all land development  
6 applications referred from the ZA within 45 days after the adjournment of the public  
7 hearing. Failure to issue a decision within the 45-day period shall result in deemed  
8 approval. All decisions shall be issued in writing and shall separately state findings  
9 of fact and conclusions of law. The decision shall also include a statement of the  
10 time within which appeals under Section 2.5 may be taken. The minutes of a  
11 meeting may suffice as a decision, provided that the factual basis and conclusions  
12 relating to the review standards are provided in accordance with these  
13 requirements. In making a decision in favor of the applicant, the DRB may attach  
14 conditions and safeguards as it deems necessary to implement the purposes of the  
15 Act, these regulations, and the Town Plan currently in effect.  
16

17 Decisions shall be issued according to the following procedure:

- 18 1) The Board's decision shall be submitted to the ZA who shall issue or deny a  
19 Zoning Permit in accordance with the decision and send the decision along with  
20 the Zoning Permit or denial by certified mail to the applicant.
- 21 2) Copies of each decision shall also be mailed to every person or body appearing  
22 and having been heard as an interested party at the hearing.
- 23 3) Copies shall be filed with the ZA and the Town Clerk as part of the public records  
24 of the Town, including memorandums of municipal action.  
25

26 **D) Coordinated Review.** In accordance with 24 V.S.A. Section 4462, in cases where a  
27 proposed project will require more than one type of DRB approval, the DRB may  
28 warn and hold a combined hearing for the purpose of reviewing and acting on the  
29 proposal. The ZA shall identify proposed projects appropriate for combined review  
30 and assist applicants in preparing and submitting coordinated applications to  
31 facilitate combined review. Notice for a combined review hearing shall be made in  
32 accordance with this Section. The hearing notice shall include a statement that the  
33 hearing will be a combined review of the proposed project and list each review  
34 process that will be conducted at the hearing. As applicable, the combined review  
35 process shall be conducted in the following order:

- 36 1) Subdivision Approval (preliminary and final)
- 37 2) Planned Unit Development Approval
- 38 3) Conditional Use Review
- 39 4) Requests for Variances and Setback Waivers
- 40 5) Access by Right-of-Way  
41

42 All hearing and decision requirements, and all deadlines applicable to each review  
43 process, shall apply. Separate written decisions may be issued for each review  
44 conducted as part of the combined review, but shall be coordinated for consistency  
45 where appropriate.  
46

1 **SECTION 2.5: APPEALS (SECTION 385)**  
2

3 **A) Appealing Decisions of the Zoning Administrator.** The applicant or any  
4 interested person (as defined in the Act § 4465(b)) may appeal any decision or act  
5 taken by the ZA by filing a written Notice of Appeal with the Town Clerk and filing a  
6 copy of the Notice of Appeal with the ZA within 15 days of the Act or decision. The  
7 Notice of Appeal will not be considered complete without the applicable fee (Section  
8 2.2).

- 9 1) A Notice of Appeal filed under this Section shall include the following information  
10 in accordance with § 4466 of the Act:  
11 a) the name and address of the appellant;  
12 b) a brief description of the property with respect to which the appeal is taken;  
13 c) a reference to the applicable provisions of these regulations;  
14 d) the relief requested by the appellant, including any request for a variance  
15 from one or more provisions of these regulations; and  
16 e) the alleged grounds why such relief is believed proper under the  
17 circumstances.  
18 2) The DRB shall set a date, time, and place for a public hearing on an appeal  
19 which shall be within 60 days of filing of the Notice of Appeal according to  
20 Section 4465 of the Act. The public hearing shall be warned in accordance with  
21 Section 2.4(A) above.  
22 3) In accordance with the Act, Section 4464(b), upon completion of a hearing, the  
23 DRB shall render a written decision within forty-five (45) days. Failure to render  
24 a decision within the required time period shall result in deemed approval. Copies  
25 of the decision shall be sent to:  
26 a) the applicant (by certified mail);  
27 b) the appellant (by certified mail);  
28 c) every person or party appearing and having been heard as an interested  
29 party at the hearing;  
30 d) the ZA; and  
31 e) the Town Clerk for filing as part of the public records of the Town.  
32

33 **B) Appealing Decisions of the DRB.** The applicant or any other interested person  
34 who has participated in a municipal regulatory proceeding as defined in the Act  
35 Section 4471 may appeal any decision of the DRB within 30 days of such decision to  
36 the Vermont Environmental Court.  
37

38 According to the Act Section 4471(c), within thirty (30) days following the date of  
39 decision rendered by the DRB, Notice of Appeal shall be filed by:

- 40 1) Certified Mailing, with fees, to the Environmental Court;  
41 2) Mailing a copy to the DRB Clerk, who shall provide a list of interested persons to  
42 the appellant within 5 working days; and  
43 3) Upon receipt of the list of interested persons, the appellant shall, by certified mail,  
44 provide a copy of the Notice of Appeal to every interested person.  
45

1 **SECTION 2.6: VIOLATIONS AND ENFORCEMENT (SECTION 335)**  
2

3 **A) Violations.** The commencement or continuation of any land development,  
4 subdivision, or use, which is not in conformance with these Regulations, is a  
5 violation. Any person who is found in violation of these Regulations shall be fined  
6 not more than the amount permitted under the Act § 4451. Each day that a violation  
7 is continued shall be a separate offense. All fines imposed and collected shall be  
8 paid to the Town of North Hero.  
9

10 **1) Enforcement Remedies.** In accordance with the Act § 4452, if any street,  
11 building, structure or land is or is proposed to be erected, constructed,  
12 reconstructed, altered, converted, maintained, or used in violation of these  
13 Regulations, the ZA shall institute in the name of the Town any appropriate  
14 action, injunction or other proceeding to prevent, restrain, correct, or abate such  
15 construction or use, or to prevent, in or about such premises, any act, conduct,  
16 business, or use constituting a violation. A court injunction may be initiated in the  
17 Environmental Court, or as appropriate before the Judicial Bureau, as provided  
18 under the Act § 1974a.  
19

20 **2) Notice of Violation.** No action may be brought under this section unless the  
21 alleged offender has had at least seven days warning notice by certified mail. An  
22 action may be brought without the seven-day notice and opportunity to cure if the  
23 alleged offender repeats the violation of the bylaw or ordinance after the seven  
24 day notice period and within the next succeeding 12 months. The seven-day  
25 warning notice shall state that a violation exists, that the alleged offender has an  
26 opportunity to cure the violation within the seven days, and that the alleged  
27 offender will not be entitled to an additional warning notice for a violation  
28 occurring after the seven days.  
29

30 **C) Limitations on Enforcement.** North Hero shall observe the 15 year limitation on  
31 enforcement proceedings relating to municipal permits and approvals as set forth in  
32 the Act [§ 4454].  
33  
34  
35

1 **ARTICLE 3: ZONING DISTRICTS**

---

2  
3 **SECTION 3.1: ESTABLISHMENT OF ZONING DISTRICTS (SECTION 200)**

4  
5 **A) Zoning Districts.** The Town of North Hero is hereby divided into the following  
6 Zoning Districts as shown on the Official Zoning Map:  
7

- 8 **1) Village District (V) (Section 250).** The Village District is located along City Bay  
9 extending south to Station Road, west approximately 450 feet from Route 2, and  
10 to the north side of Northland Lane. It also extends about 850 feet west along  
11 Northland Lane. The Village District is characterized primarily by single and two-  
12 family residences, but also includes a mix of commercial, municipal and  
13 recreational uses. The density of development is low (2-acre minimum lot size);  
14 however, relatively higher than the surrounding Rural District. The purpose of  
15 the Village District is to maintain and further this traditional village character.  
16
- 17 **2) Rural Lands District (RL) (Section 220).** The Rural Lands District consists of  
18 the balance of land in North Hero that is not designated as Village, Shorelands,  
19 Conservation, or Off Islands District. While farming is the primary use in this  
20 District, low density residential areas, as well as recreational, commercial and  
21 light industrial uses may be approved with careful review by the DRB.  
22 Development review shall focus on siting development to maintain the rural  
23 character of this District, which consists of open agricultural land with views of  
24 Lake Champlain, the Adirondacks and the Green Mountains.  
25
- 26 **3) Conservation District (C) (Section 210).** This District contains all those lands  
27 within North Hero requiring the most protection and is composed mainly of low  
28 swampy sections serving as cover and habitat for many forms of wildlife. These  
29 lands include but are not limited to Class 1 and Class 2 wetlands as defined by  
30 the Vermont Department of Environmental Conservation (DEC). These lands  
31 may be subject to regulations administered through the Vermont Agency of  
32 Natural Resources (ANR). This area is designated as a conservation zone and  
33 all development is prohibited.  
34
- 35 **4) Shorelands District (SL) (Section 230).** This District includes all land from the  
36 mean water mark of Lake Champlain (elevation 95.50 feet) inland for a distance  
37 of five hundred (500) feet. The purpose of the Shoreland District is to preserve  
38 water quality, prevent erosion, and regulate the visual character and aesthetic  
39 setting of shorelines. Low-density residential development and carefully sited  
40 commercial uses are appropriate in the Shorelands District. Building siting  
41 should take into consideration the preservation of views and include appropriate  
42 landscaping and screening. Land development in the Shorelands District shall  
43 comply with Section 7.8 Shoreline Protection.  
44
- 45 **5) Off Islands District (OI) (Section 240).** This District includes several small  
46 islands that are only accessible by boat, including: Butler, Knight, Gull, Hen,

1 Diadama (Dameas) and Grand Ma's. In this District, environmental concerns  
2 and the availability of Town services make these areas distinct from other areas.  
3 Development review should encourage the preservation of public access from  
4 North Hero to these islands.  
5

6 **6) Flood Hazard Overlay District:** This District is established to protect the  
7 Town's flood hazard areas. The Overlay District imposes an additional layer of  
8 regulations upon the affected lands (see Article 10). Where the provisions of the  
9 underlying district differ from those in the Flood Hazard Overlay District, the more  
10 restrictive shall govern.  
11

12 **B) Official Zoning Map.** The Official Zoning Map shall consist of the poster sized  
13 Town of North Hero Zoning Map located in the Town Clerk's Office<sup>1</sup>. It shall be  
14 identified by the signatures of the Selectboard. Regardless of the existence of  
15 copies, which may be made from time to time, the signed Official Zoning Map shall  
16 be the final authority as to the zoning status of all land and water areas in the Town  
17 of North Hero. No changes of any nature shall be made to it except in conformance  
18 with the formal amendment procedures and requirements set forth in the Act,  
19 Sections 4441 and 4442. A copy of the Zoning Map is included on Page 12.  
20

21 **C) Interpretation of Boundaries (Section 260).** Where uncertainty exists with respect  
22 to the boundary of any Zoning District, the following rules shall apply:


- 23 1) Boundaries indicated as approximately following the centerlines of roads,  
24 streams, transportation and utility rights-of-way, shall be construed to follow such  
25 centerlines. The abandonment of roads and/or rights-of-way shall not affect the  
26 location of boundaries.
- 27 2) Boundaries indicated as approximately following lot lines shall be construed to  
28 follow such lot lines.
- 29 3) Boundaries indicated as following shorelines shall be construed as the normal  
30 mean water level.
- 31 4) Boundaries indicated as parallel to, or as extensions of features in (1), (2), and  
32 (3) above shall be so construed.
- 33 5) When the ZA cannot definitely determine the location of a district boundary line  
34 by the above rules or by the scale or dimensions on the Official Zoning Map, the  
35 DRB shall interpret the district boundaries.

---

<sup>1</sup> The Official Flood Hazard Overlay District Map shall consist the most current flood insurance studies and maps published by the Department of Homeland Security (DHS), Federal Emergency Management Agency (FEMA), and National Flood Insurance Program (NFIP), as provided by the Secretary of the Agency of Natural Resources pursuant to 10 V.S.A. Section 753


# ZONING MAP

## Town of North Hero



### LEGEND

- |                        |                                |
|------------------------|--------------------------------|
| <b>Zoning Features</b> | <b>Transportation Features</b> |
| Village District       | Federal Highway                |
| Shoreland District     | Road                           |
| Conservation District  | Private Road                   |
| Rural Lands District   | <b>Surface Water Features</b>  |
| Off Islands District   | Stream or Brook                |
|                        | Lake or Pond                   |
|                        | <b>Other Features</b>          |
|                        | Town Boundary                  |



Data Source: All map features derived from GIS digital coverages. With the following exception: Zoning District boundaries description from the North Hero Planning Commission.

North arrow on map refers to Grid North.

**This is not the official Zoning Map. The official signed version is on file at the town clerk's office.**

DISTRICT	ACRES
Village District	48.78
Shoreland District	2,105.29
Conservation District	1647.65
Rural Lands District	4,289.52
Off Islands District	542.95



Datum: Coordinate System  
 Transverse Mercator, NAD 83  
 For planning purposes only.  
 Prepared by:  
 Northwest Regional Planning Commission  
 155 Lake Street  
 St. Albans, VT 05478  
 802.834.8568  
 www.nwrcvt.com  
 Date: August, 2012.  
<http://gis.projects/economy/grandisland/other/grandislandzoningmap-stard>

1 **ARTICLE 4: ZONING PERMITS AND CERTIFICATES OF**  
2 **OCCUPANCY**

---

3  
4 **SECTION 4.1: ZONING PERMITS (SECTION 325)**

5  
6 **A) Applicability.** A Zoning Permit is required prior  
7 to initiating land development unless specifically  
8 exempted in (B) below.

9  
10 Land development activities that require a  
11 Zoning Permit include but are not limited to the  
12 following:

- 13 1) A new structure
- 14 2) A new or modified sign
- 15 3) Moving a structure
- 16 4) Additions or expansions to existing  
17 structures, including enclosed space, stairs,  
18 porches, ramps, decks, off-grid rooftop solar  
19 arrays, and an increase in height
- 20 5) A new land use (See Table 5.1)
- 21 6) Changing from one land use to another
- 22 7) Moving a land use to another lot

23  
24 **B) Zoning Permit Exemptions (Land**  
25 **Development that Does Not Require a**  
26 **Zoning Permit).** The following land use  
27 activities do not require a Zoning Permit:

- 28 1) Statutory exemptions listed in Section 1.4
- 29 2) Land uses classified as Exempt in Table  
30 5.1.
- 31 3) Fences 6 feet or less in height.

32  
33 **C) Zoning Permit Application Requirements.** A  
34 complete application for a Zoning Permit shall  
35 include all the applicable information requested  
36 on the North Hero Zoning Permit Application  
37 Form, including the application fee. Any owner(s)  
38 of record or a designated agent of an owner may make an application for a Zoning  
39 Permit. A person must be designated in writing to be an agent under these  
40 Regulations. Zoning Permit Applications require a processing fee, which is set by  
41 the Selectboard and recorded in the Town of North Hero Fee Schedule; fees vary by  
42 use (Section 2.2).

43  
44 **D) Zoning Permit Public Notice and Issuance Requirements.** Public notice and  
45 issuance requirements must be followed before a Zoning Permit may be issued  
46 according to Article 2.

**Figure 4.1**

**Structure:** A combination of materials to form a construction for use, occupancy, or ornamentation whether installed on, above, or below the surface of land or water. Structures include but are not limited to buildings, free-standing signs, fences, carports, porches, patios, swimming pools, off-grid freestanding solar arrays, freestanding towers, and lean-tos. Specifically not included are sidewalks, driveways, underground utilities, and softscape landscaping such as trees, plants, groundcover, and mulching.

**Land Use.** How a parcel of land, including any structures located thereon, is being used. Table 5.1 identifies different types of land uses.

1 **E) Zoning Permit Requirements.**

- 2 1) The ZA shall determine that applications comply with all applicable standards  
3 and requirements in these Regulations before issuing a Zoning Permit.  
4 2) The ZA shall refer applications to the DRB if they require one or more DRB  
5 approvals. Any required DRB approvals shall be obtained before the ZA may  
6 approve or deny a Zoning Permit Application.  
7 3) For development where a DRB permit or approval has been issued, including  
8 subdivision plat approval, no zoning permit shall be issued until documentation is  
9 provided that all applicable conditions of the prior permit or approval have been  
10 met.

11  
12 **F) Zoning Permit Effective Date.**

- 13 1) No Zoning Permit shall take effect until the time for appeal has passed. In the  
14 event that a notice of appeal is properly filed, the permit shall not take effect until  
15 adjudication of that appeal by the DRB is complete and the time for taking an  
16 appeal to the Environmental Court has passed without an appeal being taken. If  
17 an appeal is taken to the Environmental Court, the permit shall not take effect  
18 until the Environmental Court rules in accordance 10 V.S.A. Section 8504 on  
19 whether to issue a stay, or until the expiration of 15 days, whichever comes first.  
20 2) Zoning Permits have an automatic expiration of two (2) years from the date of  
21 issuance unless substantial work has been complete. Once expired, such  
22 permits may be reapplied for upon payment of the appropriate fee.  
23

24 **G) Permit Filing Requirements**

- 25 1) As a condition of every permit, the applicant is required to file all relevant State  
26 and Federal permits with the Zoning Clerk.  
27

28 **SECTION 4.2: CERTIFICATE OF OCCUPANCY AND CERTIFICATE OF**  
29 **COMPLIANCE (SECTION 328)**

30  
31 **A) Certificate of Occupancy.** A Certificate of Occupancy (CO) is required following  
32 the issuance of a Zoning Permit when construction is complete but prior to  
33 occupancy or initiation of use of any land development in accordance with this  
34 Section.  
35

- 36 1) **Certificate of Occupancy Form.** A CO form shall be supplied to applicants with  
37 the Zoning Permit or may be obtained from the North Hero Town Clerk's Office.  
38  
39 2) **Certificate of Occupancy, Minor and Major.** There are two (2) classifications  
40 of CO's - minor and major.  
41 a) The following land development shall require a minor CO:  
42 • Accessory structures  
43 • Additions or expansions to existing structures where there is no change in  
44 use.  
45 b) All land development not qualifying for a minor CO, including all principal  
46 structures, shall require a major CO.

1       **3) Minor Certificate of Occupancy Process.** Applicants shall complete a CO form  
2       and by signing the form certify that the land development has been constructed  
3       and will be used in compliance with the Zoning Permit. Following receipt of the  
4       complete and signed CO form, the ZA shall approve and record the CO.  
5

6       **4) Major Certificate of Occupancy Process.** Applicants shall complete a CO form  
7       and by signing the form certify that the land development has been constructed  
8       and will be used in compliance with the Zoning Permit.  
9

10       **a) First Site Investigation.** Upon receipt of a completed CO form, the ZA shall  
11       conduct a site investigation at the time that pins are set for the pouring of a  
12       concrete foundation or slab to confirm that all setbacks will be met. At this  
13       time, the proposed location for any decks, porches or other permitted building  
14       attachments or outbuildings should also be identified.  
15

16               For single and two family homes, the applicant may request that the ZA issue  
17               a CO following the first site visit if the project is found to be in compliance. All  
18               other land development requires a second site investigation when the project  
19               is complete.  
20

21       **b) Second Site Investigation.** For all permitted development (except for single  
22       and two family homes where exception has been granted), the ZA shall  
23       conduct a second site visit when the permitted development is complete, but  
24       prior to occupation. A complete development shall include all features  
25       permitted and conditioned by the Zoning Permit and DRB Decision. At a  
26       minimum, buildings shall have all walls and roofing in place, required  
27       landscaping shall be installed according to permit requirements and off-street  
28       parking spaces shall be identified. The only exception shall be for phased  
29       improvement plans approved by the DRB.  
30

31       **c) Issuance of a CO.** If the site inspection(s) find that no violations have  
32       occurred, the ZA shall approve and record the CO within 30 days of receipt of  
33       the completed CO form.  
34

35       **B) Certificate of Compliance.** Although not required, a Certificate of Compliance may  
36       be requested at any time to determine a property's compliance with these  
37       Regulations, such as during real estate transactions.  
38

### 39       **SECTION 4.3:       TEMPORARY USES AND STRUCTURES (SECTION 326)** 40

41       **A)** Temporary permits may be issued by the ZA for a period not exceeding one (1) year  
42       for non-conforming uses incidental to construction projects, provided such permits  
43       are conditioned upon agreement by the owner to remove the structure or use upon  
44       expiration of the one (1) year time period. Such permit may be renewed upon  
45       application for an additional period not exceeding one year.  
46

1 **SECTION 4.4: ABANDONED AND DESTROYED STRUCTURES (SECTION 330)**

- 2
- 3 A) Within two (2) years after a permanent or temporary structure has been either
- 4 destroyed, demolished, become structurally unsafe or is no longer in use, the
- 5 landowner must present to the DRB a plan for the removal of debris and material,
- 6 along with a plan for the purpose of safeguarding the area from trespass. In the
- 7 case of an expired building permit, reapplication can be made in accordance with
- 8 Section 4.1. Violations will be regulated in accordance with Section 2.6.
- 9

1 **ARTICLE 5: LAND USES, DENSITY AND SETBACK**  
 2 **STANDARDS**

---

3  
 4 **SECTION 5.1: LAND USES**

5  
 6 **A) Allowed Uses.** Allowed uses may either be Permitted (P) or Conditional (C). All  
 7 allowed uses require a Zoning Permit issued by the ZA.

8 **1) Permitted Uses.** Permitted uses (P) require a Zoning Permit from the ZA only.  
 9 No approval from the DRB is required.

10 **2) Uses Requiring DRB Approval.** Uses that require Conditional Use Review  
 11 require such approval from the DRB before the ZA may issue a Zoning Permit.  
 12 Other DRB approvals included in Article 6 may also be required. For uses  
 13 requiring multiple approvals, DRB review may be coordinated in accordance with  
 14 Section 2.4(D).

15  
 16 **B) Exempt Uses.** Uses marked with an (E) in Table 5.1 are exempt and do not require  
 17 a Zoning Permit. See also Section 1.4 (Statutory Exemptions) and Section 4.1(B)  
 18 Zoning Permit Exemptions.

19  
 20 **C) Prohibited Uses.** Uses marked with an (X) in Table 5.1 are prohibited in the  
 21 corresponding Zoning District(s).

22  
 23 **D) Uses Not Listed in Table 5.1.** Applicants may apply for Conditional Use Review  
 24 from the DRB for uses not listed in Table 5.1. The DRB shall consider whether the  
 25 proposed use is of the same general character as those allowed in the district in  
 26 which the use is proposed before considering it for approval.  
 27

**Table 5.1: Land Uses**

P (Permitted use), C (Conditional Use), X (Prohibited), E (No Zoning Permit Required)

Use	Notes	Village	Rural Lands	Shore -lands	Off Island	Conser- vation
<b>Residential Uses</b>						
Dwelling, Single Family		P	P	P	P	X
Dwelling, Two Family		P	P	P	P	X
Dwelling, Multi-Family		P	C	C	C	X
Dwelling, Agricultural (in addition to Principal Dwelling)	Section 8.3	C	C	C	C	X
Mobile Home Park	Section 8.4	C	C	C	C	X
<b>Residential Accessory Uses</b>						
Bed and Breakfast		C	C	C	C	X

**Table 5.1: Land Uses**

P (Permitted use), C (Conditional Use), X (Prohibited), E (No Zoning Permit Required)

Use	Notes	Village	Rural Lands	Shore-lands	Off Island	Conservation
Casual Sales (Garage Sale)		E	E	E	E	X
Dwelling, Accessory	Section 8.2	P	P	P	P	X
Home Business	Section 8.9	E	E	E	E	E
Home Occupation	Section 8.9	P/C	P/C	P/C	P/C	X
Family Childcare Home	Section 8.6	E/C	E/C	E/C	E/C	X
<b>Commercial Uses</b>						
Earth Resource Extraction	Section 8.5	X	C	X	X	X
Gas Station / Motor Vehicle Service Station	Section 8.7	C	C	C	X	X
Light Industry		C	C	X	X	X
Lodging Establishment		C	C	C	C	X
Marinas and Yacht Clubs	Section 8.12	C	X	C	X	X
Residential Marine Associations	Section 8.12	C	X	C	C	X
Motor Vehicle Sales or Mobile/Modular Home Sales		C	C	X	X	X
Personal and Professional Service		C	C	C	C	X
Recreational Facilities		C	C	C	C	X
Restaurant (Sit Down, Take Out, and Drive-Through)		C	C	C	C	X
Retail Sales		C	C	C	C	X
Storage Facilities		C	C	C	C	X
Youth or Club Camp		C	C	C	C	X
<b>Other Uses</b>						
Accessory Structure		P	P	P	P	X
Agriculture and Forestry	Section 1.4	E	E	E	E	X

**Table 5.1: Land Uses**

P (Permitted use), C (Conditional Use), X (Prohibited), E (No Zoning Permit Required)

Use	Notes	Village	Rural Lands	Shore-lands	Off Island	Conser- vation
Congregate Care Facility		C	C	C	X	X
Group Home	Section 8.8	E	E	E	E	X
Lake Access Structure	Section 8.10	X	X	P	P	X
Off-Grid Solar Arrays	Section 8.15	See Section 8.15				X
Place of Worship	Section 8.13	C	C	C	C	X
Public or Semi-Public Facilities	Section 8.13	C	C	C	C	X
Shoreline Stabilization Measures	Section 8.14	P	P	P	P	P
Small Off-Grid Wind Energy Generation System	Section 8.15	C	C	C	C	X
Temporary Use/Structure	Section 4.3	P	P	P	P	X
Wireless Telecommunications Facility	Section 8.17	C	C	C	C	X

**SECTION 5.2: DENSITY, SETBACK AND OTHER DIMENSIONAL STANDARDS.**

**A) Applicability.** All land development shall meet the density and dimensional standards listed in Table 5.2, except when otherwise approved by the DRB as a variance, setback waiver, or PUD.

**B) Calculating Density.** When calculating maximum density for a particular lot for the purposes of subdivision, divide the total lot size including any rights of way by the applicable minimum lot size. When a lot proposed for subdivision is made up of two or more zoning districts, the district that a majority of the lot falls within will govern the requirement for minimum lot size. Where the majority of land does not fall in any one district, the DRB will determine the district that will govern the requirement for minimum lot size.

**Table 5.2: Density,Setback and Other Dimensional Standards**

	Village, Shorelands, and Off Islands	Rural Lands	Conservation District
<b>LOT SIZE</b>			
Minimum Lot Size, Non-Residential	2 acres	3 acres	10 acres

**Table 5.2: Density, Setback and Other Dimensional Standards**

	Village, Shorelands, and Off Islands	Rural Lands	Conservation District
Minimum Lot Size, Single Family	2 acres	3 acres	NA
Minimum Lot Size, Two and Multi-Family	2 acres for the first unit plus 1 acre per each additional residential unit (i.e. 3 acres for a duplex and 4 for a tri-plex)	3 acres for the first unit plus 1.5 acres per each additional residential unit (i.e. 4.5 acres for a duplex and 6 acres for a tri-plex)	NA
<b>SETBACKS (FEET)</b>			
State Highway	125 feet (NA in Off Island)	125 feet	NA
Town Road	100 feet	100 feet	NA
Lake - Residential	75 feet	NA	NA
Lake - Commercial/Industrial	150 feet		
Lake - Other	75 feet		
Private Road & Deeded ROW	50 feet – Front 25 feet – Side & Rear	50 feet – Front 25 feet – Side & Rear	NA
Yard - Side & Rear	25 feet	25 feet	NA
Class 1 Wetland	100 feet	100 feet	100 feet
Class 2 Wetland	50 feet	50 feet	50 feet
Streams	50 feet	50 feet	50 feet
<b>HEIGHT RESTRICTIONS</b>	35 feet	35 feet	NA
<b>MAXIMUM LOT COVERAGE</b>	20%	20%	NA
<b>MINIMUM ROAD OR LAKE FRONTAGE</b>	100 feet (on lake in Shoreland and Off-Island)	100 feet	NA
<b>MINIMUM LOT WIDTH</b>	100 feet	100 feet	NA

**SECTION 5.3: USES AND STRUCTURES PER LOT (SECTION 420)**

**A) Principal and Accessory Uses Per Lot.** There shall not be more than one (1) principal use and structure per lot, unless approved as a PUD (Section 6.4) or as agricultural housing (Section 8.3). There is no limit on the number of accessory uses/structures that may be permitted per lot unless otherwise limited in these Regulations.

**Figure 5.3**

**Principal Use/Structure:** A use or structure directly involved with the primary purpose of ownership on a particular lot.

**Accessory Use/Structure:** An incidental or subordinate structure and/or use that is secondary or ancillary to the primary use of the same lot. Accessory structures include garages, sheds, barns, pump houses, and other out buildings, antennae, towers, swimming pools, and other structures.

1 **SECTION 5.4: FRONTAGE (SECTION 423)**

2  
3 **A) Required Frontage.** Lots shall comply with the minimum road and lake frontage  
4 dimensions in Table 5.2. Lot frontage is determined by the length of the boundary of  
5 a lot measured along the near edge of the established right-of-way of a state  
6 highway or town road or measured in a straight line at the natural bank of Lake  
7 Champlain.


8  
9 **B) Lots without Frontage.** No land development is permitted on parcels or lots that do  
10 not have any frontage on a public road or public waters, except with the approval of  
11 the DRB for an access by right-of-way. Under Conditional Use Review or  
12 Subdivision Review, the DRB may approve access to a parcel or lot without frontage  
13 on a public road or public waters by deeded right-of way at least twenty (20) feet in  
14 width (private roads may qualify). The DRB shall consider the intended use of the  
15 property, safety, traffic, road and site conditions in granting, conditioning, or denying  
16 approval. Access by right-of-way to more than 3 lots shall comply with the Town of  
17 North Hero Road Standards (See Section 7.7).

18  
19 **SECTION 5.5: SETBACKS (SECTION 500)**

20  
21 **A) Applicability.** Land development is prohibited within the applicable setbacks listed  
22 in Table 5.2, unless granted a waiver (Section 5.5(E) and Section 6.2), or if it meets  
23 one of the exceptions in (D) below.

24  
25 **B) Measuring Setbacks.** Setbacks shall be measured from the near edge of the road  
26 traveled way, from the top of the bank of Lake Champlain, from the near edge of a  
27 deeded ROW or from a property line, as applicable (See Figure 5.5).

28  
29 **Figure 5.5 Measuring Setbacks**



1 **C) Determining Front Property Line.** In the SL and OI districts, on all lots having one  
2 hundred (100.00) feet or more frontage on Lake Champlain, the front property line is  
3 deemed to be the lake front. In all other instances, the front property line is deemed  
4 to be that property line adjoining the highway, road or right-of-way used for access  
5 to the lot.  
6

7 **D) Setback Exceptions (Section 501).** The following land development is exempt  
8 from all setback requirements:

- 9 • Fences.
- 10 • Pumphouses designed for ordinary residential or seasonal camp use.

11  
12 The following land development is exempt from the lake setback provided it is not  
13 located below or beyond an elevation of 98 feet above sea level (where jurisdiction  
14 of the Army Corps of Engineers begins):

- 15 • Lake Access Structures (See Section 8.10).
- 16 • Open decks without roofs that do not project beyond the natural bank.
- 17 • Shoreline Stabilization Measures, including retaining walls and seawalls  
18 (See Section 8.14).
- 19 • Certain parking and storage areas permitted as part of a Marina or Yacht  
20 Club under Section 8.12.

21  
22 **E) Administrative Waiver for Pre-Existing Non-Conforming Lots (See also Article**  
23 **9 regulating nonconformities).** For pre-existing non-conforming lots with not more  
24 than one dwelling unit (and no accessory dwelling unit), the ZA may grant a 10'  
25 minimum setback for not more than one accessory structure when all of the  
26 following can be satisfied:

- 27 1) The setback is from side and/or rear property lines only
- 28 2) The proposed structure is less than or equal to 150 square feet with one side of  
29 the structure measuring at least 8 feet.
- 30 3) The ZA conducts a site visit.
- 31 4) No other variance or waiver is required.

## 32 **SECTION 5.6: HEIGHT (SECTION 422)**


33  
34  
35 **A) Applicability.** No building or structure shall exceed 35.0 feet in height above  
36 average finished grade, except as provided below.

- 37  
38 **1) Measuring Height.** Height of structures shall be measured from average  
39 finished grade to the ridgeline or deckline of the roof, whichever is higher (Figure  
40 5.6).  
41

1 **2) Exceptions to 35 Foot Height Maximum.**

- 2 a) Ornamental, symbolic, and other rooftop  
3 features of buildings and structures,  
4 including but not limited to spires,  
5 cupolas, belfries, domes, cooling towers,  
6 and rooftop solar arrays, are exempt from  
7 the 35 foot height maximum provided  
8 they are not used for human occupancy  
9 or commercial advertisement and do not  
10 exceed 45.0 feet in height above average  
11 finished grade.  
12 b) Small Off-Grid Wind Energy Generation  
13 Systems and Wireless  
14 Telecommunications Facilities are  
15 exempt from this Section; however, shall  
16 comply with the height restrictions in  
17 Section 8.15 and 8.17 respectively.  
18 c) Under Conditional Use Review, the DRB  
19 may approve heights greater than 35  
20 feet.  
21

**Figure 5.6**



22 **SECTION 5.7: LOT COVERAGE (SECTION 413)**

23  
24 In all Zoning Districts except the Conservation District, the maximum area on a lot  
25 permitted to be covered by buildings and other structures is twenty (20) percent of the  
26 lot area. All buildings and structures must be included in determining the percentage of  
27 Lot Coverage. Pavement and other surfaces not included in the definition of building  
28 and structure do not count.  
29

1 **ARTICLE 6: DRB APPROVALS**

---

2  
3 **SECTION 6.1: CONDITIONAL USE REVIEW (SECTION 327)**

4  
5 **A) Applicability:** The following uses require Conditional Use Review from the DRB:

- 6 1) Uses listed in Table 5.1 as conditional (C), including new uses, changing an  
7 existing use to a different use, and expanding or modifying an existing use so  
8 that is no longer conforms to its existing conditional use approval.  
9 2) Uses not listed in Table 5.1.  
10 3) Nonconformities (in some cases, see Section 9.2).  
11 4) Structures with a height greater than 35 feet (Section 5.6).  
12 5) Access by right-of-way to lots without frontage (Section 5.4).  
13

14 **B) Purpose:** Conditional Use Review requires compliance with standards addressing  
15 the impact of proposed land uses on adjacent properties, the neighborhood or  
16 district in which the project is located, and the community at large. Conditional Use  
17 Review also requires that building and site design is consistent with the purpose and  
18 character of the district within which it is located. Standards and conditions  
19 emphasize considerations to identify, avoid, and/or mitigate off-site impacts of a  
20 proposed project, in addition to those considerations related to internal layout of the  
21 site, its physical design and appearance as viewed from off-site, and the functional  
22 integration of the site with surrounding properties and uses.  
23

24 **C) Application/Site Plan Requirements:** A complete application for Conditional Use  
25 Review shall include:

- 26 1) All the information requested on the North Hero Application to the DRB,  
27 including a description of all existing and proposed activities that will take place  
28 on the property both inside and outside of structures and the hours of operation  
29 for commercial and industrial operations;  
30 2) the application fee; and  
31 3) two copies of a site plan, which shall be prepared in a clear and legible manner  
32 and include the following information:  
33 a) Names and addresses of the owner(s) and/or his agent.  
34 b) Names of the owners of contiguous properties. For these Regulations  
35 contiguous property means property adjacent to any and all sides of the  
36 specified property to include property separated by roads or deeded rights  
37 of way.  
38 c) Date, north arrow and scale (numeric and graphic).  
39 d) Property lines, with rough dimensions, and the area of the subject parcel.  
40 e) Proposed name or identifying title of parcel(s) and name of the Town.  
41 f) Significant features such as the location of wetlands, streams, etc.  
42 g) Existing and proposed structures (indicating type), public roads, deeded  
43 rights-of-way, wells, septic systems, etc. and their size, type and location  
44 relative to the property lines.  
45 h) Vicinity map, which is a map inset that shows the location of the subject  
46 property on the island.

- 1 i) Parking and circulation, including access to roads.
- 2 j) Designated on-site vehicular and pedestrian circulation with adequate
- 3 access provided for all site amenities.
- 4 k) The location of all exterior storage areas for material, machinery, and/or
- 5 vehicles.
- 6 l) The location, dimensions and detail of signage, displays and
- 7 advertisements.
- 8 m) Any fuel or hazardous waste storage areas.
- 9

10 **D) Review Procedure:** The DRB shall issue a written decision following a duly noticed  
11 public hearing according to Section 2.4.

12  
13 **E) Review Standards:**

- 14
- 15 1) The DRB shall find that the proposed development will not result in an undue
- 16 adverse effect on any of the following:
- 17
- 18 **a) The capacity of existing or planned community facilities.** The DRB shall
- 19 consider the demand for community services and facilities resulting from the
- 20 proposed development, and determine whether that demand will exceed the
- 21 existing or planned capacity of existing facilities or services. In making such
- 22 a determination, the DRB will consider any capital program or budget in effect
- 23 at the time of application.
- 24
- 25 **b) The character of the neighborhood area, or district affected.** The DRB
- 26 shall consider the location, scale, type, density, and intensity of the proposed
- 27 development in relation to the character of the area likely to be affected by the
- 28 proposed development, as defined by the purpose(s) of the zoning district(s)
- 29 within which the project is located (See Section 3.1) and specifically stated
- 30 polices and standards of the North Hero Town Plan.
- 31
- 32 **c) Traffic on roads and highways in the vicinity.** The DRB shall consider the
- 33 projected impact of traffic resulting from the proposed development on the
- 34 capacity, safety, efficiency and use of affected roads, bridges, and
- 35 intersections. A traffic impact study may be required.
- 36
- 37 **d) Other Town bylaws in effect.** The DRB shall consider whether the
- 38 proposed development complies with all municipal bylaws and ordinances in
- 39 effect at the time of application, including conformance with applicable
- 40 Development Standards and Specific Use Standards in Article 7 and 8 of
- 41 these Regulations. No development shall be approved in violation of existing
- 42 municipal bylaws and ordinances.
- 43
- 44 **e) The utilization of renewable energy resources.** The DRB shall consider
- 45 whether the proposed development will interfere with the sustainable use of
- 46 renewable energy resources, including the existing and future availability of
- 47 and access to such resources on adjoining properties.

1 2) The DRB may impose appropriate conditions and safeguards with respect to:

2  
3 a) **Maximum safety of vehicular and pedestrian circulation between the site**  
4 **and the street network.** The DRB shall consider the safety of vehicular and  
5 pedestrian circulation between the site and the street network. Particular  
6 attention shall be given to visibility at intersections, to traffic flow and control,  
7 to pedestrian safety and convenience, and to access in case of emergency.

8  
9 b) **Adequacy of circulation, parking, and loading facilities.** The DRB shall  
10 consider the adequacy of circulation, parking and loading facilities, including  
11 compliance with Section 7.5. Particular consideration shall be given to the  
12 effect of noise, glare or odors on adjoining properties and state and town  
13 highways. Adequacy of provisions for erosion control, runoff, refuse removal,  
14 service areas, and snow removal shall be considered.

15  
16 c) **Adequacy of landscaping and screening according to Section 7.3.** The  
17 DRB shall consider the adequacy of landscaping and screening on the site.  
18 Exterior storage of material shall be designated to a specific area and  
19 adequately screened from view from adjacent properties, roads and the Lake  
20 and is prohibited in setback areas.

21  
22 d) **Adequacy of waste management plan.** The DRB shall consider the  
23 adequacy of the plan for managing and disposing of trash, fuel and oil,  
24 cleaning materials, paint and other refuse.

25  
26 e) **Conformance with applicable Development Standards and Specific Use**  
27 **Standards in Article 7 and 8.**

28  
29 **F) Conditions.** The DRB shall have the power to impose reasonable conditions and  
30 safeguards to ensure compliance with the standards above, including but not limited  
31 to, the following conditions:

32  
33 1) The DRB may require project phasing or improvements necessary to  
34 accommodate the proposed development to ensure that the demand for facilities  
35 or services does not exceed existing or planned capacity.

36 2) The DRB may limit the scale or dimensions of the proposal.

37 3) The DRB may increase setback distances for non-residential uses which are  
38 contiguous to residential uses, recreation uses, or natural areas.

39 4) The DRB may require landscaping and screening as appropriate to ensure the  
40 development fits in with its surroundings.

41 5) The DRB may limit the hours of operation.

42 6) The DRB may limit outdoor storage of materials, goods, and equipment.

43 7) The DRB may require that outdoor storage of or work associated with goods,  
44 parts, supplies, vehicles or machinery is inside a building or behind screening.

45 8) The DRB may attach conditions with regard to size and location of parking areas,  
46 landscaping, and signs.

47 9) The DRB may require roadway improvements on-site or off-site, if deemed

1 necessary, to accommodate the increased traffic associated with the  
2 development. Improvements may also include traffic calming, sidewalks,  
3 crosswalks and other similar improvements.

4 10) The DRB may limit the location of buildings, structures and landscaping to  
5 protect visual and physical lake access for neighbors.  
6

## 7 **SECTION 6.2: SETBACK WAIVER**

8  
9 **A) Purpose and Applicability:** A Setback Waiver is an approved reduction to the  
10 minimum setback distance required for a particular structure according to Table 5.2.  
11 To preserve and continue existing development patterns, the DRB may waive the  
12 setback according to the following provisions:  
13

- 14 1) Where existing structures within 200.00 feet of the proposed structure do not  
15 meet minimum road setback standards, the DRB may approve a reduction to the  
16 state, town, private road, or lake setback for not more than one (1) primary or  
17 accessory structure (on conforming and non-conforming lots). See also Article 9  
18 regulating nonconformities.
- 19 2) For structures on non-conforming lots, the DRB may approve a reduction to yard  
20 setbacks. See also Article 9 regulating nonconformities.
- 21 3) For handicap accessibility ramps, the DRB may approve a reduction to any  
22 setback.
- 23 4) Lots with more than one dwelling unit, including accessory dwelling units, are not  
24 eligible for a setback waiver.  
25

26 **B) Application Requirements:** A complete application for a Setback Waiver shall  
27 include all the information requested on the North Hero Application to the DRB, and  
28 if applicable to the requested waiver a detailed drawing of all structures within two  
29 hundred (200.00) feet of the proposed structure including those on adjacent  
30 properties.  
31

32 **C) Review Procedure:** The DRB shall issue a written decision following a duly noticed  
33 public hearing according to Section 2.4.  
34

35 **D) Review Standards:** The DRB may approve a setback waiver in accordance with  
36 the standards below.

- 37 1) The DRB shall not approve a waiver that that would have an undue adverse  
38 effect on adjacent property, the character of the area or on public health and  
39 safety
- 40 2) In the issuance of waivers the DRB:
  - 41 a) Shall consider and may require design features, screening, or some other  
42 remedy in order to mitigate anticipated impacts of any such waiver. The  
43 design feature shall provide adequate privacy to the surrounding use(s).  
44 Examples include fences, densely planted landscaping such as a hedge, or  
45 other natural and/or man-made landforms.

- 1 b) May require that all outdoor storage of materials and equipment, including  
2 waste storage facilities, not be stored or located within the reduced setback  
3 area.  
4 c) Shall provide only the minimum waiver that will represent the least deviation  
5 possible from the bylaw.  
6 3) In the issuance of waivers for setbacks to state, town, or private roads, or the  
7 lake, the DRB shall not approve a setback less than the average of like structures  
8 (principal or accessory) within 200 feet of the proposed structure. If there is only  
9 one like structure, the average shall be calculated with the one like structure and  
10 the minimum setback requirement for the District. In no case shall a setback to a  
11 State, Town or private road be less than 25 feet from the center line of the Right  
12 of Way.  
13 4) Any waiver approved by the DRB shall be considered the minimum setback for  
14 that structure and it shall be considered conforming with respect to that setback  
15 distance.  
16

### 17 SECTION 6.3: VARIANCES (SECTION 329)

18

19 **A) Applicability.** Requests for variances from the provisions of these Regulations may  
20 be submitted for structures (but not for uses) and shall be regulated as prescribed in  
21 Section 4469 of the Act.  
22

23 **B) Application Requirements.** A complete application for a variance shall include all  
24 the information requested on the North Hero Application to the DRB, including the  
25 application fee. The application shall also include a written description of how the  
26 proposal meets the requirements of Section 6.3(D) below.  
27

28 **C) Review Procedure:** The DRB shall issue a written decision following a duly noticed  
29 public hearing according to Section 2.4.  
30

31 **D) Review Standards.** The DRB may grant a variance and render a decision in favor  
32 of the applicant only if all the five (5) facts listed below are found, and the findings  
33 are specified in its written decision. In addition to the five (5) facts listed below,  
34 variances for structures in the Flood Hazard Area Overlay District shall conform to  
35 Article 10.  
36

- 37 • That there are unique physical circumstances or conditions, including irregularity,  
38 narrowness, or shallowness of lot size or shape, or exceptional topographical or  
39 other physical conditions peculiar to the particular property, and that  
40 unnecessary hardship is due to such conditions and not the circumstances or  
41 conditions generally created by the provisions of the zoning regulation in the  
42 neighborhood or district in which the property is located.
- 43 • That because of such physical circumstances or conditions, there is no  
44 possibility that the property can be developed in strict conformity with the  
45 provisions of these Regulations and that the authorization of a variance is  
46 therefore necessary to enable the reasonable use of the property.

- 1 • That the unnecessary hardship has not been created by the applicant.
  - 2 • That the variance, if authorized, will not alter the essential character of the
  - 3 neighborhood or district in which the property is located, substantially or
  - 4 permanently impair the appropriate use or development of adjacent property,
  - 5 reduce access to renewable energy resources, nor be detrimental to the public
  - 6 welfare.
  - 7 • That the variance, if authorized, will represent the minimum variance that will
  - 8 afford relief and will represent the least deviation possible from zoning regulation
  - 9 and from the plan.
- 10
  - 11 1) In making a decision in favor of the applicant for a variance, the DRB may attach
  - 12 conditions which are necessary to comply with the Act and/or the Town Plan.
  - 13
  - 14 2) On a request for a variance for a structure which is primarily a renewable energy
  - 15 resource structure, the DRB may grant the variance only if it finds that all of the
  - 16 facts listed in 24 V.S.A. §4469(b) are found in the affirmative.
  - 17

18 **SECTION 6.4: PLANNED UNIT DEVELOPMENT (PUD) (SECTION 352)**

19

20 **A) Purpose.** In accordance with Section 4417 of the Act, Planned Unit Developments

21 (PUDs) are permitted in order to achieve the following purposes:

- 22 1) Compact, pedestrian-oriented, mixed-use development;
- 23 2) Affordable housing;
- 24 3) Open space preservation and project compatibility with surrounding rural lands
- 25 4) Flexibility in lot layout and site design;
- 26 5) The efficient use of public facilities and infrastructure; and
- 27 6) Energy-efficient forms of development.

28

29 **B) Applicability.** The ZA shall evaluate all proposals for PUDs to determine whether

30 the project qualifies to be considered as a PUD as outlined below.

- 31 1) To qualify as a PUD, a project shall:
  - 32 a) Be located in the Rural Lands or Village Districts;
  - 33 b) Contain at least 4.0 contiguous acres; and
  - 34 c) Further at least two of the purposes of a PUD identified above.
- 35
- 36 2) PUDs may:
  - 37 a) Involve the creation of separate building lots or may include a development in
  - 38 which multiple principal structures and uses are constructed on an existing
  - 39 parcel or parcels.
  - 40 b) Involve one parcel or multiple adjacent parcels as a single PUD project.

41

42 **C) Review Procedure.** An application for PUD approval shall be reviewed according to

43 the Subdivision Review process in Section 6.5. For PUDs that include one or more

44 uses requiring Conditional Use Review, such approval(s) shall also be required for

45 the specific uses. These approvals shall be coordinated with PUD review to the

46 extent practical.

- 1 **D) Application Requirements.** In addition to application requirements for subdivision  
2 review, applications for PUDs must include the following:  
3 1) A brief summary of the project that explains how it meets the purposes of a PUD  
4 as identified in 6.4(A) above.  
5 2) Any request for flexibility in the application of the dimensional standards in Table  
6 5.2 of these Regulations and any request for a density bonus according to  
7 Section 6.4(G) below.

8  
9 **E) General Standards.**

- 10  
11 1) **Dimensional Standards.** To further the goals of PUDs, applicants may request  
12 reduced minimum lot area and setback distances from those prescribed in Table  
13 5.2 of these Regulations. The DRB shall set minimum lot area and setback  
14 distances appropriate to the project in the written decision. The DRB shall take  
15 into consideration the purpose of the Zoning District, the goals of PUDs,  
16 compatibility of adjacent uses, traffic, and other conditional use and site plan  
17 standards in setting minimum lot area and setback distances.  
18  
19 2) **Perimeter Setback.** The minimum setback requirements for the District in which  
20 the project is located shall apply to the perimeter of the project under review.  
21  
22 3) **Allowed Uses.** The uses allowed in a PUD shall be governed by the standards  
23 of Section 5.1.  
24  
25 4) **Mixed Uses; More than 1 Principal Use per Lot.** PUDs may involve multiple  
26 types of uses. The DRB may approve more than one principal use per lot (within  
27 separate structures or shared structures). Mixed uses shall be arranged to be  
28 compatible, and to minimize visual and noise impact for the residents of the  
29 development and adjacent properties. To achieve this, the DRB shall require  
30 landscaping, screening, and/or setbacks as appropriate.  
31  
32 5) **Clustering.** Development shall be clustered to preserve rural character and the  
33 working landscape and to further the efficient use of land.

34  
35 **F) Open Space Standards.**

- 36  
37 1) PUDs shall be designed to preserve open space for one or more of the following  
38 reasons: parks, recreation, agriculture, forestry, or scenic views. The location,  
39 size, shape, and intended use of lands set aside to be preserved for open space  
40 shall be approved by the DRB in accordance with the following:  
41 a) A minimum of 10% of total project acreage shall be open space in the Village  
42 District and a minimum of 50% of the total project acreage shall be open  
43 space in the Rural Lands District.  
44 b) Notwithstanding (a) above, the location, shape, and size of the open space  
45 shall be suitable for its context and intended use.

- c) Open space shall be configured to be contiguous with existing and/or potential open space and conform with and extend existing areas sharing similar characteristics or natural features and resources on adjacent parcels.
- d) Areas preserved for agricultural and forestry use should be of a size that retains their eligibility for available tax abatement programs.
- e) Sewage disposal areas, utility and road rights-of-way or easements, and access and parking areas shall not be counted as open space, except where the applicant can demonstrate, to the satisfaction of the DRB that they will in no way disrupt or detract from the intended use for which the open space is to be protected.

2) Open space shall be protected for its intended use by one of the following means:

- a) An easement granted to a third party for an appropriate open space use.
- b) The open space may be held in common by a homeowners association and protected from further development by condition of DRB approval and by condition of any homeowner's association covenant.
- c) The open space may be held by a single owner and protected from further development by condition of DRB approval and deed restriction.
- d) The open space may be conveyed in fee simple to one of the following as approved by the DRB:
  - i) the Town of North Hero, if it agrees; or
  - ii) a non-profit organization whose mission includes the protection of natural resources and/or public recreation.
- e) The open space may be held in single ownership and the DRB may condition that it be made available, by deed, for public or common use in order to further one or more purposes of a PUD.
- f) The open space may be protected by other similarly effective means acceptable to the DRB.

**G) Density Bonus.**

- 1) The DRB may grant a density bonus according to the criteria below. The density bonus shall be applied to the density calculated according to Section 5.2.
  - a) In the Village District, the DRB may grant a five percent (5%) density bonus for each of the criteria listed below which is met by the proposed project:
    - i) The project incorporates re-use of existing historic structures.
    - ii) The project incorporates commercial and residential uses.
    - iii) The project incorporates walking trails or parks (for use by the public or by residents/occupants of the project only).
    - iii) The project incorporates pedestrian or recreation infrastructure, such as playground equipment, benches or picnic tables, BB-Q areas, gazebos or pavilions, playing fields, tennis courts, or other sports amenities, which is made available to the public or to residents/occupants of the project only.
    - iv) The project incorporates vehicular connectivity by making all proposed streets connect to the streets of adjacent developments to form a network.
    - v) The project incorporates pedestrian connectivity by making proposed trails

- and sidewalks connect to existing systems.
- vi) The project provides land and/or infrastructure for public use without fee.
  - vii) The project has one or more Leadership in Energy and Environmental Design (LEED) certified components (certified by the US Green Building Council).
  - viii) The project is designed to meet the needs of elderly or handicapped individuals or families whose income is less than the median income of Grand Isle County.
  - ix) At least twenty (20) percent of housing units or a minimum of five units, whichever is greater, are affordable housing units. Affordable units shall be subject to covenants or restrictions that preserve their affordability for a minimum of 15 years. Affordable housing is defined in the Act.
- b) In the Rural Lands District, the DRB may grant a two percent (2%) density bonus for each of the criteria listed below which is met by the proposed project:
- i) The project incorporates walking trails or parks (for use by the public or by residents/occupants of the project only).
  - ii) The project incorporates vehicular connectivity by making all proposed streets connect to the streets of adjacent developments to form a network with no dead-end roads.
  - iii) The project incorporates re-use of existing historic structures.
  - iv) The project has one or more Leadership in Energy and Environmental Design (LEED) certified components (certified by the US Green Building Council).
  - v) At least twenty (20) percent of housing units or a minimum of five units, whichever is greater, are affordable housing units. Affordable units shall be subject to covenants or restrictions that preserve their affordability for a minimum of 15 years. Affordable housing is defined in the Act.

## SECTION 6.5: SUBDIVISION (SECTION 340)

**A) Purpose.** The purpose of these subdivision regulations is:

- 1) to guide community settlement patterns based on the vision of the Town Plan;
- 2) to ensure the efficient extension of services, utilities, and facilities as land is developed;
- 3) to ensure that any required public improvements meeting specified standards be made by the developer of the subdivision;
- 4) to create lots that meet minimum size requirements, are not irregularly shaped, and have adequate access; and

**Figure 6.5(a)**

**Subdivision:** The division of a lot or parcel of land into two or more lots or other divisions of land for sale, development or lease.

1 5) to ensure that lots are mapped and tied to surveying reference points so they can  
2 be easily recorded by the Town.

3 **Figure 6.5(b)**

4 **B) Applicability.** Pursuant to the Act, all  
5 subdivisions of land and boundary  
6 adjustments within the Town of North  
7 Hero require Subdivision Approval  
8 according to this Article.

9  
10 **C) Subdivision Classification.** For the  
11 purposes of these regulations,  
12 subdivisions shall be classified by the  
13 ZA as minor subdivisions or major  
14 subdivisions in accordance with the  
15 following:

- 16 1) Minor Subdivisions shall include:
- 17 • Any subdivision containing not  
18 more than three (3) lots and  
19 that does not require any new  
20 public or private road, road  
21 extension, or extension of  
22 municipal facilities;
  - 23 • Boundary lot adjustments;
  - 24 • Amendments to an approved  
25 minor subdivision; or
  - 26 • Amendments to an approved  
27 major subdivision plan that will  
28 not substantially change the  
29 nature of any previous  
30 subdivision or conditions of  
31 approval.

- 32  
33 2) Major subdivisions shall include  
34 subdivisions that do not meet the  
35 minor subdivision criteria in  
36 6.5(C)(1) above, in addition to:
- 37 • Planned unit developments;
  - 38 • Subdivisions involving more  
39 than one Zoning District; and
  - 40 • Subdivisions that create a new  
41 lot without frontage on a public  
42 road or waters (access by right-  
43 of-way must be approved  
44 according to Section 5.4).

45  
46 **D) Review Process.** There are three (3)

**Plan and Survey Plat Specifications**

**Sketch Plans.** An informal sketch of the proposed subdivision, the purpose of which is to enable the subdivider to save time and expense in reaching general agreement with the DRB on the design of the subdivision and objectives and requirements of these regulations. Sketch plans shall include basic information as required in Table 6.5 and may be hand drawn.

**Size and number of copies:** No size requirement. One original copy is required, the ZA may require additional copies.

**Subdivision Site Plans.** A Subdivision Site Plan is a detailed illustration of the proposed subdivision, which may be one sheet or many sheets as necessary to make the information clear and legible. Subdivision Site Plans shall be drawn to scale and include detailed information as required in Table 6.5.

**Size and number of copies:** One original 18 inches by 24 inches or larger, additional copies may be required and may be reduced as specified by the DRB during Sketch Plan Review, or by the ZA.

**Survey Plat.** A map surveyed to scale on Mylar by a licensed land surveyor for filing in the Town's land records. It shall clearly depict one or more parcels, tracts or subdivisions of land, showing, but not limited to, boundaries, corners, markers, monuments, easements and other rights. Survey Plats shall be prepared according to Section 6.5(l) and 27 V.S.A. Section 17.

1 levels of subdivision review:

- 2 • Sketch Plan Review,
- 3 • Preliminary Plan Review, and
- 4 • Final Plan Review.

5  
6 **1) Minor Subdivisions** may elect to undergo Sketch Plan Review. Minor  
7 Subdivisions are exempt from Preliminary Plan Review and shall require Final  
8 Plan Review only.

9  
10 **2) Major Subdivisions** require Sketch Plan Review, Preliminary Plan Review and  
11 Final Plan Review. However, the DRB may waive Preliminary Plan Review at  
12 Sketch Plan Review.

13  
14 **3) Site Visit.** The DRB may request a site visit before or during the Sketch Plan  
15 Review public hearing, the Preliminary Plan Review public hearing, or the Final  
16 Plan Review public hearing. The applicant will be asked to mark significant  
17 aspects of the proposal for DRB observation. The public will be invited to attend,  
18 but no testimony or evidence may be given at the site visit.

19  
20 **4) Number of Reviews.**

21 a) Additional Sketch Plan Review meetings will be permitted at the mutual  
22 discretion of the DRB and applicant. This is to ensure the most complete and  
23 efficient review of projects, to save resources for both the applicant and the  
24 Town, and to provide public and municipal input at the earliest stages of  
25 project development.

26 b) At the discretion of the DRB, Preliminary Plan and Final Plan Public Hearings  
27 may be continued to another date and time certain announced during the  
28 public hearing by the DRB.

29  
30 **E) Application Requirements.** For all subdivisions (including boundary adjustments),  
31 one original set of application materials is required for submission under this  
32 Section. The DRB may request additional copies. A set of application materials  
33 includes:

34 a) A completed Application to the DRB,

35 b) The application fee according to the fee schedule adopted by the North Hero  
36 Selectboard,

37 c) A set of site plans that include all the information required in Table 6.5,

38 d) Abutting property owner information, and

39 e) Any additional materials that may be required according to Table 6.5 or by the  
40 DRB.

41  
42 **1) Application Material Waivers.** The DRB may waive or vary application  
43 submission requirements it judges are not requisite in the interest of the public  
44 health, safety, and general welfare, or which are inappropriate both in the short  
45 and long term. No such waiver shall be granted if it would have the effect of  
46 nullifying the intent and purpose of the North Hero Town Plan or these

1  
2

Regulations.

**Table 6.5: Subdivision Sketch Plan/Site Plan Requirements**

✓: Required NA: Not Required	Sketch Plan Review	Preliminary Plan Review	Final Plan Review
<i>Note: Information required in this Table may be prepared on 1 or more sheets, as necessary to make the information clear and legible.</i>			
<b>Required Form (See Figure 6.5(b))</b>	Sketch Plan	Site Plan	Survey Plat
<b>Location Map</b> showing the project location in the context of the whole town	✓	✓	✓
<b>Title Block</b> including the following information:	✓	✓	✓
Project Title	✓	✓	✓
Plan Title (Overall site plan, utilities, stormwater, etc)	✓	✓	✓
Location Description	✓	✓	✓
Site Address	✓	✓	✓
Name of Landowner	✓	✓	✓
Name of Developer/Client (If different than landowner)	✓	✓	✓
Scale	✓ Approximate	✓	✓
Name, Title, License Number, and Stamp of Surveyor, VT Licensed Engineer, Architect, or Landscape Architect who prepared the plan (if applicable)	NA	✓	✓
<b>North Arrow</b>	✓	✓	✓
<b>Date of preparation and record of any revisions</b>	✓	✓	✓
<b>Relevant Planning and Zoning Information</b> , including zoning district, density analysis (how many lots/units allowed according to zoning standards), setbacks, parking standards, etc.	✓	✓	✓
<b>Area of land</b> in square feet or acres for each tract, lot, structure, and large feature.	✓ Approximate	✓	✓
<b>Contour lines</b> at intervals of 5 feet (unless waived or modified by DRB)	NA	✓	✓
<b>Lot and tract identification</b> boundaries for entire tract, lot lines for each existing and proposed lot, and for any involved land (access roads, easements, rights-of-way, and any open space or mitigation land). Existing and proposed lots should be differentiated. Each lot should be given a number for reference.	✓ Approximate	✓	✓
<b>Property Boundary Survey Signed and Stamped by Licensed Land Surveyor:</b> Property boundary surveys are required for all new subdivided lots. Property boundary surveys are required for the entire parent parcel (original lot from which lots are subdivided) when: -it is 10 acres or less in size, and/or -greater than 50% is subdivided into lots	NA	NA	✓

**Table 6.5: Subdivision Sketch Plan/Site Plan Requirements**

✓: Required NA: Not Required	Sketch Plan Review	Preliminary Plan Review	Final Plan Review
<i>Note: Information required in this Table may be prepared on 1 or more sheets, as necessary to make the information clear and legible.</i>			
<b>Adjacent property and owners:</b> all adjacent lands should be labeled with the name of the property owner(s).	✓	✓	✓
<b>Existing features (i.e. non-portable features of the landscape):</b> Streams, ponds, and wetlands; structures, foundations, and old cellar holes; wells, springs, and septic systems; stone walls and fence lines; forest boundaries, fields, large trees, and rock outcroppings; transportation and utility infrastructure like roads, sidewalks, and power lines; and any other existing features. <b>A letter from the Vermont Department of Environmental Conservation Wetlands Section on whether any wetlands exist on the property shall be submitted.</b>	✓ Approximate	✓	✓
<b>The proposed project (i.e. all improvements planned for one or more related sites and which fall under the purview of these Regulations):</b> All proposed buildings, roads, driveways and parking areas, landscaping, utilities, signs, dumpsters, tanks, lights, water supplies, and septic systems.	✓ Approximate	✓	✓
<b>Mitigation measures:</b> Any stream or wetland buffers, or agricultural or wildlife habitat easements, or other areas required to be set aside for preservation/conservation.	✓ Approximate	✓	✓
<b>Off-site Improvements</b> that may be required locally or by the state, such as improvements that mitigate traffic impacts like a turning lane, or construction, buffers, landscaping or other mitigation within an adjacent easement or leased area.	✓ Approximate	✓	✓
<b>Building envelopes, reserve areas, and open space.</b> "Building envelopes" delineate the general area development is proposed. "Reserve areas" are those set aside for future development or expansion. "Open space" is any area set aside to satisfy the open space requirement for PUD approval.	✓ Approximate	✓	✓
<b>Public rights-of-way and easements</b>	✓ Approximate	✓	✓
<b>Specialized Plans</b>			
<b>Utility Plan:</b> Location of water and sewer improvements and easements, including force-mains, pump stations, and underground electric and telephone lines.	NA	✓	✓
<b>Grading and Erosion Control Plan:</b> Locations where sediment must be trapped before entering a watercourse and the devices used to impede erosion (i.e. silt fencing, hay-bale or stone dams around catch basins and at intervals in swales and ditches).	NA	✓	✓
<b>Stormwater Management Plan:</b> Detail on collection, retention, and treatment of stormwater. Should show site grades, direction of drainage flow, and design of any detention basins.	NA	✓	✓
<b>Road and Bike/Pedestrian Plan:</b> Current and proposed grades for the installation of roads, driveways, sidewalks, bike lanes, and other pedestrian amenities. Should show cross sections of	NA	✓	✓

**Table 6.5: Subdivision Sketch Plan/Site Plan Requirements**

	Sketch Plan Review	Preliminary Plan Review	Final Plan Review
<p>✓: Required NA: Not Required</p> <p><i>Note: Information required in this Table may be prepared on 1 or more sheets, as necessary to make the information clear and legible.</i></p>			
<p>proposed roads and sidewalks.</p> <p><b>Landscaping Plan:</b> Locations for existing and proposed vegetation, as well as structures, features, and other topographical information. Scientific and common names for proposed species should be identified. Areas proposed for clearing and no-cut zones should be identified.</p>	NA	✓	✓
<p><b>Lighting and Signage Plan:</b> Locations and illumination of exterior lights. Location and dimensions of all exterior signs.</p>	NA	As Required	As Required
<p><b>Garbage Collection Plan:</b> Location for garbage collection and method for containing garbage put out for pick-up.</p>	NA	As Required	As Required
<p><b>Transportation Impact Study:</b> A report analyzing anticipated roadway conditions with and without the proposed project. The report may include an analysis of mitigation measures and a calculation of fair share financial contributions.</p>	NA	As Required	As Required
<p><b>Master Plan:</b> An indication of proposed roads, driveways or streets, the future probable lot lines and building envelopes of the remaining portion of the tract, and a description of the probable uses (drawn in sketch plan format).</p>	NA	As Required	As Required
<p><b>Legal Documents:</b> A draft of all newly created or revised deeds, covenants, or other legal documents associated with the proposed development.</p>	NA	As Required	✓

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22

**F) Sketch Plan Review.** All major subdivisions require Sketch Plan Review. Minor subdivisions may elect to undergo Sketch Plan Review. Sketch Plan Review is completed by the DRB according to this Section.

**1) Public Hearing.** A public hearing shall be held by the DRB at the earliest available regular or special meeting after a complete application for sketch plan review is submitted to the ZA. The hearing shall be warned according to Section 2.4

The subdivider, or duly authorized representative, shall attend the public hearing to discuss the requirements of these Regulations for lot layout, building location, streets, improvements, stormwater management, fire protection, resource protection, and other aspects; as well as the availability of existing services and conformance with the planning standards of these Regulations.

**2) Action on Sketch Plan.** The DRB shall study the Sketch Plan to determine whether or not it conforms to these Regulations and any other municipal regulations in effect. Where it deems necessary, the DRB will make specific recommendations for changes in subsequent submissions. Where necessary for the protection of the public health, safety, and welfare, the DRB may require that a Minor Subdivision comply with all or some of the requirements for Major

1 Subdivisions specified in these Regulations. The minutes of the Sketch Plan  
2 meeting shall constitute record of Sketch Plan Review for each application; no  
3 formal decision is issued. Sketch Plan Review is effective for a period of 1 year.  
4

5 **G) Preliminary Plan Review.**  
6

- 7 **1) Application Process.** Within 1-year of Sketch Plan Review, applications for  
8 Preliminary Plan Review of a Major Subdivision shall be submitted to the ZA.  
9 Complete application materials shall contain those items set forth in Section  
10 6.5(E) above. The Plan shall build upon the layout approved at Sketch Plan  
11 Review plus any recommendations made by the DRB and agreed upon by the  
12 applicant. When requested in writing, the DRB may grant extensions beyond this  
13 1-year period when the project is delayed due to circumstances beyond the  
14 applicant's control. If no extension is granted, the subdivider shall be required to  
15 complete the subdivision review process again beginning with Sketch Plan  
16 Review and will be subject to any new regulations that have gone into effect.  
17
- 18 **2) Action on Preliminary Plan.** Public notice, public hearing, and decision  
19 requirements in Section 2.4 apply. The DRB shall review the subdivision for  
20 conformance with the density requirements in Article 5, the Development  
21 Standards in Article 7 and any other applicable standards in these Regulations.  
22
- 23 **3) Effect of Preliminary Plan Approval.** Approval of a Preliminary Plan does not  
24 constitute approval of the subdivision and does not guarantee approval of the  
25 Final Plan. Prior to approval of the Final Subdivision Plan, the DRB may require  
26 additional changes as a result of further study. The approval of a Preliminary  
27 Plan is effective for a period of 1 year.  
28

29 **H) Final Plan Review.**  
30

- 31 **1) Application Process.** Within 1-year of Sketch Plan Review (if applicable for  
32 minor subdivisions) or Preliminary Plan Approval (for Major Subdivisions),  
33 applications for Final Plan Review shall be submitted to the ZA. The Final Plan  
34 application materials must conform to the layout approved at Preliminary Plan  
35 Review, including any amendments required by the DRB. When requested in  
36 writing, the DRB may grant extensions beyond this 1-year period when the  
37 project is delayed due to circumstances beyond the applicant's control. If no  
38 extension is granted, the subdivider shall be required to complete the subdivision  
39 review process again beginning with Sketch Plan Review and will be subject to  
40 any new regulations that have gone into effect.  
41
- 42 **2) Action on Final Plan.** Public notice, public hearing, and decision requirements  
43 in Section 2.4 apply. The DRB shall review the subdivision for conformance with  
44 the density requirements in Article 5, the Development Standards in Article 7 and  
45 any other applicable standards in these Regulations.  
46
- 47 **3) Acceptance of Public Infrastructure.** Final approval by the DRB shall not be

1 deemed to constitute or be evidence of acceptance by the Town of any street,  
2 road, easement, utilities, park, recreational area, or open space shown on the  
3 Final Plan or Survey Plat. Such acceptance may only be accomplished by formal  
4 resolution of the Selectboard.  
5

6 **4) Other Permits and Regulations.** Approval of the Final Plan shall not exempt an  
7 applicant from compliance with all other applicable local, state, or federal  
8 regulations, standards, policies, and ordinances.  
9

10 **I) Filing of Final Survey Plat.** Upon approval of the Final Plan by the DRB, the  
11 subdivider shall prepare a Survey Plat for recording in conformance with the  
12 requirements of 27 V.S.A. Chapter 17. A Survey Plat is a map drawn to scale on  
13 Mylar by a licensed land surveyor of one or more parcels, tracts or subdivisions of  
14 land, showing, but not limited to, boundaries, corners, markers, monuments,  
15 easements and other rights. A signed certification is required from the licensed land  
16 surveyor who prepared the Survey Plat, indicating that all the permanent lot markers  
17 (pins) have been set. Survey Plats shall be prepared according to the specifications  
18 listed below. Draft paper Survey Plats may be required for approval by the DRB  
19 before preparing a Mylar copy for filing.  
20

21 **Survey Plat Specifications:**

- 22 • Mylar
- 23 • Clear and legible data and information
- 24 • 18.0 inches by 24.0 inches in size
- 25 • Stamp and signature of licensed Land Surveyor
- 26 • Margin of 2.0 inches outside of the borderlines on the left side for binding  
27 and a 1.0-inch margin outside the border along the remaining sides
- 28 • Inset locus map clearly indicating the location of the land depicted and a  
29 legend of symbols used
- 30 • Plat scale ratios sufficient to allow all pertinent survey data to be shown,  
31 and graphic scale graduated in units of measure used in the body of the  
32 plat  
33

34 The chairperson (or acting chairperson) of the DRB shall endorse the Survey Plat  
35 with the date of Final Plan Approval. Following endorsement by the chairperson of  
36 the DRB and within 180 days of the DRB's Final Approval, the subdivider shall  
37 submit the Survey Plat to the Town Clerk for filing. The Town Clerk shall endorse the  
38 Survey Plat before filing. The DRB's written decision and Final Subdivision Site  
39 Plans, which includes all permit conditions set by the DRB, shall be filed in the land  
40 records of the Town and their location must be clearly referenced on the Survey  
41 Plat.  
42

43 Final Plan Approval shall expire if the subdivider does not receive endorsement and  
44 file the Survey Plat and related documents within the 180-day period. The ZA, upon  
45 written request prior to the expiration date, shall extend the date for filing the Survey  
46 Plat by an additional 90 days if final local or state permits or approvals are still

1 pending.

2  
3 **J) Revisions.** Except as may be required in any condition of final approval, no  
4 changes, modifications, or revisions shall be made on any final Subdivision Site Plan  
5 and Survey Plat after Final Approval, unless said Final Plan and Survey Plat are first  
6 resubmitted to the DRB in accordance with these Regulations and the DRB  
7 approves the modifications. See Section 6.5(H).

8  
9 **K) Phasing.** At any point in the Subdivision Review process, the DRB may require the  
10 Plan to be divided into two or more phases to be developed at separate times. The  
11 DRB may impose specific conditions for subsequent application submissions to  
12 ensure the orderly development of the Plan and coordination with the planned and  
13 orderly growth of the Town as reflected in the Town Plan and any capital budget and  
14 program in effect.

15  
16 **L) Master Plan Review.**

- 17 a) When part of a larger parcel is proposed for development, the DRB may  
18 require a description of the potential build-out of the entire parcel and  
19 adjacent parcels (Master Plan) as part of the requirements established after  
20 Sketch Plan Review.
- 21 b) When required, the Master Plan build-out shall include an indication of  
22 proposed roads, driveways or streets, the future probable lot lines and  
23 building envelopes of the remaining portion of the parcel, and a description of  
24 the probable uses. The build-out may be drawn in a sketch plan format. The  
25 DRB may require that the build-out be submitted as part of an extended  
26 sketch plan review, or as a part of the preliminary or final plan.
- 27 c) Requirements for Master Plan review are intended to ensure the orderly  
28 development of the Town, and will be required when the DRB determines that  
29 the development currently under application may have an impact on the  
30 future development potential of the remaining parcel or adjacent parcels. It  
31 will also be required when the DRB determines that the future build-out of the  
32 applicant's holdings, combined with the current proposal may have a  
33 significant impact on the Town of North Hero.
- 34 d) Approval of an applicant's current application does not constitute approval of  
35 the Master Plan build-out.

1 **ARTICLE 7: DEVELOPMENT STANDARDS**

---

2  
3 **SECTION 7.1: APPLICATION OF STANDARDS**

4  
5 The ZA and DRB shall evaluate applications against the applicable standards below.  
6 Not all standards will apply to every application. The DRB may require modification of  
7 subdivision or site plan design, phasing, or permit conditions to avoid or mitigate any  
8 adverse impacts and to ensure conformance with these standards.  
9

10 **SECTION 7.2: FENCES (SECTION 426)**

- 11  
12 A) All fences over six (6) feet require a Zoning Permit.  
13  
14 B) No wall, fence or shrubbery shall be erected, maintained or planted on any lot in a  
15 position where it could obstruct or interfere with either traffic visibility or the vision of  
16 a motorist, cyclist or pedestrian on a highway, road or right-of-way. This restriction  
17 applies to, but is not limited to, areas on a curve or on a tangent to a curve and on a  
18 corner lot to the triangular area formed by the lot lines along the highways, roads or  
19 rights-of-way and a line connecting them at points thirty (30.00) feet from the  
20 intersection.  
21

22 **SECTION 7.3: LANDSCAPING AND SCREENING (SECTION 436)**

- 23  
24 A) **Landscaping.** The DRB may require planting and other landscaping to enhance  
25 the features and conditions unique to each site and/or to provide screening from  
26 adjacent uses in accordance with the following standards.  
27 1) Landscaping may be required in front and side yards, adjacent to parking areas,  
28 where rear yards abut residential properties or public roads, or as otherwise  
29 necessary to provide adequate landscaping, buffering and/or screening.  
30 2) The DRB may impose requirements with regard to the size, variety, number and  
31 location of trees, front yard green space, other buffer yards, and screening  
32 outside of storage areas or other unsightly areas from public streets and/or  
33 adjoining properties.  
34 3) In determining the amount of landscaping the DRB shall consider existing trees,  
35 shrubs, evergreens and other plant material to be preserved on the site.  
36 Particular consideration shall be given to preservation of existing vegetation and  
37 important features of the site, including trees and tree lines, views and vistas,  
38 fences, stone walls, and shrubs; visibility of unsightly or incompatible areas from  
39 the road and adjoining properties; and the adequacy of landscaping materials to  
40 meet seasonal conditions, soil conditions and erosion control, and light on the  
41 site.  
42 4) Native plantings are encouraged over the use of non-native plantings. Invasive  
43 species are prohibited.

Figure 7.3

**For listings of native plants reference:**

Vermont Rain Garden Plant List

(<http://www.uvm.edu/~seagrant/communications/assets/VTRainGardenManualPlantList.pdf>), OR

Elmore Roots Vermont Native Plant List

(<http://www.elmoreroots.com/guides/vermont-native-plants-list/>).

**For invasive plants reference:**

The Vermont Invasive Exotic Plant Committee's list

(<http://www.vtinvasiveplants.org/invaders.php>).

- 1  
2  
3 5) Plantings shall be installed and maintained in accordance with professional  
4 landscape practices. A three (3) year plan for all proposed landscaping, and/or  
5 bonding or other surety also may be required to ensure installation and  
6 maintenance.  
7

- 8 **B) Screened Service and Loading Areas (Section 437).** Except in conjunction with  
9 one-family and two-family dwelling units, all areas designated, used or intended to  
10 be used as service and loading areas for any building or land use must be screened  
11 from view from all adjacent residential properties. Screening must extend at least  
12 five (5.00) feet above finish grade and may be a wall, a solid fence or a fence of  
13 evergreens.  
14

15 **SECTION 7.4: OUTDOOR LIGHTING**  
16

- 17 **A) General Standards.** To allow for appropriate outdoor lighting, while minimizing its  
18 undesirable effects, the following standards apply to all outdoor lighting installations  
19 in the Town of North Hero, with the exception of temporary holiday light displays  
20 which are exempt from these requirements:

- 21 1) All outdoor lighting shall be kept to the minimum required for safety, security, and  
22 intended use, consistent with the character of the neighborhood in which it is  
23 located.  
24 2) Permanent outdoor lighting fixtures shall be designed to minimize glare, and shall  
25 not direct light upward or onto adjacent properties, roads, or public waters, or  
26 result in excessive lighting levels that are uncharacteristic of the surrounding  
27 neighborhood or area.  
28

- 29 **B) Specific Standards.** For outdoor lighting installations associated with development  
30 that is subject to subdivision or conditional use review, the DRB may also require  
31 the following and condition approval accordingly:

- 32 1) Information regarding exterior lighting fixtures, including fixture type, mounting  
33 locations and heights, illumination levels and distribution, and color, to be  
34 submitted as part of the subdivision or conditional use application under Article 6.  
35 A lighting plan, prepared by a qualified lighting expert, may be required as  
36 appropriate for projects requiring outdoor parking area, street, or security lighting.

- 2) The use of security or street lighting only if unusual or hazardous conditions require it. Security lighting, where deemed necessary by the DRB, shall be shielded and aimed so that only designated surfaces or areas are illuminated.
- 3) Street lighting shall not be provided except where it is deemed necessary by the DRB for safety or security, such as at road intersections, or pedestrian crossings or walkways.
- 4) Outdoor lighting fixtures associated with nonresidential uses, except for approved security lighting, shall be illuminated only during business hours, unless otherwise specifically approved by the DRB.

**C) Waiver.** The DRB may waive or modify the requirements of this Section if it finds that such a modification or waiver is needed for public safety, or to meet an overriding public purpose, such as the illumination of a public building or monument.

**SECTION 7.5: PARKING AREAS/LOTS (OFF ROAD PARKING) (SECTION 438)**

Off-road parking must comply with the following standards:

- A) Parking areas/lots shall be setback 25 feet from all property lines and the Lake. This standard shall not apply to parking areas for one (1) and two (2) family dwellings.
- B) Parking areas/lots must be designed so that no parking or maneuvering will be necessary on any public road or highway. Entrances and exits are to be clearly marked and comply with all public road requirements.
- C) Parking spaces must be adequately sized for their intended vehicles (approximately nine (9) feet by eighteen (18) feet for non-commercial cars and trucks and ten (10) feet by forty (40) feet for large trucks and other large vehicles).
- D) Minimum requirements for the number of spaces to be provided are provided in Table 7.5. Accessible parking spaces in compliance with the Americans with Disabilities Act shall also be provided.

One and Two Family Dwellings	2 spaces per unit
Accessory Dwellings	1 space for 600 sq. ft. apartment or less, otherwise 2 spaces
Multi-Family Dwellings	2 spaces for each of the first 2 units, 1 space per additional unit
Home Occupation	1 space plus 1 additional space for each 300 sq. ft. of office space
Lodging Establishments	1 space for each guestroom
Personal and Professional Services, Retail Sales, Gas/Service Stations	1 space for each motor vehicle used in the business plus 1 additional space for each 200 sq. ft. of floor area.
Restaurants	1 space for each 150 sq. ft. of floor area.

Marinas and yacht clubs

1 space for each mooring and/or docking berth as permitted by the State of Vermont (see also Section 8.12 for shared parking opportunities).

Other uses

As required by the DRB.

- 1  
2 E) Parking lots proposed for new developments must provide adequate landscaping  
3 and screening (in the form of plantings) from public roads and adjacent properties.  
4 For parking lots in excess of 20 spaces, landscaped areas must be integrated into  
5 the parking lot design in addition to providing screening around the edges.  
6 Residential uses are exempt from this requirement.

7  
8 **SECTION 7.6: PERFORMANCE STANDARDS FOR USES (SECTION 440).**

9  
10 The following performance standards must be met by all uses in all districts. Uses shall  
11 not under normal circumstances:

- 12  
13 A) Emit any sustained noise, odors, dust, smoke or noxious gases that endanger the  
14 health, safety or welfare of any person or that have a tendency to cause injury or  
15 damage to property, business or vegetation.  
16  
17 B) Use any lighting or signs that create a glare and could interfere with the vision of the  
18 operator of any motor vehicle or boat or that pose an annoyance to neighbors  
19 whether on adjacent property or within sight of the source.  
20  
21 C) Present a potential for explosion, fire or any other calamity or disaster. Flammable  
22 or combustible liquids or any hazardous waste shall be stored within containment  
23 structures sufficient to contain fuel spillage, be marked with HazMat signs and  
24 comply with all applicable Vermont and Federal regulations.  
25  
26 D) Discharge any harmful or hazardous wastes into any sewage disposal system or into  
27 Lake Champlain or any pond, stream, or other body of water or watercourse.  
28

29 **SECTION 7.7: ROAD, DRIVEWAYS AND ACCESS STANDARDS**

30  
31 **A) Applicability.** The following standards shall apply to all roads and driveways.

- 32  
33 **1) Driveways (private).** All accesses serving not more than three (3) lots shall be  
34 considered driveways and shall comply with the driveway standards in Sub-  
35 Section (B) below. The interest of the owner of each lot served by a common or  
36 shared driveway shall be protected by an easement recorded in the deed of each  
37 lot involved.  
38  
39 **2) Roads (public or private).** All accesses serving four (4) or more lots shall be  
40 considered roads and shall comply with the Town of North Hero Road Standards  
41 and Sub-Section (C) below. All roads shall be private unless otherwise accepted

1 as public roads by the Selectboard. The interest of the owner of each lot served  
2 by a private road shall be protected by an easement recorded in the deed of each  
3 lot involved.  
4

5 3) **Access to lots without frontage** on a public or private road may be permitted  
6 by the DRB according to Section 5.4.  
7

8 **B) Driveway Standards.** Driveways shall be setback a minimum of 25 feet from all  
9 property lines (the DRB may waive this standard for shared driveways involving  
10 adjacent properties). Driveways serving two (2) or three (3) lots shall have a  
11 minimum width of 20 feet.  
12

13 **C) Road Standards.** The standards of this section shall apply to all proposed public  
14 roads and to proposed private roads serving 4 or more lots. In addition, these  
15 standards may be applied to private roads serving three or fewer lots when the DRB  
16 determines that such standards are necessary to provide suitable access or to  
17 accommodate potential future land development.  
18

19 1) **Arrangement.** The arrangement of new roads shall connect with existing roads  
20 on adjoining parcels and allow for future continuation through adjoining properties  
21 which are not yet subdivided or developed, in order to make possible necessary  
22 fire protection, movement of traffic and construction or extension, presently or  
23 when later required, of needed utilities and public services. To allow for future  
24 continuation of roads, the DRB may require right-of-ways that extend to adjacent  
25 property lines. Where in the opinion of the DRB, topographic or other conditions  
26 make such connection or continuance undesirable or impracticable, the above  
27 conditions may be modified.  
28

29 2) **Topography.** Roads shall be logically related to the topography so as to produce  
30 usable lots, reasonable grades and safe intersections in appropriate relation to  
31 the proposed use of the land to be served by such roads.  
32

33 3) **Access Management Standards.**

- 34 1) The DRB may require measures such as speed change lanes, turning lanes,  
35 right turn only egress or other design elements necessary to provide for safe  
36 circulation on the site and adjoining roads. The DRB may require additional  
37 improvements and configuration to improve and facilitate pedestrian access  
38 and safety.  
39 2) The DRB may limit access to the property to a side street or secondary road,  
40 or previously approved access on the subject property or adjoining properties.  
41 Where traffic access is required to only a portion of the land, sharing that  
42 access with future uses for the remainder of the parcel may be required.  
43 3) The DRB shall require a common access point to serve multiple properties  
44 under single or different ownership in order to limit the number of curb cuts  
45 onto major roads and state highways. This condition may be modified where  
46 in the opinion of the DRB, topographic or other conditions make such shared  
47 access undesirable or impracticable.

1 **4) Dead Ends.** No dead end road shall be permitted without a suitable cul-de-sac at  
2 its terminus with a radius of not less than thirty-five (35) feet. Hammerhead, "T" or  
3 "Y" design configurations suitable to topography and adequate for emergency  
4 vehicles to turn around efficiently may be permitted in lieu of a cul-de-sac.  
5

6 **5) Road Intersections.**

- 7 1) No road intersection shall be within 100 feet from another road intersection  
8 unless the roads directly oppose each other.  
9 2) All road intersections shall be as nearly at right angles as possible.  
10 3) All accesses and intersections must have a safe line of sight so as to prevent  
11 the construction of blind or hidden driveways and roads.  
12 a) A vehicle operator preparing to exit should be able to see unobstructed a  
13 minimum of 550 feet in either direction when entering a 50 mph zones.  
14 The sight distance drops to 440 feet for a 40 mph zone and 330 feet for a  
15 30 mph zone. Nothing should be erected, placed, planted, or allowed to  
16 grow in a triangle of vision so as to impair the vision of the motorist.  
17 b) No access shall be constructed closer than 550 feet from a sharp curve,  
18 hill, or blind area (50 mph zone). This minimum corner distance drops to  
19 440 feet at 40 mph, and 330 feet at 30 mph.  
20

21 **6) Accessibility.** All dwellings must be accessible by emergency and service  
22 vehicles, with the exception of the outer islands. In determining accessibility, the  
23 standards of the most recently updated NFPA 1 Uniform Fire Code will be used  
24 as guidance, and local emergency service providers may be consulted for input.  
25

26 **7) Upgrading Existing Access.** Where an existing public or private road is  
27 inadequate or unsafe, the DRB may require the applicant to upgrade that access  
28 road to the extent necessary to serve additional traffic from the proposed  
29 development.  
30

31 **8) Design.** All public and private roads shall be designed in accordance with the  
32 North Hero Town Road and Bridge Standards, as most recently amended.  
33

34 **9) Curbs, Sidewalks, and Pedestrian Accesses.** Curbs and sidewalks may be  
35 required when deemed necessary by the DRB. When required, they shall be  
36 constructed to standards established by the Town. In order to facilitate  
37 pedestrian access from the roads to schools, parks, playgrounds, or other nearby  
38 roads, perpetual unobstructed easements at least twenty (20) feet in width may  
39 be required.  
40

41 **SECTION 7.8: SHORELINE PROTECTION**

42  
43 **A) Purpose.** The Shorelands District is created to protect the natural shoreline  
44 vegetation of Lake Champlain from the 95.5 water mark of Lake Champlain inland  
45 500 feet. The development standards in this Section intend to preserve water  
46 quality, prevent erosion, and regulate the appearance of shorelines.

1 **B) Applicability.** All land development in the Shorelands District shall be subject to  
2 this Section in addition to other applicable standards in these regulations.  
3

4 **C) Setback.** All land development shall be setback from the top of the natural bank of  
5 Lake Champlain a distance according to Table 5.2, except for those exceptions  
6 noted in Section 5.5.  
7

8 **D) Preservation of Natural Shoreline.**

- 9 1) For all lakefront properties, existing natural shoreline vegetation shall be  
10 incorporated into development plans. No more than 50% of existing trees with a  
11 caliper of 4 inches in diameter or more may be cut within 25 feet of the top of the  
12 natural bank of Lake Champlain. Removal of dead trees or trees of immediate  
13 threat to human safety is permitted.  
14 2) The DRB may require restoration of natural shoreline vegetation if it has been  
15 substantially damaged or is in violation of these standards.  
16

17 **SECTION 7.9: SIGNS (SECTION 430)**  
18

19 **A) Applicability.** A permit issued by the ZA shall be required prior to the erection,  
20 construction, or replacement of any outdoor sign, except as exempted in B below.  
21

22 **B) Exemptions.** The following are exempt and do not require a permit:

- 23 1) Signs erected by the Town or State on public roads;  
24 2) Non-advertising signs placed for directional or safety purposes;  
25 3) Temporary auction, lawn, or garage sale signs that do not to exceed two (2) in  
26 number and that do not to exceed fifteen (15) square feet in total area (all such  
27 temporary signs shall be promptly removed when they have fulfilled their  
28 function);  
29 4) One temporary real estate or construction sign not to exceed six (6) square feet  
30 in area and six (6) feet in height, providing such sign is promptly removed when it  
31 has fulfilled its function;  
32 5) Farm signs;  
33 6) A sign no larger than sixteen (16) square feet, which announces the name,  
34 address, and profession of the occupant of the premises engaged in a home  
35 occupation; and  
36 7) A bulletin board or kiosk no larger than twenty-four (24) square feet may be  
37 permitted on the premises of any church, school, or similar public structure.  
38 8) Signs or flags indicating that a business is open and/or the hours of operation,  
39 provided such signs or flags are  
40 a) Limited to one (1) per use (one (1) for hours of operation and one (1)  
41 open/closed sign, or one (1) for both);  
42 b) Are located on the premises of the use for which the sign is advertising;  
43 c) Do not exceed ten (10) square feet for a flag and four (4) square feet for a  
44 sign.  
45

46 **C) Prohibited Signs.** The following shall be prohibited in all districts:

- 1) Signs that impair highway safety.
- 2) Signs that are animated, flashing, or intermittently illuminated, and signs painted or placed on rock outcrops or similar natural features.
- 3) Roof signs and wall signs that extend above the roof line.
- 4) Signs that project over public rights-of-way or property lines.
- 5) Internally lit signs.

**D) Sign Maintenance.** All signs shall be of durable materials and shall be maintained in good condition.

**E) Business Signs.** Signs shall meet the following standards:

- 1) One free-standing sign is allowed adjacent to a building containing one or more businesses. The maximum size of this sign shall be forty (40) square feet and the maximum height shall be eight (8) feet.
- 2) One sign per business establishment is allowed to be attached to the building. The maximum size of this sign shall be twenty (20) square feet.
- 4) The maximum square footage for all signs associated with a building shall be the total of: forty (40) square feet, plus twenty (20) square feet for each business establishment. See examples in Figure 7.9.
- 5) The primary purpose of all business signs shall be for identification of the business (name), products sold, and the business or activity conducted on the premises.
- 6) Illuminated signs shall be shielded in such a way as to produce no glare, undue distraction, confusion, or hazard to the surrounding area or to vehicular traffic.
- 7) Illumination shall be properly focused upon the sign itself.
- 8) No strings or pennants or similar attention-gathering media are permitted.

**Figure 7.9**

**Examples of Total Sign Area**

- A building with three business establishments may have 1 free-standing sign plus 3 signs attached to the building; therefore the total area of all signs (see H below) may not exceed 100 square feet:  $40+20+20+20$ .
- A building with one business may have a total of 60 square feet of signs:  $40+20$ .

**F) Off-Premise Signs.** Any sign located elsewhere than upon the lot containing the subject of the sign shall conform to state statute and regulation for off-premise signs.

**G) Signs at Edge of Highway.** Free-standing signs of 8 feet in height or less may be placed at the edge of the highway right-of-way within any required setback area. However, such signs shall not be located within 25 feet of adjacent private property or an intersection.

**H) Computation of Sign Area.** When computing the total permissible sign area for any use:

- 1) Existing signs shall be included in the calculation of total sign area.
- 2) The total area of all signs shall not exceed the requirements as set forth in these regulations.
- 3) Sign measurement shall be the entire surface area of the sign, exclusive of posts.
- 4) Signs consisting of free-standing letters, numerals, or other devices shall include any intervening space between them.
- 5) Back-to-back signs may be counted as one sign.

**SECTION 7.10: STORAGE OF SEASONAL VEHICLES AND EQUIPMENT (SECTION 490)**

Seasonal vehicles and equipment should be stored inconspicuously from the roadway so as to prevent visibility and setback requirements must be met.

**SECTION 7.11: STORMWATER MANAGEMENT AND EROSION CONTROL**

- A) Developments shall incorporate temporary and permanent stormwater management and erosion control practices as appropriate for the type and density of proposed development and lot coverage to ensure that the project and subsequent development does not result in soil erosion, the degradation of Lake Champlain and other surface waters and/or hazards to properties within the vicinity. Accordingly:
- 1) All stormwater management systems shall be designed to:
    - a) use natural drainage systems to the extent feasible, and minimize the need for system maintenance;
    - b) maximize on-site infiltration and treatment of storm water, and minimize surface runoff;
    - c) accommodate anticipated flows, including existing surface water runoff and total runoff generated by the proposed development at build-out, including anticipated flows from storm events;
    - d) provide storage areas and treatment to manage flows and protect water quality; and
    - e) avoid damage to adjoining properties and downstream drainage facilities.
  - 2) The DRB may require the submission of stormwater management and/or erosion control plans, prepared by a licensed professional, for all phases of development. Such plans shall incorporate accepted management practices as recommended by the state in the Vermont Stormwater Management Manual, and the Vermont Handbook for Soil Erosion and Sediment Control on Construction Sites, as most recently amended, and identify the person(s) or organization responsible for system maintenance.
  - 3) The applicant shall demonstrate that existing downstream drainage facilities will be able to accommodate any additional runoff from the development. If increased runoff exceeds the capacity of downstream drainage, storage or treatment facilities, the DRB may require that the applicant phase the development and/or delay construction until such capacity exists, or install off-site improvements as needed to increase downstream capacity.

1 4) The DRB also may require project phasing to minimize the extent of soil  
2 disturbance and erosion during each phase of development.  
3

4 **SECTION 7.12: WASTEWATER SYSTEM (SEPTIC) AND POTABLE WATER**  
5 **SUPPLY (SECTION 480)**  
6

7 All structures and uses that generate wastewater or require access to potable water  
8 may be required to obtain a Wastewater and Potable Water Supply Permit from the  
9 Vermont Department of Environmental Conservation (DEC) in accordance with 10  
10 V.S.A. Chapter 64 and the Wastewater System and Potable Water Supply Rules (dated  
11 September 29, 2007 or as revised from time to time by the DEC). Applicants proposing  
12 land development that generates wastewater or requires access to potable water must  
13 contact the Agency of Natural Resources District Permit Specialist to determine if such  
14 a permit is required.  
15

- 16 A) If, according to the DEC, a Wastewater System and Potable Water Supply Permit is  
17 not required, the property owner/applicant shall provide written proof from the DEC  
18 of such to the ZA.  
19  
20 B) It shall be unlawful to use or occupy any new principal structure or accessory  
21 dwelling requiring a Wastewater and Potable Water Supply Permit until a Certificate  
22 of Occupancy has been issued by the ZA (See Section 4.2).  
23

24 **SECTION 7.13: HANDICAPPED ACCESS**  
25

- 26 A) For handicapped access structures to a single-family dwelling which are conforming,  
27 and/or in cases in which an access does not meet setbacks and in which the ramp  
28 will not be roofed, the ZA may grant a permit with no charge. For all other  
29 handicapped access to a single-family dwelling Conditional Use Approval is  
30 required. No fee will be required for the Conditional Use Approval or the Zoning  
31 Permit. (325L)  
32  
33 B) Handicapped access not included in Section (A) above and which does not meet  
34 setbacks or which is part of an existing conditional use permit requires Conditional  
35 Use Approval.

1 **ARTICLE 8 SPECIFIC USE/STRUCTURE STANDARDS**  
2

---

3 **SECTION 8.1: APPLICATION OF STANDARDS**  
4

5 The ZA and DRB shall evaluate specific uses according to the corresponding standards  
6 below. The DRB may require modification of subdivision or site plan design, phasing, or  
7 permit conditions to avoid or mitigate any adverse impacts and to ensure conformance  
8 with these standards.  
9

10 **SECTION 8.2: ACCESSORY DWELLING UNITS (SECTION 401)**  
11

12 A) One accessory dwelling may be permitted by the ZA on a property as per 24 VSA §  
13 4412 (E) that is located within or appurtenant to an owner-occupied single-family  
14 dwelling.  
15

16 B) An accessory dwelling unit means an efficiency or one-bedroom apartment that is  
17 clearly subordinate to a single-family dwelling, and has facilities and provisions for  
18 independent living, including sleeping, food preparation, and sanitation, provided the  
19 ZA specifies upon approval there is compliance with all of the following:  
20

- 21 1) The accessory dwelling shall be located within or appurtenant to (on the same lot  
22 as) a single family dwelling.
- 23 2) Floor space shall not exceed 30% of the habitable floor area of the single family  
24 residence or 400 square feet, whichever is greater.
- 25 3) The owner must occupy either the primary residence or the accessory dwelling.
- 26 4) The property has sufficient wastewater capacity according to Section 7.12.
- 27 5) The property meets all of the following applicable Bylaws:  
28 a) Setbacks, see Bylaw Section 5.5;  
29 b) Maximum Lot Coverage see Bylaw Section 5.7; and  
30 c) Parking, see Bylaw Section 7.5.  
31

32 C) The following restrictions apply:

- 33 1) An accessory dwelling is not permitted in an accessory structure which has been  
34 granted variances, setback exceptions or waivers.
- 35 2) In accordance with Section 9.2(C)(2), on lots that contain nonconforming primary  
36 residential uses (more than one) or pre-existing (unpermitted) accessory  
37 dwellings, such as cottages, application can be made to the DRB under  
38 Conditional Use Review to convert one of the nonconforming dwellings to an  
39 accessory dwelling. Approval as an accessory dwelling may cause such  
40 structures to be conforming.
- 41 3) An accessory structure on a nonconforming lot cannot be converted to an  
42 accessory dwelling nor can an accessory dwelling be permitted as a new  
43 accessory structure on nonconforming lots.  
44

1 **SECTION 8.3: AGRICULTURAL HOUSING**

2  
3 A) Agricultural housing which is intended solely to house farm workers and their  
4 families or seasonal or migrant agricultural workers, and is necessary to the principal  
5 agricultural use of a property, may be approved subject to the following provisions:  
6

7 1) Up to two additional single family dwellings (not including the farm residence)  
8 may be approved as a conditional use in all districts, subject to the following  
9 requirements:

- 10 a) Occupancy is restricted to farm workers and their families.  
11 b) The dwellings shall conform to the Vermont Wastewater and Potable Water  
12 Supply rules and permitting requirements.  
13 c) Off-street parking capacity must exist to accommodate residents.

14  
15 2) The DRB decision and Zoning Permit shall clearly state that this dwelling is  
16 necessary to the principal agricultural use of the property and shall be retained in  
17 common ownership for this purpose. An agricultural dwelling may only be  
18 occupied and/or converted for sale or use as a single family dwelling separate  
19 from the agricultural use if it is legally subdivided from the parent parcel and  
20 meets all current local and state regulations.  
21

22 **SECTION 8.4: CAMPGROUNDS, MOBILE HOME PARKS AND TRAVEL TRAILER**  
23 **CAMPS/PARKS (SECTION 446)**

24  
25 **A) Applicability.** Campgrounds, mobile home parks and travel trailer camps/parks  
26 may be permitted subject to the requirements of this section and State Law.  
27

28 **B) Permits and Approvals.**

29 1) Campgrounds, mobile home parks and travel trailer parks/camps shall be  
30 reviewed as a Planned Unit Development by the DRB and shall be subject to the  
31 standards in this section in addition to the Planned Unit Development standards  
32 in Article 6 and all other applicable provisions of this Regulation. Modifying an  
33 existing park by increasing the number of sites, mobile homes or travel trailers  
34 permitted in the park also requires PUD review by the DRB. Alterations involving  
35 the erection, construction, or placement of accessory structures and the  
36 replacement of an existing mobile home in an existing mobile home park shall  
37 not require DRB review; however, a zoning permit is required.  
38

39 **C) Review Standards.** The following standards shall ensure public health, safety, and  
40 welfare in campgrounds, mobile home parks and travel trailer parks/camps in the  
41 Town of North Hero.

- 42 1) All parks/camps shall have a contiguous use area of not less than five (5) acres  
43 and not more than thirty (30) acres.  
44 2) The maximum density of any mobile home park shall not exceed an overall  
45 average of one (1) mobile home per acre. There is no maximum density for  
46 campgrounds and travel trailer parks/camps unless set by the DRB.

- 3) All parks/camps shall maintain a strip of land at least fifty (50) feet wide as a landscaped area abutting all property lines. No campsite, mobile home unit, travel trailer, office, utility or service building may be placed within this buffer area. The DRB may reduce or eliminate this landscaped area requirement if such a modification or waiver will make it possible to preserve a scenic view from the park/camp, provided that privacy for adjacent property owners can be maintained.
- 4) For mobile home parks, the minimum lot size shall be 20,000 square feet unless a lot is provided with either off-site water or sewer, in which case the minimum lot size shall be 15,000 square feet. For campgrounds and travel trailer parks/camps there is no minimum lot size unless set by the DRB.
- 5) Each lot in a mobile home park shall have at least fifty (50) feet of frontage on a mobile home park road. There are no frontage requirements for campgrounds and travel trailer parks/camps unless set by the DRB.
- 6) All internal park/camp roads shall be constructed to the Selectboard's road standards.
- 7) A non-porous pad, at least four (4) inches thick shall be provided for each mobile home lot.
- 8) A minimum yard setback of 15 feet and a minimum setback from the access road of 20 feet are required on each mobile home park lot. There are no setback requirements for campgrounds and travel trailer parks/camps.
- 9) Sewage disposal, water supply and garbage facilities shall comply with state regulations.
- 10) The DRB shall have power to impose reasonable conditions as to the amount, ownership, use, and maintenance of open space and recreation as it deems necessary to assure the preservation of such lands for their intended purpose.

**SECTION 8.5: EARTH RESOURCE EXTRACTION (SECTION 448).**

**A) Applicability.** Earth resource extraction includes the commercial extraction of minerals, including solids such as sand and gravel, liquids such as water, and gases such as natural gas. It may also include preparation activities such as crushing and washing customarily part of earth resource extraction activities. Earth Resource Extraction requires Conditional Use Review in specified zoning districts according to Table 5.1.

- 1) Unless approved as Earth Resource Extraction under this Section, the removal of earth resources including sod, topsoil, loam, fill, sand, shale, gravel or quarried stone is prohibited except when in connection with permitted land development such as the construction of a building on the same lot or a farm operation, nursery, or cemetery to the extent that such removal is necessary to the operation of the same.

**B) Application Requirements.** In addition to Conditional Use application requirements, earth resource extraction proposals shall be prepared by a Vermont Licensed Engineer and include:

- the depth of excavation;

- 1 • existing grade and proposed grade created by removal or addition of material;
- 2 • proximity to roads and adjacent properties;
- 3 • the average amount of earth resource to be extracted on a monthly or annual
- 4 basis;
- 5 • the hours of operation and seasons of use;
- 6 • the expected duration of operation;
- 7 • the number of truck trips per day traveling to/from the extraction site;
- 8 • an erosion and sediment control plan to be following while the extraction
- 9 operation is active; and
- 10 • a reclamation plan that addresses grading, seeding, mulching, planting, fencing,
- 11 drainage, and other measures.

12  
 13 **C) Review Standards.** The DRB shall find that the plan does not cause any undue  
 14 adverse effect to health or property based on the Conditional Use Review standards  
 15 and the following additional standards.

- 16 1) The operation shall not have an adverse effect upon the use of adjacent property  
 17 or town roads due to noise, dust, or vibration.
  - 18 a) Within the required setback areas, the natural vegetation shall be retained,  
 19 and supplementary planting or other screening may be required in order to  
 20 buffer impacts from the operation.
  - 21 b) No power-activated sorting or crushing machinery or equipment shall be  
 22 located within three hundred feet of any street or other property line, and all  
 23 such machinery shall be equipped with satisfactory dust control devices.
- 24 2) The operation shall not create traffic hazards or excessive congestion or physical  
 25 damage to public highways and expected routes of truck traffic.
- 26 3) All surface drainage affected by excavation operations shall be controlled by the  
 27 owner to prevent erosion debris and other loose materials from filling any  
 28 drainage course, street, or private property.
- 29 4) Suitable fencing or other appropriate safety precautions may be required around  
 30 extraction sites, sedimentation ponds, and spoil or equipment storage areas.
- 31 5) Explosives may be used only per a plan approved by the DRB.
- 32 6) The operation shall prepare a site rehabilitation plan that when followed will  
 33 reclaim the site by removing all debris, leveling all cut slopes and soil banks and  
 34 grading to an even low angle, and establishing a firm cover of grass or other  
 35 vegetation sufficient to prevent erosion. The DRB may require the posting of a  
 36 bond to assure such rehabilitation.

37  
 38 **SECTION 8.6: FAMILY CHILD CARE HOME OR FACILITY**

- 39  
 40 A) A family child care home or facility means a home or facility where the owner or  
 41 operator is to be licensed or registered by the state for childcare.
- 42 1) A family child care home serving no more than six (6) full-time children and four  
 43 (4) part-time children shall be considered to constitute a permitted single-family  
 44 residential use of property (i.e. Once a zoning permit for a single-family  
 45 residential use of property has been obtained, no permit is required for such a  
 46 family child care home or facility on that property, although any new structures or

1 structural alterations that would otherwise normally require a permit still require a  
2 permit).

- 3 2) Family child care homes or facilities that serve more than six (6) full-time and four  
4 (4) part-time children shall be considered a Personal or Professional Service  
5 under these Regulations (see Table 5.1).  
6

7 **SECTION 8.7: GASOLINE STATIONS AND MOTOR VEHICLE SERVICE**  
8 **STATIONS (SECTION 450)**  
9

10 Gas and Motor Vehicle Service Stations, when allowed according to Table 5.1, must  
11 comply with all applicable Vermont and Federal regulations and meet the following  
12 standards:  
13

- 14 A) A gasoline station lot cannot be located within five hundred (500) feet of any lot  
15 occupied by a school, public building, library, hospital, or religious institution.  
16  
17 B) Minimum lot size is one and one-half (1.5) acres and both lot depth and width shall  
18 not be less than two hundred (200) feet (this standard shall apply over Table 5.2).  
19  
20 C) No fuel or oil storage nor any pumps, lubricating or other service equipment can be  
21 located within fifty (50) feet of any property line.  
22  
23 D) All motor vehicle parts, dismantled vehicles, junk and trash must be stored within a  
24 building and no repair work can be performed outside of a building.  
25  
26 E) There can be no more than two (2) access driveways and a suitable curbed  
27 landscape area of at least six (6) feet in depth is to be provided and maintained  
28 along all frontage not used by the access driveways.  
29

30 **SECTION 8.8: GROUP HOMES**  
31

32 A residential care home or group home, to be operated under state licensing or  
33 registration, serving not more than eight (8) persons who have a handicap or disability  
34 as defined in 9 V.S.A. §4501, shall be considered by right, to constitute a permitted  
35 single-family residential use of property (i.e. Once a zoning permit for a single-family  
36 residential use of property has been obtained, no permit is required for such a group  
37 home on that property, although any new structures or structural alterations that would  
38 otherwise normally require a permit still require a permit). The only exception is that no  
39 such home shall be so considered if it is located within one thousand (1,000) feet of  
40 another existing or permitted such home. Licensed or registered group homes serving  
41 more than eight persons who have a handicap or disability shall be considered  
42 Congregate Care Facilities under these regulations.  
43

44 **SECTION 8.9: HOME BASED BUSINESSES (SECTION 452)**  
45

1 **A) Home Businesses.** A Home Business shall not require a Zoning Permit in any  
2 district and shall be considered to be part of a residential use. A Home Business is  
3 a use of an accessory building or minor portion of a dwelling for a business that  
4 exhibits no external indications that a business exists. Home Businesses must meet  
5 all of the following standards:  
6

- 7 1) There are no employees other than members of the household.
- 8 2) The Home Business is not visible from outside the home or accessory building.
- 9 3) The Home Business does not generate additional traffic.
- 10 4) The Home Business has no impact on the character of the neighborhood.
- 11 5) The Home Business has no signs.
- 12 6) The Home Business has no external storage of materials or equipment.
- 13 7) The Home Business produces no objectionable noise, smoke, vibration, dust or  
14 odors discernible on any adjoining property.

15  
16 **B) Home Occupations.** Home Occupations require a Zoning Permit. Any resident of  
17 a dwelling may use a minor part of the residential property for an occupation which is  
18 customary in residential areas, does not involve retail sales, and which does not  
19 change the character of the residential area providing all of the following standards  
20 are met:

- 21 1) The Home Occupation is carried on wholly within the principal dwelling or  
22 accessory structures.
- 23 2) The Home Occupation is carried on only by residents of the premises and not  
24 more than one (1) additional full-time or part-time employee who is not a resident  
25 of the home.
- 26 3) Exterior storage of material is not permitted unless adequately screened from  
27 view from adjacent properties, roads and the Lake. Exterior storage is prohibited  
28 in setback areas.
- 29 4) The Home Occupation does not generate a greater volume of traffic than would  
30 normally be expected in the neighborhood.
- 31 5) There shall be no exterior displays, except that one unlit sign not exceeding four  
32 (4) square feet per side is allowed.
- 33 6) The Home Occupation does not cause any objectionable noise, vibration, smoke,  
34 dust, electrical disturbance, odors, heat or glare.
- 35 7) Off-street parking spaces shall be provided according to Section 7.5. Parking  
36 shall be located in side or rear yards outside setback areas. However, existing  
37 residential parking areas may be utilized.
- 38 8) The Home Occupation does not utilize a square footage that is larger than  
39 twenty-five (25) percent of the total area of the principal dwelling.

40  
41 **C) Home Occupations with Two or Three Employees.** A Home Occupation having 2  
42 or 3 non-family full-time equivalent employees may be permitted after Conditional  
43 Use Review by the DRB. The DRB shall find that the Home Occupation complies  
44 with the standards in (B) 3-7 above in addition to the Conditional Use Review  
45 standards in Section 6.1. In addition to the Conditional Use application materials

1 listed in Section 6.1, applications for Home Occupations with Two to Three  
2 Employees shall provide:

- 3
- 4 1) A description of all activities, existing and proposed, specifying which shall be  
5 carried on outside of the principal dwelling or accessory structures.
- 6 2) A description of all exterior storage of material, machinery, and/or vehicles, and  
7 the location of where it is to be stored.
- 8 3) The size, location and use of any exterior displays or advertisements.
- 9 4) A description of hours of operation, and specifically any activity which might  
10 result in objectionable noise, vibration smoke, dust, electrical disturbance, odors,  
11 heat or glare.
- 12

### 13 **SECTION 8.10: LAKE ACCESS STRUCTURES**

14  
15 Lake access structures come under the jurisdiction of the North Hero Development  
16 Regulations and this section when they are not under the jurisdiction of the Army Corps  
17 of Engineers or the Vermont Department of Environmental Conservation (Army Corps  
18 jurisdiction begins for development that is located below or beyond an elevation of 98  
19 feet above sea level). Structures located all or partially below the 102 foot elevation  
20 contour are subject to Flood Hazard Area review in accordance with Article 10 in  
21 addition to this section.

22  
23 Lake access structures include stairways or pedestrian ramps, boat launch ramps and  
24 docks constructed to gain access to the lakeshore. Lake access structures are exempt  
25 from the lake setback requirement (Table 5.2) but shall require a 25 foot setback from  
26 side property lines. Lake access structures shall be permitted according to the  
27 requirements of this Section.

- 28
- 29 **1) One set of stairs or one pedestrian ramp, meeting required setbacks,** may be  
30 permitted by the ZA according to the following standards:
  - 31 a) Maximum stair or ramp width shall be four (4) feet.
  - 32 b) No roofs or other permanent shelters are permitted.
  - 33 c) Landings and turnarounds shall be kept as small as possible. Top landings shall  
34 not exceed 144 square feet, and mid-landings shall not exceed 50 square feet.
  - 35 d) Any lighting shall be downward pointing and only on when stairway is in use.
- 36
- 37 **2) Permanent boat launching ramps or slipways, meeting required setbacks,**  
38 may be permitted by the ZA according to the following standards  
39 (temporary/portable boat launching ramps or slipways are exempt):
  - 40 a) At least one permanent boat launching ramp or slipway may be permitted per  
41 property regardless of the amount of shoreline frontage. Additional permanent  
42 boat launching ramps or slipways may be permitted for properties with a more  
43 than 100 feet of shoreline frontage at a ratio of one (1) per 100 feet of shoreline  
44 frontage.
  - 45 b) No more than 24 feet of bank per boat launch ramp or slipway may be disturbed.

1 c) Any lighting shall be downward pointing and only on when the boat launching  
2 ramp or slipway is in use.

3  
4 **3) Docks meeting required setbacks** may be permitted by the ZA according to  
5 standards below. There are two types of docks considered by these regulations:  
6 permanent docks attached to the shore by means of permanent structure or other  
7 fixed apparatus and seasonal carry-in docks.

8 a) At least one permanent dock or seasonal carry-in dock may be permitted per  
9 property regardless of the amount of shoreline frontage. Additional permanent  
10 docks and seasonal carry-in docks may be permitted for properties with more  
11 than 100 feet of shoreline frontage at a ratio of one (1) permanent dock and one  
12 (1) seasonal carry-in dock per 100 feet of shoreline frontage.

13 b) Any lighting shall be downward pointing and only on when the dock is in use.  
14

### 15 **SECTION 8.11: LIGHT INDUSTRY AND COMMERCIAL ACTIVITY**

16  
17 Light Industry and Commercial Activity as listed in Table 5.1 must meet the  
18 requirements for Conditional Use Review, including preparation of a site plan, as found  
19 in Section 6.1.  
20

### 21 **SECTION 8.12: MARINAS, YACHT CLUBS AND RESIDENTIAL MARINE** 22 **ASSOCIATIONS (SECTION 456)**

23  
24 **A) Applicability.** In addition to the Conditional Use Review standards, marinas, yacht  
25 clubs and residential marine associations shall comply with the specific standards in  
26 this section.

27 1) A **marina** is a business whose purpose is the sale, servicing, launching, or rental  
28 of boats and/or the sale or rental of moorings or docking berths. A marina may  
29 also include services ancillary to the marina operation such as retail, repair, food,  
30 laundry facilities, etc.

31 2) A **yacht club** is a facility similar to a marina but operated on a non-profit basis for  
32 the benefit of members or associates. The land may be held or controlled by  
33 either an individual or a business entity. A yacht club may also include services  
34 ancillary to the yacht club such as retail, repair, food, laundry facilities, etc.

35 3) A **residential marine association** is any commonly held shoreline property  
36 which is a common element of or an appurtenance to a residential development  
37 on the same or adjacent property that provides access to the shoreline for more  
38 than two (2) residences.  
39

40 **B) Review Standards for Marinas and Yacht Clubs.** Marinas and yacht clubs  
41 must comply with the following standards, except that for a yacht club the DRB may  
42 grant an exemption from any standard in this Section, at the request of the applicant, if  
43 the DRB finds that such standard is not applicable and does not nullify the intent of  
44 these Regulations or the Town Plan. Marinas and yacht clubs require Conditional Use  
45 Approval, including preparation of a site plan, in accordance with Section 6.1.

- 1       **1) Shoreline Frontage.** Marinas and yacht clubs require a minimum of 200 feet of  
2       consecutive shoreline frontage.  
3
- 4       **2) Parking, Storage and Circulation Standards.** The site plan shall indicate a  
5       plan for parking; storage of boats, dinghy's, and other marina equipment; and  
6       onsite circulation in conformance with the following standards.  
7
- 8       **a) Parking.** Marinas and yacht clubs shall comply with the off-street parking  
9       requirements of Section 7.5 and this section. Parking areas shall be setback  
10      25 feet from all property lines and the Lake. Parking spaces intended for  
11      vehicles and boat trailers shall be adequately sized (approximately 10 feet by  
12      40 feet). The DRB may approve shared parking spaces for those spaces  
13      used primarily in the summer and those used for winter storage.  
14
- 15      **b) Storage of Boats and Dinghy's.** Boat and dinghy storage areas shall be  
16      designated on the site plan. Boat and dinghy storage areas shall be setback  
17      at least 25 feet from all property lines and the Lake, except that dinghy  
18      storage areas are exempt from the 25 foot setback from the Lake.  
19      **i) Overnight/Long-term Storage.** The DRB may allow overnight and/or  
20      long-term storage of boats if designated to a specific area on the site plan.  
21      Winter storage areas shall be screened from rights of way and adjacent  
22      property lines. Winter storage areas shall include adequate space for  
23      parking and access to stored boats.  
24      **ii) Temporary Habitation on Stored Boats.** The DRB may allow temporary  
25      habitation (not more than 30 consecutive days) on stored boats provided  
26      that onsite restrooms are made available.  
27
- 28      **c) Onsite Circulation.** The site plan shall indicate on-site vehicular and  
29      pedestrian circulation with adequate access provided for all site amenities,  
30      including the pump out station and fuel storage area. Adequate space shall  
31      be provided for launching and servicing boats so as not to interfere with the  
32      public right-of-way.  
33      **i) Pedestrian Accessibility.** The site plan shall include designated  
34      pedestrian paths to and from buildings and bathroom facilities, parking  
35      areas, moorings and docking berths, and to adjacent properties.  
36      Crosswalks may be required for marinas and yacht clubs bisected by a  
37      road or where it is appropriate to provide safe access to adjacent uses.  
38
- 39      **d) Fuel storage areas** shall be located in containment structures sufficient to  
40      contain fuel spillage from tanks and shall meet EPA standards.  
41
- 42      **3) Waste Management.** A plan for managing and disposing of trash, fuel and oil,  
43      cleaning materials, paint, and sewage is required. This shall include an on-  
44      shore, on premises holding tank for receiving boat sewage. A minimum of two  
45      (2) toilets for use by customers, members or associates is required.  
46

1 **4) Stormwater Management.** In addition to the standards in Section 7.11, if a  
2 marina will provide boat washing it must be designated to a limited area on the  
3 site plan and adequate stormwater management shall be provided to prevent  
4 run-off into the lake.

5  
6 **5) State and Federal Permits.** It shall be a condition of every permit that all State  
7 and Federal permits are filed by the applicant with the Town of North Hero land  
8 records and zoning office.

9  
10 **C) Review Standards for Residential Marine Associations.** Residential marine  
11 associations shall comply with the following standards.

- 12 1) Residential Marine Associations on undeveloped properties require a minimum of  
13 100 feet of consecutive shoreline frontage. Residential Marine Associations on  
14 developed lots require a minimum of 200 feet of consecutive shoreline frontage.
- 15 2) Residential marine associations are strictly limited to use by the residences in the  
16 associated residential development and their guests according to and limited by  
17 recorded covenants in the land records.
- 18 3) Residential marine associations shall not provide or allow ancillary services, such  
19 as retail, repair, food and laundry facilities, which are allowed for marinas and  
20 yacht clubs, unless otherwise permitted in conformance with these regulations.
- 21 4) The DRB may require designated parking spaces to ensure efficient and safe  
22 vehicular circulation if the level of use and site layout warrants it.

#### 23 24 **SECTION 8.13: PUBLIC FACILITIES (SECTION 404)**

25  
26 A) In accordance with the Act (Section 4413), the following public facilities may be  
27 regulated, subject to Conditional Use Review only with respect to location, size,  
28 height, building bulk, yards, courts, setbacks, density of buildings, off street parking  
29 and loading, traffic, noise, lighting, and landscaping or screening requirements, and  
30 only to the extent that the regulations do not interfere with the intended functional  
31 use:

- 32  
33 1) State or community owned and operated institutions and facilities;
- 34 2) Public and private schools and other educational institutions certified by the  
35 Vermont Department of Education;
- 36 3) Churches and other places of worship (see definitions), convents, and parish  
37 houses;
- 38 4) Public and private hospitals;
- 39 5) Regional solid waste facilities certified by the State (10 V.S.A. chapter 159); and
- 40 6) Hazardous waste management facilities for which a notice of intent to construct  
41 has been received under state law (10 V.S.A. 6606a).

#### 42 43 **SECTION 8.14: SHORELINE STABILIZATION MEASURES**

44  
45 A) **Applicability.** Shoreline stabilization measures come under the jurisdiction of the  
46 North Hero Development Regulations and this section when they are not under the

1 jurisdiction of the Army Corps of Engineers or the Vermont Department of  
2 Environmental Conservation (Army Corps jurisdiction begins for development that is  
3 located below or beyond an elevation of 98 feet above sea level). Structures located  
4 all or partially below the 102 foot elevation contour are subject to Flood Hazard Area  
5 review in accordance with Article 10 in addition to this section.  
6

7 Shoreline stabilization measures involve the use of structures, vegetation, or land  
8 management practices to provide protection of a shoreline from future or existing  
9 erosion, including but not limited to vegetative buffers, rip-rap, and seawalls. There  
10 are nonstructural, structural, bioengineering and biotechnical stabilization methods  
11 (for more detail reference the Shoreline Stabilization Handbook for Lake Champlain  
12 and other Inland Lakes published by the Northwest Regional Planning Commission).  
13 All shoreline stabilization measures, except non-structural plantings, require a  
14 Zoning Permit issued by the Zoning Administrator in addition to compliance with this  
15 section.  
16

17 **B) Shoreline stabilization measure review standards:**

- 18
- 19 1) Non-structural and bio-technical stabilization methods are preferred over  
20 structural and bio-engineering methods.  
21
  - 22 2) The design of structural, bio-technical and bio-engineering stabilization methods  
23 shall be reviewed and approved by a qualified environmental professional. The  
24 ZA shall require a written statement from the qualified environmental professional  
25 stating that:
    - 26 • Unique characteristics of the site make the chosen stabilization method the  
27 best solution to prevent loss of a principal structure or significant erosion, and
    - 28 • Evidence that the chosen stabilization method will not have undue adverse  
29 impact in the form of significant erosion on adjacent shoreline properties.  
30

31 The *Shoreline Stabilization Handbook for Lake Champlain and Other Inland*  
32 *Lakes* includes a description of the various forms of lakeshore erosion and detail  
33 on the appropriate use and potential impacts of stabilization methods; it shall be  
34 referenced by the engineer.  
35

- 36 3) Where plantings are part of the stabilization measure, native plants, trees and  
37 shrubs shall be used. Reference the *Vermont Lakeshore Protection Series #3*  
38 *Plants and Plantings on Lakeshores*.  
39

40 **SECTION 8.15: SMALL OFF-GRID ENERGY GENERATION SYSTEMS**

41

42 **A) Purpose and Applicability.** The purpose of this Section is to promote the safe,  
43 effective and efficient use of small off-grid energy systems which are not regulated  
44 by the Vermont Public Service Board.  
45

1 **B) Off-Grid Solar Arrays.** Solar arrays shall comply with all required state and federal  
2 codes and regulations, including the FAA Regulations and the National Electrical  
3 Code. The manufacturer frequently supplies this information. Solar arrays may be  
4 attached to a building or be free-standing with a support structure.  
5 Solar arrays attached to a building and free standing solar arrays that are twenty-five  
6 (25) feet or less in height are permitted uses in all zoning districts except the  
7 Conservation District where they are prohibited. Free standing solar arrays greater  
8 than twenty-five (25) in height require Conditional Use Review. The DRB shall  
9 require that the minimum setback from property lines be equal to or greater than the  
10 height of the array.  
11

12 **C) Small Off-Grid Wind Energy Generation Systems.** Small off-grid wind energy  
13 systems are a Conditional Use in all zoning districts except the Conservation District  
14 where they are prohibited. In addition to Conditional Use application requirements,  
15 applications for wind energy generation systems shall include standard drawings of  
16 the wind turbine structure, including the tower, base, and footings. An engineering  
17 analysis of the tower showing compliance with the Uniform Building Code and  
18 certified by a qualified environmental professional shall also be submitted. This  
19 analysis is frequently supplied by the manufacturer. In addition to the Conditional  
20 Use Standards in Article 6.1, the DRB shall find that proposed small off-grid wind  
21 energy systems comply with the following standards before approving an  
22 application:

- 23 1) Tower Height: For property sizes between ½ acre and one acre the tower height  
24 shall be limited to 80.0 ft. For property sizes of one acre or more, there is no  
25 limitation on tower height, except as imposed by FAA Regulations.
- 26 2) Setback: The tower base shall be setback a distance no less than the tower  
27 height (including blade, rotor, or other vertical elements), which shall create a fall  
28 zone entirely on the landowners property. Guy wire anchors and other accessory  
29 elements may extend to the setback for the Zoning District in which it is located.
- 30 3) Noise: Small off-grid wind energy systems shall not exceed 60.0 dBA, as  
31 measured at the closest neighboring inhabited dwelling. The level, however,  
32 may be exceeded during short-term events such as utility outages and/or severe  
33 windstorms.
- 34 4) Compliance with State and Federal Codes and Regulations: Small off-grid wind  
35 energy systems must comply with all required state and federal codes and  
36 regulations, including the FAA Regulations and the National Electrical Code. The  
37 manufacturer frequently supplies this information.  
38

## 39 **SECTION 8.16: RV AND TRAVEL TRAILERS (SECTION 464)**

40

41 A) A travel trailer is designed for short-term occupancy. As used in these Regulations,  
42 the term "travel trailer" also includes but is not limited to a camper trailer, motor  
43 home, recreational vehicle, tent trailer and truck camper.  
44

1 The owner of a travel trailer may store it on his/her own property as inconspicuously  
2 as possible in accordance with the setback requirements for the specific zoning  
3 district and the standards included in this Section.  
4

5 B) A legally registered travel trailer designed and manufactured for recreational  
6 camping uses, may be stored or parked on a developed residential lot provided it  
7 meets the following requirements:

- 8 1) It shall not be permanently attached to the land.
- 9 2) It shall not be occupied for residential use while on the lot.
- 10 3) It shall not be attached to a septic system.
- 11 4) There shall not be more than two such units on a lot.
- 12 5) Such use shall not conflict with any provision of this Regulation.

13  
14 C) A legally registered travel trailer designed and manufactured for recreational  
15 camping uses, may be placed on an undeveloped lot and used for limited seasonal  
16 occupancy provided it meets the following requirements:

- 17 1) It shall not be permanently attached to the land.
- 18 2) It may be occupied seasonally (for not more than a total of 180 days between  
19 May 1 and November 30 and no more than 60 days between November 1 and  
20 May 31) if it is hooked up to a water supply and a legally existing septic system  
21 that has been continuously used for that purpose, or a system approved under  
22 these regulations.
- 23 3) There shall not be more than one such unit on a lot.
- 24 4) Such use shall not conflict with any provision of this or other applicable  
25 regulations.

26  
27 D) A legally registered travel trailer designed and manufactured for recreational  
28 camping purposes, may be placed on an undeveloped lot and used for recreational  
29 camping purposes, only, provided it meets the following requirements:

- 30 1) It shall not be permanently attached to the ground
- 31 2) It may be occupied for recreational camping purposes, only, for not more than a  
32 total of 45 days between May 1<sup>st</sup> and November 30<sup>th</sup> if it is not hooked up to a  
33 water supply or septic system.
- 34 3) It has a self-contained storage tank for waste water, which is either emptied off  
35 site in an approved disposal facility or the owner and occupant enters into a  
36 service contract with an approved hauler for collection and disposal off site in an  
37 approved facility, OR, an approved self-contained port-a-let is provided on site  
38 and the owner or occupant enters into a service contract with an approved hauler  
39 for collection and disposal off site in an approved facility
- 40 4) There is not more than one unit on a lot.
- 41 5) Such use does not conflict with any provision of this or any other applicable  
42 regulations.

1 **SECTION 8.17: WIRELESS TELECOMMUNICATION FACILITIES**

2  
3 New or expanded wireless telecommunications facilities that are not subject to 30  
4 V.S.A. Section 248, including but not limited to towers and accessory structures, are  
5 subject to Conditional Use Review and the provisions of this Section. In conformance  
6 with 24 V.S.A. § 4412(9), the DRB may permit new or expanded telecommunications  
7 facilities if the DRB finds that the facility will impose not more than a de minimus impact  
8 on the conditional use standards in Section 6.1 and the criteria in (F) below.  
9

- 10 A) The following requires a Certificate of Public Good from the Department of Public  
11 Service under 30 V.S.A. Section 248, which preempts these Regulations:  
12 1) Placement of wireless telecommunications facilities on electric transmission or  
13 generation facilities; and  
14 2) Single application to construct or install 3 or more telecommunications facilities,  
15 each at least 50.0 ft. above ground level, within 3 years as part of a network.  
16  
17 B) No Zoning permit shall be required for the following:  
18 1) Antennae with an aggregate area of not more than eight (8) square feet on the  
19 largest face and which are on masts that extend not more than twelve feet above  
20 the specific roof area to which they are attached and are not located on historic  
21 landmarks and structures.  
22 2) Antenna structures less than twenty (20) feet in height with a primary function to  
23 transmit or receive communication signals for commercial, industrial, municipal,  
24 county, or state purposes.  
25 3) Telecommunication facilities that are used exclusively for municipal radio  
26 dispatch service or emergency radio dispatch service and which do not exceed  
27 100.0 feet in height.  
28  
29 C) Amateur radio, citizens band radio, AM or FM radio, or broadcast television service  
30 towers that exceed the requirements in (B) above but do not exceed 100 feet in  
31 height are exempt from the provisions of this Section, but require a Zoning Permit as  
32 an accessory structure.  
33  
34 D) Supplemental Application Requirements. In addition to the application requirements  
35 required for Conditional Use Review a wireless telecommunication facility permit  
36 application shall also include:  
37 1) A location map showing the general area within a 2 mile radius of the facility.  
38 2) A vicinity map showing the entire vicinity within a 2,500 foot radius of the facility,  
39 including the location of all existing and proposed towers, topography, public and  
40 private roads and driveways, buildings, structures, utilities, water bodies,  
41 wetlands, 50 foot contour lines, landscape features, historic sites, and significant  
42 wildlife habitats. It shall indicate the property lines of the proposed facility site  
43 parcel and all easements or rights-of- way needed for access from a public way  
44 to the facility.  
45 3) Elevations and proposed site plans of the facility showing all facades and  
46 indicating all exterior materials and colors of towers, buildings and equipment, as

- 1 well as all landscaping, utility wires, guy wires and screening. (All plans except  
2 the vicinity map shall be drawn at a minimum scale of 1 inch = 50 feet.)
- 3 4) In the case of a site that is forested, the approximate average elevation of the  
4 existing vegetation within 50 feet of any tower base.
- 5 5) A report from a qualified Vermont Licensed Engineer that:  
6 a) Describes any tower's design and elevation.  
7 b) Documents the elevation above grade for all proposed mounting positions for  
8 antennas to be mounted on a tower and the minimum distances between  
9 antennas.  
10 c) Describes a tower's capacity, including the number, elevation, and types of  
11 antennas that the tower is proposed to accommodate.  
12 d) In the case of new facilities, demonstrates that existing towers and structures  
13 within five miles of the site cannot reasonably be modified to provide  
14 adequate coverage and adequate capacity to the community.  
15 e) Describes potential changes or additions to existing structures or towers that  
16 would enable them to provide adequate coverage.  
17 f) Describes the output frequency, number of channels, and the power output  
18 per channel for each antenna. As an alternative, a coverage map may be  
19 provided.  
20 g) Demonstrates the facility's compliance with the standards set forth in these  
21 Regulations or other applicable standards.  
22 h) Provides proof that at the proposed facility site the applicant will be in  
23 compliance with all FCC Regulations, standards and requirements, and  
24 includes a statement that the applicant commits to continue to maintain  
25 compliance with all FCC Regulations, standards and requirements for radio  
26 frequency radiation (RFR).  
27 i) Includes such other information as determined by the DRB to evaluate the  
28 application.
- 29 6) A letter of intent committing the facility owner and its successors to permit shared  
30 use of any tower if the additional users agree to meet reasonable terms and  
31 conditions for shared use, including compliance with all applicable FCC  
32 Regulations, standards and requirements and the provisions of these bylaws and  
33 all other applicable laws.
- 34 7) In the case of an application for additional antennas or other equipment to be  
35 installed on an existing facility, a copy of the executed contract with the owner of  
36 the existing structure.
- 37 8) To the extent required by the National Environmental Policy Act (NEPA) and as  
38 administered by the FCC, a complete Environmental Assessment (EA) draft or  
39 final report describing the probable impacts of the facility, or a written statement  
40 by the applicant that an EA is not required for the facility.

41  
42 **E) Construction Standards.** Telecommunications facilities shall conform to the  
43 following construction standards:

- 44 1) The facility will not be built on speculation. If the applicant is not a  
45 telecommunication service provider, the applicant shall provide a copy of a  
46 contract or letter of intent showing that a telecommunication service provider is

1           legally obligated to locate a wireless telecommunication facility on lands owned  
2           or leased by the applicant.

- 3       2) The facility will not project more than 20 feet above the average elevation of the  
4       tree line measured within 100 feet of the highest vertical element of the wireless  
5       telecommunication facility, unless the proposed elevation is reasonably  
6       necessary to provide adequate telecommunication service capacity or coverage  
7       to North Hero, or to accomplish co-location.
- 8       3) All telecommunication facilities shall comply with the setback provisions of the  
9       zoning districts in which facilities are located. Notwithstanding the above, in  
10      order to ensure public safety, the minimum distance of any wireless  
11      telecommunication facility to any property line, dwelling, or occupied structure  
12      shall be no less than the height of the tower, including antennas or other vertical  
13      appurtenances. This setback shall be referred to as a fall zone. In the event that  
14      an existing structure such as a barn silo, church steeple, or utility pole is  
15      proposed as a mounting for a wireless telecommunication facility, a fall zone  
16      setback may not be required.
- 17     4) The facility will not be illuminated by artificial means and will not display any  
18     lights or signs except for such lights and signs as required by Federal Aviation  
19     Administration, federal or state law, or these Regulations.
- 20     5) The DRB may require the applicant to provide a bond, or other form of financial  
21     guarantee acceptable to the DRB, to cover the cost of removal of the facility,  
22     should the facility be abandoned or cease to operate.
- 23     6) The applicant demonstrates that the facility will be in compliance with all FCC  
24     standards and requirements regarding radio frequency radiation. The owner of a  
25     wireless telecommunication facility shall, on a yearly basis, file a certificate to the  
26     ZA showing that it is in compliance with all FCC standards and requirements  
27     regarding radio frequency radiation, and that adequate insurance has been  
28     obtained for the facility.
- 29     7) The facility will be properly identified with appropriate warnings indicating the  
30     presence of radio frequency radiation.
- 31     8) The proposed equipment is installed on an existing wireless telecommunication  
32     facility, unless it is demonstrated by the applicant that such co-location is not  
33     structurally or spatially possible.
- 34     9) The facility provides reasonable opportunity for the installation and operation of  
35     other telecommunications equipment (co-location).
- 36     10) Unless otherwise approved by the DRB, an abandoned or unused wireless  
37     telecommunication facility shall be removed within 2 years of abandonment or  
38     cessation of use. The applicant may apply to the DRB for an extension for  
39     removal. If the facility is not removed, or an extension granted, within 2 years of  
40     abandonment or cessation of use, the DRB may cause the facility to be removed.  
41     The costs of removal shall be assessed against the facility owner.
- 42     11) Unused portions of a wireless telecommunication facility shall be removed within  
43     1 year of the time that such portion is no longer used. Replacement of portions  
44     of a facility previously removed shall require a new permit.

46   **F) Additional Conditional Use Criteria.** In addition to the Conditional Use Standards  
47    in Section 6.1 and the construction standards in (E) above, the DRB shall approve

- 1 an application for a wireless telecommunications facility when it finds that the  
2 application does not impose more than a de minimus impact on the following criteria:
- 3 1) The facility will not unreasonably interfere with the view from any public park,  
4 natural scenic vista, historic building or district, or major view corridor.
  - 5 2) The facility will not have an undue adverse aesthetic impact. In determining this,  
6 the DRB shall consider the following factors:
    - 7 a) The results of a balloon test, if conducted.
    - 8 b) The extent to which the proposed towers and equipment have been designed  
9 to blend into the surrounding environment through the use of screening,  
10 camouflage, architectural design, and/or imitation of natural features.
    - 11 c) The extent to which access roads have been designed to follow the contour of  
12 the land and will be constructed within forest or forest fringe areas and not  
13 open fields.
    - 14 d) The duration and frequency with which the facility will be viewed from a public  
15 road or from public property.
    - 16 e) The degree to which the facility will be screened by existing vegetation,  
17 topography, or existing structures.
    - 18 f) Background features in the line of sight to the facility that obscure or make the  
19 facility more conspicuous.
    - 20 g) The distance of the facility from the point of view and the proportion of the  
21 facility that is above the skyline.
      - 22 i) The sensitivity or unique value of a particular view affected by the facility.
      - 23 ii) Any significant disruption of a viewshed that provides context to an  
24 important historic or scenic resource.
  - 25 3) The facility will not generate undue noise.

1 **ARTICLE 9: NONCONFORMITIES**

---

2  
3 **SECTION 9.1: NONCONFORMING LOTS**

4  
5 **Pre-existing Lots (Section 360).**

- 6  
7 A) Any lot that is legally subdivided, is in individual and separate and nonaffiliated  
8 ownership from surrounding properties, and is in existence on the date of enactment  
9 of any bylaw, including an interim bylaw, may be developed for the purposes  
10 permitted in the district in which it is located, even though the small lot no longer  
11 conforms to minimum lot size requirements of the new bylaw or interim bylaw  
12 provided such lot is not less than one-eighth acre in area and not less than forty feet  
13 in width and depth. (See also Section 5.5(E)).  
14
- 15 B) If a pre-existing small lot comes under common ownership with one or more  
16 contiguous lots, it shall be deemed merged with said contiguous lot unless the small  
17 lot is developed and contiguous to a legal undeveloped lot. Deemed merging  
18 happens in the following situations:  
19 1) Contiguous undeveloped small lots under the same ownership,  
20 2) An undeveloped small lot contiguous to a developed small lot under the same  
21 ownership,  
22 3) A small undeveloped lot contiguous to a developed legal lot under the same  
23 ownership, and  
24 4) A small undeveloped lot contiguous to a legal undeveloped lot under the same  
25 ownership.  
26
- 27 C) However, a nonconforming lot shall not be deemed merged and may be separately  
28 conveyed if all the following apply:  
29 1) The lots are conveyed in their preexisting, nonconforming configuration.  
30 2) On the effective date of any bylaw, each lot was developed with a water supply  
31 and wastewater disposal system.  
32 3) At the time of transfer, each water supply and wastewater system is functioning  
33 in an acceptable manner.  
34 4) The deeds of conveyance create appropriate easements on both lots for  
35 replacement of one or more wastewater systems, potable water systems, or  
36 both, in case there is a failed system or failed supply as defined in 10 V.S.A.  
37 chapter 64.  
38

39 **SECTION 9.2: NON-CONFORMING STRUCTURES AND USES(SECTION 375)**

- 40  
41 **A) Applicability.** Nonconforming structures and uses are those that were in existence  
42 before the effective date of these Regulations, which do not conform to the  
43 requirements set forth in these Regulations. Structures located on pre-existing small  
44 lots, which otherwise conform to these Regulations, including setbacks, are not  
45 considered nonconforming. Structures and uses improperly authorized as a result of  
46 error by the ZA are nonconforming.

1  
2 **B) Continuation of Nonconforming Structures and Uses.**  
3

4 **1) Nonconforming Structures.** No provision of these Regulations shall prevent  
5 the normal maintenance and repair of a non-conforming structure provided that  
6 such action does not increase the degree of non-conformance.  
7

8 **2) Nonconforming Uses.** Any non-conforming use of a structure or of land may be  
9 continued indefinitely except that a non-conforming use shall not be  
10 reestablished after being abandoned for a period of one year, or after being  
11 changed to, or replaced by, a conforming use. Intent to resume a non-  
12 conforming use shall not confer the right to do so. A non-conforming use is  
13 considered abandoned when one of the following occurs:

- 14 a) The characteristic activity, equipment and/or furnishings of the non-  
15 conforming use have been removed from the premises and have not been  
16 replaced by similar equipment within one (1) year.  
17 b) It has been changed to another use under an approved permit.  
18

19 **C) Improvements to Nonconforming Structures and Uses.**  
20

21 **1) Nonconforming Structures.** The ZA may approve improvements to non-  
22 conforming structures provided that the improvement does not increase the  
23 degree of non-conformity through issuance of a Zoning Permit in accordance  
24 with these Regulations. The DRB may approve improvements to nonconforming  
25 structures that increase the degree of nonconformity as a conditional use only if  
26 required to comply with environmental, safety, health or energy codes, laws or  
27 regulations. See Figure 9.2 for an illustration of increasing the degree of  
28 nonconformity. Nonconforming structures are eligible for a setback waiver in  
29 certain instances (see Section 6.2 Setback Waivers).  
30

31 **2) Nonconforming Uses.** Nonconforming uses shall not be expanded or changed  
32 without Conditional Use Approval from the DRB in accordance with this Section.  
33 In addition to the Conditional Use Standards in Article 6.1, the DRB shall apply  
34 the following standards:

- 35 a) Nonconforming uses shall not be expanded. Improvements that enlarge  
36 footprint area or add floor space to structures occupied by nonconforming  
37 uses are prohibited. The DRB may approve an improvement to a  
38 nonconforming use that does not expand the use, enlarge footprint area or  
39 add floor space, such as changing a sign.  
40 b) A non-conforming use may change to another use only if in the opinion of the  
41 DRB the new use is in greater compliance with these Regulations.  
42


43 **D) Nonconformities in a Mobile Home Park.** If a mobile home park, as defined in 10  
44 V.S.A. chapter 153, is a nonconformity, the entire mobile home park shall be treated  
45 as a nonconformity, and individual lots within the mobile home park shall in no event  
46 be considered nonconformities. Its status regarding conformance or  
47 nonconformance shall apply to the parcel as a whole, and not to any individual

1 mobile home lot within the park. An individual mobile home lot that is vacated shall  
2 not be considered a discontinuance or abandonment of a nonconformity.  
3

**Figure 9.2 Increasing the Degree of Nonconformity of a Structure**

*The building 'A' is the original nonconforming structure because it encroaches into the setback. Additions 'B', 'C' and 'D' are allowed under these regulations because they do not encroach further into the setback than Building 'A'. Addition 'E' is not allowed under these regulations because it encroaches further into the setback than Building 'A'.*

4



5  
6

1 **ARTICLE 10: FLOOD HAZARD REGULATIONS**

---

2  
3 **SECTION 10.1 LAND TO WHICH THESE STANDARDS APPLY**

4  
5 These standards shall apply to development in the Flood Hazard Overlay District. This  
6 District includes the Special Flood Hazard Areas in and on the most current flood  
7 insurance studies and maps published by the Department of Homeland Security (DHS),  
8 Federal Emergency Management Agency (FEMA), and National Flood Insurance  
9 Program (NFIP), as provided by the Secretary of the Agency of Natural Resources  
10 pursuant to 10 V.S.A. Section 753, which are hereby adopted by reference and  
11 declared to be part of these regulations.

12  
13 The provisions of these flood hazard regulations shall not in any way impair or remove  
14 the necessity of compliance with any other local, state, or federal laws or regulations.  
15 Where this flood hazard regulation imposes a greater restriction the provisions here  
16 shall take precedence.

17  
18 **A) Base Flood Elevations & Floodway Limits shall be determined as follows:**

19  
20 Base flood elevations provided by the National Flood Insurance Program and in the  
21 Flood Insurance Study and accompanying maps shall be used to administer and  
22 enforce these regulations. Flood Hazard Area District boundaries shall be  
23 determined by the ZA. Appeals with respect to the District Boundaries (Section 3.1)  
24 can be made to the DRB in accordance with Section 2.5. Floodway limits are not  
25 required for the flood hazard zone A2 located on Lake Champlain as shown in the  
26 NFIP Study and accompanying maps.

27  
28 **B) Warning and Disclaimer.** The Flood Hazard Overlay District standards in this  
29 section do not imply that land outside of the areas of special flood hazard or land  
30 use permitted within Flood Hazard Overlay District will be free from flooding or flood  
31 damages. These standards shall not create liability on the part of the Town of North  
32 Hero or any town official or employee thereof for any flood damages that result from  
33 reliance on the standards of this section or any administrative decision lawfully  
34 made thereunder.

35  
36 **SECTION 10.2 DEVELOPMENT PERMITS IN THE FLOOD HAZARD OVERLAY**  
37 **DISTRICT**

38  
39 A permit is required for all development within the Special Flood Hazard Area. For the  
40 purposes of this Section, development is defined as any man-made change to improved  
41 or unimproved real estate, including but not limited to buildings or other structures,  
42 mining, dredging, filling, grading, paving, excavation or drilling operations or storage of  
43 equipment or materials in accordance with Federal Regulations Title 44 CFR 59.1.

44  
45 **A) Within the Special Flood Hazard Area:**

46 1) Permit required from ZA:

- 1 a) Lake Access Structures
- 2 b) Improvements to existing roads
- 3 c) Non-substantial improvements to existing structures
- 4 d) New or replacement storage tanks for existing structures
- 5 e) Recreational vehicles
- 6
- 7 2) Permit issued after Conditional Use Review by DRB:
- 8 a) Substantial improvements to existing structures
- 9 b) Marinas, Yacht Clubs and Residential Marine Associations
- 10 c) Accessory Structures
- 11 d) Shoreline Stabilization Measures
- 12 e) Bridges, culverts, or public projects which are functionally dependent on lake
- 13 access or crossing
- 14 f) Grading, excavation or the creation of a pond
- 15 g) Public utilities
- 16

17 **C) Prohibited Development throughout Special Flood Hazard Area:**

- 18
- 19 1) The following are prohibited throughout the Special Flood Hazard Area:
- 20 a) Storage of any explosive, flammable, hazardous, toxic, or floatable materials,
- 21 or junk yards,
- 22 b) New residential structures (including the placement of manufactured homes);
- 23 c) New commercial structures;
- 24 d) Critical facilities;
- 25 e) All development not exempted, permitted, conditionally permitted, or allowed
- 26 as a nonconforming use; and,
- 27 f) New fill except where necessary to elevate structures to meet the
- 28 Development Standards.
- 29

30 **SECTION 10.3 APPLICATION REQUIREMENTS**

- 31
- 32 A) In addition to the application requirements in Section 6.1, applications for
- 33 development within the Flood Hazard Area Overlay District shall also include the
- 34 following information:
- 35 1) the location, on the site development plan, and associated elevations of all
- 36 structures, roads, and water supply and wastewater facilities in relation to the
- 37 channel, floodway, and base flood elevations;
- 38 2) a completed FEMA "Elevation Certificate" prepared by a registered surveyor,
- 39 engineer, architect or other official authorized by the state to certify building
- 40 elevations, for any building constructed after the publication of the town's Flood
- 41 Insurance Rate Maps;
- 42 3) where flood-proofing is proposed, a completed FEMA "Flood-proofing Certificate"
- 43 prepared by a registered professional engineer or architect who is authorized by
- 44 the state to certify flood-proofing design and construction;
- 45 5) a description of the extent to which any watercourse will be altered or relocated
- 46 as a result of the proposed development.

- 1 B) Proposals for development within the Special Flood Hazard Area must be submitted  
2 by the ZA or DRB to the Vermont Agency of Natural Resources for comment in  
3 accordance with 24 V.S.A. §4424(D). A zoning application shall not be considered  
4 complete until such comments have been received or 30 days has elapsed since the  
5 application was submitted, whichever is sooner.  
6
- 7 C) If the applicant is seeking a permit for the alteration or relocation of a watercourse,  
8 copies of the application shall also be submitted to the adjacent communities, the  
9 Stream Alteration Engineer at the Vermont Agency of Natural Resources, and the  
10 Army Corps of Engineers. Copies of such notice shall be provided to the State  
11 National Flood Insurance Program (NFIP) Coordinator at the Vermont Agency of  
12 Natural Resources, Department of Environmental Conservation. A permit may be  
13 issued only following receipt of comments from the Vermont Agency of Natural  
14 Resources, or the expiration of 30 days from the date the application was mailed to  
15 the Vermont Agency of Natural Resources, whichever is sooner.  
16

17 **SECTION 10.4 FLOOD HAZARD AREA DEVELOPMENT STANDARDS**  
18

19 **A) All Development:**

- 20 1) All development in the Special Flood Hazard areas shall be reasonably safe from  
21 flooding and:  
22 a) Designed (or modified) and adequately anchored to prevent flotation, collapse,  
23 or lateral movement of the structure during the occurrence of the base flood;  
24 b) Constructed with materials resistant to flood damage;  
25 c) Constructed by methods and practices that minimize flood damage; and  
26 d) Constructed with electrical, heating, ventilation, plumbing and air conditioning  
27 equipment and other service facilities that are designed and/or located so as  
28 to prevent water from entering or accumulating within the components during  
29 conditions of flooding.  
30 e) Adequately drained to reduce exposure to flood hazards.  
31 f) Required to locate any fuel storage tanks (as needed to serve an existing  
32 building in the Special Flood Hazard Zone) a minimum of one foot above the  
33 base flood elevation and be securely anchored to prevent flotation; or storage  
34 tanks may be placed underground, if securely anchored as certified by a  
35 qualified professional.  
36

37 **B) Residential Development:**

- 38 1) New construction and existing buildings to be substantially improved that are  
39 located in the Flood Hazard Areas shall have the lowest floor, including  
40 basement, elevated to or above the base flood elevation.  
41 2) Manufactured homes to be placed and existing manufactured homes to be  
42 substantially improved that are located in a new manufactured home park or  
43 subdivision, outside of a manufactured home park or subdivision, in an  
44 expansion to an existing manufactured home park or subdivision, or in a  
45 manufactured home park or subdivision which has incurred substantial damage  
46 from a flood shall be elevated on a permanent foundation such that the lowest

1 floor of the manufactured home is elevated or above the base flood elevation  
2 and be securely anchored to an adequately anchored foundation system to  
3 resist floatation, collapse, and lateral movement during the occurrence of the  
4 base flood.  
5

6 **C) Non-residential Development:**

- 7 1) New construction located in the Flood Hazard Areas shall have the lowest floor,  
8 including basement, elevated to or above the base flood elevation.  
9 2) Existing buildings to be substantially improved located in the Flood Hazard  
10 Areas shall have the lowest floor, including basement, elevated to or above the  
11 base flood elevation or together with attendant utility and sanitary facilities be  
12 designed so that below the base flood elevation the structure is watertight with  
13 walls substantially impermeable to the passage of water and with structural  
14 components having the capability of resisting hydrostatic and hydrodynamic  
15 loads and effects of buoyancy. (Note: while buildings need only be floodproofed  
16 to the base flood elevation for floodplain management purposes, the building  
17 must be floodproofed to an elevation at least one foot above the base flood  
18 elevation to receive credit for base flood protection for flood insurance rating  
19 purposes.  
20 3) A permit for a building proposed to be floodproofed shall not be issued until a  
21 registered professional engineer or architect has reviewed the structural design,  
22 specifications and plans, and has certified that the design and proposed  
23 methods of construction are in accordance with accepted standards of practice  
24 for meeting the provisions of this subsection.  
25

26 **D) Subdivisions:**

- 27 1) New subdivision developments (including planned unit developments and  
28 manufactured home parks) of more than 5 acres or 50 lots, whichever is less,  
29 shall be designed to assure:  
30  
31 a) Such proposals minimize flood damage within the flood-prone area,  
32 b) public utilities and facilities, such as sewer, gas, electrical, and water systems  
33 are located and constructed to minimize or eliminate flood damage, and  
34 c) adequate drainage is provided to reduce exposure to flood hazards.  
35

36 **E) Enclosed Areas Below the Lowest Floor:**

- 37 1) Enclosed areas below the lowest floor which are subject to flooding shall be  
38 used solely for parking of vehicles, building access, or storage.  
39 2) New construction and existing buildings to be substantially improved with fully  
40 enclosed areas below the lowest floor that are subject to flooding shall be  
41 designed to automatically equalize hydrostatic flood forces on exterior walls by  
42 allowing for the entry and exit of floodwaters.  
43 3) Designs for meeting this requirement must either be certified by a registered  
44 professional engineer or architect or meet or exceed the following minimum  
45 criteria: A minimum of two openings having a total net area of not less than one  
46 square inch for every square foot of enclosed area subject to flooding shall be  
47 provided. The bottom of all openings shall be no higher than one foot above

1 grade. Openings may be equipped with screens, louvers, valves, or other  
2 coverings or devices provided that they permit the automatic entry and exit of  
3 floodwaters.  
4

5 **F) Recreational Vehicles:** Recreational Vehicles placed on sites with special flood  
6 hazard areas shall either:

- 7 1) be on the site for fewer than 180 consecutive days,
- 8 2) be fully licensed and ready for highway use, or
- 9 3) be permitted in accordance with the elevation and anchoring requirements for  
10 "manufactured homes" in section 10.4 B(2).  
11

12 **G) Accessory Structures Lake Access Structures:** Small accessory buildings and  
13 lake access structures that represent a minimal investment need not be elevated to  
14 the base flood elevation provided the structure meets the following requirements:

- 15 1) The structure must only be used for parking, storage, or lake access;
- 16 2) The structure must have the required openings to allow floodwaters in and out,
- 17 3) The structure must be constructed using flood resistant materials below the  
18 Base Flood Elevation,
- 19 4) The structure must be adequately anchored to resist flotation, collapse, and  
20 lateral movement, and
- 21 5) All building utility equipment including electrical and heating must be elevated or  
22 floodproofed.  
23

24 **H) Water Supply Systems:** New and replacement water supply systems shall be  
25 designed to minimize or eliminate infiltration of flood waters into the systems.  
26

27 **I) Sanitary Sewage Systems:** New and replacement sanitary sewage systems shall  
28 be designed to minimize or eliminate infiltration of flood waters into the systems and  
29 discharges from the systems into flood waters.  
30

31 **J) On-Site Waste Disposal Systems:** On-site wastewater disposal systems shall be  
32 located to avoid impairment to them or contamination from them during flooding.  
33

34 **K) Watercourse Carrying Capacity:** The flood carrying capacity within any altered or  
35 relocated portion of a watercourse shall be maintained.  
36

## 37 **SECTION 10.5 STANDARDS FOR REVIEW OF NONCONFORMING STRUCTURES.** 38

39 **A)** The DRB may approve the repair, relocation, replacement, or enlargement of a  
40 nonconforming structure within a regulated flood or other hazard area, subject to  
41 compliance with applicable federal and state laws and regulations, and provided that  
42 the following criteria are met:

- 43 1) The DRB finds that the repair, relocation, or enlargement of the nonconforming  
44 structure is required for the continued economically feasible operation of a  
45 nonresidential enterprise.

- 2) The DRB finds that the repair, relocation, or enlargement of the nonconforming structure will not increase flood levels in the regulatory floodway, increase the risk of other hazard in the area, or threaten the health, safety, and welfare of the public or other property owners.
- 3) The permit so granted states that the repaired, relocated, or enlarged nonconforming structure is located in a regulated flood or other hazard area, does not conform to the regulations pertaining to that area, and will be maintained at the risk of the owner.

**SECTION 10.6 VARIANCES TO THE DEVELOPMENT STANDARDS.**

Variations shall be granted by the DRB only in accordance with 24 V.S.A. § 4469 and in accordance with the criteria for granting variations found in 44 CFR, Section 60.6, of the National Flood Insurance Program regulations. A decision in favor of the appellant shall be granted if all the following facts are found, and the supporting findings are specified in the decision:

- A) Variations are generally limited to a lot size less than one-half acre relating to historical structures (provided the proposed repair or rehabilitation will not preclude the structure’s continued designation as an historic structure), or a necessary development functionally dependent on stream access;
- B) The variance, if authorized shall be issued by the DRB only upon:
  - 1) Determination that failure to grant the variance would result in exceptional hardship to the applicant; and,
  - 2) Determination that the variance will not result in increased flood heights, increased susceptibility to flooding or erosion, additional threats to public safety or infrastructure (including emergency services during flood events), or extraordinary public expense;
  - 3) The variance will not increase the potential of materials being swept onto other lands or into the stream and causing damage to others;
- C) The variance if granted will represent the minimum variance that will afford relief and will represent the least deviation possible from the bylaw and from the plan;
- D) Any variance issued will inform the applicant in writing over the signature of a community official that the issuance of a variance to construct a structure below the base flood elevation increases risk to life and property and will result in increased flood insurance premiums up to amounts as high as \$25 for \$100 of coverage. Such notification shall be maintained with a record of all variance actions.

**SECTION 10.7 RECORDING REQUIREMENTS**

The ZA shall maintain a record of development within the Flood Hazard Area Overlay District including:

- 1 A) All permits issued for development in areas of special flood hazard;
- 2 B) The elevation, in relation to mean sea level, of the lowest floor, including basement,
- 3 of all new or substantially improved buildings;
- 4 C) The elevation, in relation to mean sea level, to which buildings have been
- 5 floodproofed;
- 6 D) All flood proofing certifications required under this regulation; and
- 7 E) All variance actions, including justification for their issuance.

## 8

### 9 **SECTION 10.8 VIOLATION OF FLOOD HAZARD AREA REGULATIONS**

- 10
- 11 A) Where a violation of the Flood Hazard Overlay District standards and regulations
- 12 has not been cured after a warning notice has been sent in accordance with the Act,
- 13 the ZA shall submit a declaration to the Administrator of the NFIP requesting a
- 14 denial of flood insurance. Section 1316 of the National Flood insurance Act of 1968,
- 15 as amended, authorizes FEMA to deny flood insurance to a property declared by a
- 16 community to be in violation of their flood hazard area regulations. The declaration
- 17 shall consist of:
- 18 1) The name of the property owner and address or legal description of the property
  - 19 sufficient to confirm its identity or location,
  - 20 2) A clear and unequivocal declaration that the property is in violation of a cited
  - 21 State or local law, regulation, or ordinance,
  - 22 3) A clear statement that the public body making the declaration has authority to do
  - 23 so and a citation to that authority,
  - 24 4) Evidence that the property owner has been provided notice of the violation and
  - 25 the prospective denial of insurance, and
  - 26 5) A clear statement that the declaration is being submitted pursuant to Section
  - 27 1316 of the National Flood Insurance Act of 1968, as amended.
- 28

### 29 **SECTION 10.9 FLOOD HAZARD DEFINITIONS**

30

31 Definitions in this section apply only to the Flood Hazard Regulations in this article.

32 Additional definitions are found in Article 11.

33

34 **AREA OF SPECIAL FLOOD HAZARD:** Special flood hazard area.

35

36 **BASE FLOOD:** The flood having a one percent chance of being equaled or exceeded in

37 any given year (commonly referred to as the 100-year flood).

38

39 **BASE FLOOD ELEVATION (BFE):** The height of the base flood, usually in feet, in

40 relation to the National Geodetic Vertical Datum of 1929, the North American Vertical

41 Datum of 1988, or other datum referenced in the Flood Insurance Study report, or

42 average depth of the base flood, usually in feet, above the ground surface.

43

44 **BASEMENT:** Any area of the building having its floor elevation below ground level on all

45 sides. A "walk-out" basement whose floor is at ground level on at least one side of the

1 house, usually with a door on that side is not considered a "basement" for the purpose  
2 of the flood hazard regulations.

3  
4 **COMMON PLAN OF DEVELOPMENT:** Where a structure will be refurbished over a  
5 period of time. Such work might be planned unit by unit.

6  
7 **CRITICAL FACILITIES:** Include police stations, fire and rescue facilities, hospitals,  
8 shelters, schools, nursing homes, water supply and waste treatment facilities, and other  
9 structures the community identifies as essential to the health and welfare of the  
10 population and that are especially important following a disaster. For example, the type  
11 and location of a business may raise its status to a Critical Facility, such as a grocery or  
12 gas station that survive a flood and now are the only points for food and gas.

13  
14 **DEVELOPMENT:** Any human-made change to improved or unimproved real estate,  
15 including but not limited to buildings or other structures, mining, dredging, filling,  
16 grading, paving, excavation or drilling operations or storage of equipment or materials.

17  
18 **EXISTING MANUFACTURED HOME PARK OR SUBDIVISION:** A manufactured home  
19 park or subdivision for which the construction of facilities for servicing the lots on which  
20 the manufactured homes are to be affixed (including, at a minimum, the installation of  
21 utilities, the construction of streets, and either final site grading or the pouring of  
22 concrete pads) is completed before the effective date of the initial floodplain  
23 management regulations adopted by a community.

24  
25 **EXPANSION TO AN EXISTING MANUFACTURED HOME PARK OR SUBDIVISION:**  
26 The preparation of additional sites by the construction of facilities for servicing the lots  
27 on which the manufacturing homes are to be affixed (including the installation of utilities,  
28 the construction of streets, and either final site grading or the pouring of concrete pads).

29  
30 **FILL:** Any placed material that changes the natural grade, increases the elevation, or  
31 diminishes the flood storage capacity at the site.

32  
33 **FLOOD:** (a) A general and temporary condition of partial or complete inundation of  
34 normally dry land areas from: the overflow of inland or tidal waters; the unusual and  
35 rapid accumulation or runoff of surface waters from any source; and mudslides which  
36 are proximately caused by flooding and are akin to a river of liquid and flowing mud on  
37 the surfaces of normally dry land areas, as when earth is carried by a current of water  
38 and deposited along the path of the current. (b) The collapse or subsidence of land  
39 along the shore of a lake or other body of water as a result of erosion or undermining  
40 caused by waves or currents of water exceeding anticipated cyclical levels or suddenly  
41 caused by an unusually high water level in a natural body of water, accompanied by a  
42 severe storm, or by an unanticipated force of nature, such as flash flood or abnormal  
43 tidal surge, or by some similarly unusual and unforeseeable event which results in  
44 flooding.

45  
46 **FLOOD INSURANCE RATE MAP (FIRM):** An official map of a community, on which the  
47 Federal Insurance Administrator has delineated both the special flood hazard areas and

1 the risk premium zones applicable to the community. In some communities the hazard  
2 boundaries are available in paper, pdf, or Geographic Information System formats as a  
3 Digital Flood Insurance Rate Map (DFIRM).

4  
5 **FLOOD INSURANCE STUDY:** An examination, evaluation and determination of flood  
6 hazards and, if appropriate, the corresponding water surface elevations or an  
7 examination, evaluation and determination of mudslide (i.e., mudflow) and /or flood  
8 related erosion hazards.

9  
10 **FLOODPLAIN OR FLOOD-PRONE AREA:** Any land area susceptible to being  
11 inundated by water from any source (see definition of "flood").

12  
13 **FLOOD PROOFING:** Any combination of structural and non-structural additions,  
14 changes, or adjustments to structures which reduce or eliminate flood damage to real  
15 estate or improved real property, water and sanitary facilities, structures and their  
16 contents.

17  
18 **FLOODWAY:** The channel of a river or other watercourse and the adjacent land areas  
19 that must be reserved in order to discharge the base flood without cumulatively  
20 increasing the water surface elevation more than one foot at any point. Please note that  
21 where the Special Flood Hazard Areas have established base flood elevations, the  
22 extent of FEMA floodways may be shown on a separate series of panels

23  
24 **FLOODWAY, REGULATORY IN THE TOWN OF NORTH HERO:** The regulatory  
25 floodway in of the Town of North Hero is the channel of a river or other watercourse and  
26 the adjacent land areas that must be reserved in order to discharge the base flood  
27 without cumulatively increasing the water surface elevation more than one foot at any  
28 point.

29  
30 **FUNCTIONALLY DEPENDENT USE:** A use which cannot perform its intended purpose  
31 unless it is located or carried out in close proximity to water.

32  
33 **HISTORIC STRUCTURE:** Any structure that is: (a) listed individually in the National  
34 Register of Historic Places (a listing maintained by the Department of the Interior) or  
35 preliminarily determined by the Secretary of the Interior as meeting the requirements for  
36 individual listing on the National Register; (b) certified or preliminarily determined by the  
37 Secretary of the Interior as contributing to the historical significance of a registered  
38 historic district or a district preliminarily determined by the Secretary to qualify as a  
39 registered historic district; (c) individually listed on a state inventory of historic places in  
40 states with historic preservation programs which have been approved by the Secretary  
41 of the Interior; or (d) individually listed on a local inventory of historic places in  
42 communities with historic preservation programs that have been certified either: (i) by  
43 an approved state program as determined by the Secretary of the Interior or (ii) directly  
44 by the Secretary of the Interior in states without approved programs.

45  
46 **LETTER OF MAP AMENDMENT (LOMA):** A letter issued by the Federal Emergency  
47 Management Agency officially removing a structure or lot from the flood hazard zone

1 based on information provided by a certified engineer or surveyor. This is used where  
2 structures or lots are located above the base flood elevation and have been  
3 inadvertently included in the mapped special flood hazard area.  
4

5 **LOWEST FLOOR:** The lowest floor of the lowest enclosed area (including basement).  
6 An unfinished or flood resistant enclosure, usable solely for parking of vehicles, building  
7 access or storage in an area other than a basement area is not considered a building's  
8 lowest floor; provided, that such enclosure is not built so as to render the structure in  
9 violation of the applicable non-elevation design requirements of 44 CFR §60.3.  
10

11 **MANUFACTURED HOME:** A structure, transportable in one or more sections, which is  
12 built on a permanent chassis and is designed for use with or without a permanent  
13 foundation when attached to the required utilities. The term "manufactured home" does  
14 not include a "recreational vehicle".  
15

16 **MINOR IMPROVEMENT:** Any repairs, reconstruction, or improvement of a structure  
17 (other than customary maintenance), the cost of which is less than fifty (50) percent of  
18 the market value of the existing structure.  
19

20 **NEW CONSTRUCTION:** Structures for which the start of construction commenced on  
21 or after the effective date of the floodplain management regulation adopted by a  
22 community and includes any subsequent improvements to such structures. For the  
23 purposes of determining insurance rates, "new construction" means structures,  
24 including manufactured homes, for which the "start of construction" commenced on or  
25 after the effective date of an initial FIRM or after December 31, 1974, whichever is later,  
26 and includes any subsequent improvements to such structures.  
27

28 **NON-RESIDENTIAL:** Includes, but is not limited to: small business concerns, churches,  
29 schools, nursing homes, farm buildings (including grain bins and silos), pool houses,  
30 clubhouses, recreational buildings, government buildings, mercantile structures,  
31 agricultural and industrial structures, and warehouses.  
32

33 **RECREATIONAL VEHICLE:** A vehicle which is: (a) Built on a single chassis; (b) 400  
34 square feet or less when measured at the largest horizontal projection; (c) Designed to  
35 be self-propelled or permanently towable by a light duty truck; and (d) Designed  
36 primarily not for use as a permanent dwelling but as a temporary living quarters for  
37 recreational, camping, travel, or seasonal use.  
38

39 **SPECIAL FLOOD HAZARD AREA:** The floodplain within a community subject to a 1  
40 percent or greater chance of flooding in any given year. For purposes of these  
41 regulations, the term "area of special flood hazard" is synonymous in meaning with the  
42 phrase "special flood hazard area". This area is usually labeled Zone A, AO, AH, AE, or  
43 A1-30 in the most current flood insurance studies and on the maps published by the  
44 Federal Emergency Management Agency. Maps of this area are available for viewing in  
45 the town office or online from the FEMA Map Service Center: [msc.fema.gov](http://msc.fema.gov). Base flood  
46 elevations have not been determined in Zone A where the flood risk has been mapped  
47 by approximate methods. Base flood elevations are shown at selected intervals on

1 maps of Special Flood Hazard Areas that are determined by detailed methods. Please  
2 note, where floodways have been determined they may be shown on separate map  
3 panels from the Flood Insurance Rate Maps.  
4

5 **START OF CONSTRUCTION:** Includes substantial improvement, and means the date  
6 the building permit was issued provided the actual start of construction, repair,  
7 reconstruction, rehabilitation, addition placement, or other improvement was within 180  
8 days of the permit date. The actual start means either the first placement of permanent  
9 construction of a structure on a site, such as the pouring of slab or footings, the  
10 installation of piles, the construction of columns, or any work beyond the stage of  
11 excavation; or the placement of a manufactured home on a foundation. Permanent  
12 construction does not include land preparation, such as clearing, grading and filling; nor  
13 does it include the installation of streets and/or walkways; nor does it include excavation  
14 for a basement, footing, piers, or foundations or the erection of temporary forms; nor  
15 does it include the installation on the property of accessory buildings, such as garages  
16 or sheds not occupied as dwelling units or not part of the main structure. For a  
17 substantial improvement, the actual start of construction means the first alteration of any  
18 wall, ceiling, floor, or other structural part of a building, regardless whether that  
19 alteration affects the external dimensions of the building.  
20

21 **STRUCTURE:** A walled and roofed building, as well as a manufactured home, and any  
22 related built systems, including a gas or liquid storage tanks.  
23

24 **SUBSTANTIAL DAMAGE:** Damage of any origin sustained by a structure whereby the  
25 cost of restoring the structure to its before-damaged conditions would equal or exceed  
26 50 percent of the market value of the structure before the damage occurred.  
27

28 **SUBSTANTIAL IMPROVEMENT:** Any reconstruction, rehabilitation, addition, or other  
29 improvement of a structure after the date of adoption of these regulations, the cost of  
30 which, over three years, or over a the period of a common plan of development,  
31 cumulatively equals or exceeds 50 percent of the market value of the structure before  
32 the "start of construction" of the improvement. This term includes structures which have  
33 incurred "substantial damage", regardless of the actual repair work performed. The  
34 term does not, however, include either: (a) Any project for improvement of a structure to  
35 correct existing violations of state or local health, sanitary, or safety code specification  
36 which have been identified by the local code enforcement official and which are the  
37 minimum necessary to assure safe living conditions or (b) Any alteration of a "historic  
38 structure", provided that the alteration will not preclude the structure's continued  
39 designation as a "historic structure."  
40

41 **VIOLATION:** The failure of a structure or other development to be fully compliant with  
42 these regulations. A structure or other development without the elevation certificate,  
43 other certifications, or other evidence of compliance required in Federal Regulation 44  
44 CFR 60.3 is presumed to be in violation until such time as that documentation is  
45 provided.  
46

1 **ARTICLE 11: GENERAL DEFINITIONS**

---

2  
3 Except where specifically defined herein, all words used in these Regulations shall carry  
4 their customary meanings. The word "shall" is mandatory and the word "may" is  
5 permissive. Where doubt exists as to the precise meaning of any word or words in  
6 these Regulations, the DRB shall rule on the interpretation.

7  
8 **ACCESSORY STRUCTURE/USE:** See Structure/Use, Accessory.

9  
10 **BED AND BREAKFAST:** Overnight accommodations and a morning meal in a single  
11 family residence provided to transients for compensation.

12  
13 **BUILDING:** Any structure having a roof supported by columns or walls intended for the  
14 shelter, housing, or enclosure of any individual, animal, process, equipment, goods, or  
15 materials of any kind.

16  
17 **BUILDING, ACCESSORY:** See Structure, Accessory.

18  
19 **CAMPGROUND:** A recreational campground or camping park where transient  
20 residence is offered or provided for seasonal or short-term vacation or recreational  
21 purposes on which may be located cabins, tents, or lean-tos, or campsites designed for  
22 temporary set-up of portable or mobile camping, recreational, or travel dwelling units  
23 including tents, campers, and recreational vehicles such as motor homes, travel trailers,  
24 truck campers, and van campers.

25  
26 **CASUAL SALES (GARAGE SALE):** The occasional (not more than six (6) days per  
27 year) sale of goods on one's own residential property. Casual sale includes garage  
28 sales, yard sales, lemonade stands, and the like.

29  
30 **COMMERCIAL USE:** An activity involving the sale of goods or services carried out for  
31 profit.

32  
33 **CONGREGATE CARE FACILITY:** A facility licensed by the state which provides  
34 primarily non-medical residential care services to 9 or more individuals in need of  
35 personal assistance essential for sustaining the activities of daily living, or for the  
36 protection of the individual, excluding members of the resident family or persons  
37 employed by the facility, on a 24-hour a day basis. See also Personal or Professional  
38 Service.

39  
40 **DAYCARE CENTER:** Any establishment, whether providing services in-home or in a  
41 separate non-residential facility, providing childcare service on a regular or continual  
42 basis for a fee and does not meet the definition of a Family Childcare Home. See also  
43 Personal or Professional Service.

44  
45 **DOCK:** A wharf, pier, or other structure permanently or temporarily anchored to the  
46 shore and projecting into the Lake.

1  
2 **DWELLING, SINGLE FAMILY:** A structure containing one dwelling unit.

3  
4 **DWELLING, TWO FAMILY:** A structure containing two dwelling units, including units  
5 that are located one over the other and units in a row separated by one or more vertical  
6 common fire resistant walls.

7  
8 **DWELLING, MULTI-FAMILY:** A structure containing three or more dwelling units,  
9 including units that are located one over the other and units in a row separated by one  
10 or more vertical common fire resistant walls.

11  
12 **DWELLING, ACCESSORY:** An efficiency or one bedroom apartment located within or  
13 appurtenant to a single family dwelling, that is clearly subordinate to a single family  
14 dwelling, and has facilities and provisions for independent living, including sleeping,  
15 food preparation, and sanitation.

16  
17 **EARTH RESOURCE EXTRACTION:** The commercial extraction of minerals, including  
18 solids such as sand and gravel, liquids such as water, and gases such as natural gas.  
19 It may also include preparation activities such as crushing and washing customarily part  
20 of earth resource extraction activities. See also Light Industry.

21  
22 **FAMILY CHILDCARE HOME:** A business providing childcare service within the  
23 provider's place of residence to not more than 6 full time children and 4 part time  
24 children on a regular or continual basis for a fee, which is considered to constitute a  
25 permitted single family residential use of property.

26  
27 **FENCE:** An artificially constructed barrier of any material or combination of materials  
28 erected to enclose, screen or separate areas.

29  
30 **GAS / MOTOR VEHICLE SERVICE STATION:** Any building, land area or other  
31 premises, or portion thereof, used for the retail dispensing or sales of vehicular fuels  
32 and/or the servicing and repair of automobiles.

33  
34 **GROUP HOME:** A state licensed or registered residential care home serving not more  
35 than 8 persons who are handicapped or developmentally disabled as defined in 9  
36 V.S.A. §4501. In accordance with the Act [§4412G], such a group home shall be  
37 considered by right to constitute a permitted single family residential use of property,  
38 except that no such home shall be so considered if it is located within 1,000 feet of  
39 another such home.

40  
41 **HOME BUSINESS:** Home Business is a use of an accessory building or portion of a  
42 dwelling for a business which exhibits no apparent indications that a business exists.  
43 Uses otherwise listed in Table 5.1 may qualify as a Home Business if they meet the  
44 requirements of Section 8.9.

45  
46 **HOME OCCUPATION:** Use of a portion of a residential lot by a resident for an  
47 occupational business with not more than one non-family full time equivalent employee,

1 and which could normally be expected to be customarily located in the area and that will  
2 not change the character of the neighborhood. Home Occupations do not generate  
3 more than an average of 10 vehicle trips per weekday. Uses otherwise listed in Table  
4 5.1 may qualify as a Home Occupation if they meet the requirements of Section 8.9.

5  
6 **LAKE ACCESS STRUCTURE:** A stairway or pedestrian ramp, boat launch ramp, dock  
7 or other structure constructed to gain access to the lakeshore.

8  
9 **LAND DEVELOPMENT:** The division of a parcel into two (2) or more parcels; the new  
10 construction, reconstruction, conversion, structural alteration, relocation, or enlargement  
11 of any building or other structure; any mining or earth resource extraction; or any  
12 change in the use of any building, other structure, or land, or extension of the use of  
13 land.

14  
15 **LAND USE.** How a parcel of land, including any structures located thereon, is being  
16 used. Table 5.1 identifies different types of land uses.

17  
18 **LAND USE, ACCESSORY:** See Structure, Accessory.

19  
20 **LAND USE, PRINCIPAL:** A use directly involved with the primary purpose of ownership  
21 on a particular lot.

22  
23 **LIGHT INDUSTRY:** A light industrial facility that meets the performance standards and  
24 any other applicable standards in these Regulations, including such uses as  
25 manufacturing, wholesale trade, saw mills, slaughter houses, and earth resource  
26 extraction.

27  
28 **LODGING ESTABLISHMENT:** Building or buildings containing rooms which are rented  
29 for money or other compensation as sleeping units for transients, each sleeping unit  
30 consisting of, at the least, a bedroom and a bathroom (shared bathrooms are also  
31 permitted).

32  
33 **LOT:** See Parcel.

34  
35 **LOT SIZE:** The total area within the lot lines of a lot, including any road rights-of-way.

36  
37 **LOT FRONTAGE:** The length of the lot line measured at the road right-of-way line.

38  
39 **LOT WIDTH:** The horizontal distance between the side lines of a lot measured at right  
40 angles to its depth along a straight line parallel to the road frontage at the minimum  
41 required setback line.

42  
43 **LOT COVERAGE:** The portion of a lot that is covered by buildings measured as the  
44 ratio of the building footprint area to the total lot area.

45  
46 **MARINA:** A business whose purpose is the sale, servicing, launching, or rental of boats  
47 and/or the sale or rental of moorings or docking berths. A marina may also include

1 services ancillary to the marina operation such as retail, repair, food, laundry facilities,  
2 etc.

3  
4 **MOBILE HOME PARK:** Any parcel of land under single or common ownership or  
5 control which contains, or is designed, laid out, or adapted to accommodate, more than  
6 two mobile homes. Mobile home park does not mean land or premises used solely for  
7 storage or display of mobile homes; nor any parcel of land under the ownership of an  
8 agricultural employer who may provide up to four mobile homes used by full-time  
9 workers or employees of the agricultural employer as a benefit or condition of  
10 employment; nor any parcel of land used solely on a seasonal basis for vacation or  
11 recreational mobile homes. See also Campground.

12  
13 **MOTOR VEHICLE SALES:** The use of any building, land area, or other premises for  
14 the display and sale of new or used automobiles generally but may include light trucks  
15 or vans, trailers, or recreation vehicles and including any vehicle preparation or repair  
16 work conducted as an accessory use. Also included is the sale of modular or mobile  
17 homes.

18  
19 **PARCEL:** A contiguous lot or tract of land owned and recorded as the property of the  
20 same person(s) or controlled by a single entity.

21  
22 **PERSONAL OR PROFESSIONAL SERVICE:** Establishment primarily engaged in  
23 providing assistance or providing services involving the care of a person or of a persons  
24 goods or apparel, such as salons and barbershops, laundromats and dry cleaners, linen  
25 supply, shoe repair, funeral services, health clubs, clothing rental, lawyer's office,  
26 accountant's office, engineer's office, kennels, veterinary offices, automobile repair, and  
27 other professional services and offices. Also includes congregate care facility, daycare  
28 center, and healthcare office or facility.

29  
30 **PLACE OF WORSHIP:** A special purpose building that is architecturally designed and  
31 particularly adapted for the primary use of conducting on a regular basis formal religious  
32 services by a religious congregation.

33  
34 **PUBLIC OR SEMI PUBLIC FACILITIES:** A building or other facility owned, leased,  
35 held, used, and/or controlled exclusively for public or semi-public purposes by a  
36 municipality, state or federal government, regulated utility or railroad. Such facilities  
37 include, but are not limited to municipal buildings and garages, water and wastewater  
38 facilities, and educational facilities. This definition also includes uses in Title 24 V.S.A.  
39 § 4413(a).

40  
41 **PRINCIPAL USE/STRUCTURE:** See Structure/Use, Principal.

42  
43 **RECREATIONAL FACILITIES:** An area of land or enclosed structure designed and  
44 equipped for the conduct of sports and leisure time activities as a commercial or public  
45 establishment. Includes golf course, golf driving range, trap, skeet, and archery range,  
46 swimming pool, skating rink, tennis court, riding stable, park, beach, recreation stadium,  
47 skiing, indoor bowling alleys, theaters, table tennis and pool halls, skating rinks,

1 gymnasiums, swimming pools, hobby workshops, and similar places of indoor  
2 commercial recreation.

3  
4 **RESIDENTIAL MARINE ASSOCIATION:** Any commonly held shoreline property which  
5 is a common element of or an appurtenance to a residential development on the same  
6 or adjacent property that provides access to the shoreline for more than 2 residences.

7  
8 **RESTAURANT:** Establishment where food and beverage are prepared and served in a  
9 form ready for consumption, which may be consumed on or off-site.

10  
11 **RETAIL SALES:** Establishments engaged in selling goods or merchandise to the  
12 general public and rendering services incidental to the sale of such goods.

13  
14 **SETBACK (YARD AND ROAD):** The distance between any land development and any  
15 lot line.

16  
17 **SETBACK (LAKE, STREAM OR WETLAND):** The distance between any land  
18 development and the top of the natural bank of Lake Champlain or any stream, or the  
19 edge of a wetland.

20  
21 **SOLAR ARRAY:** A system which uses one or more solar panels to convert sunlight  
22 into electricity. It consists of multiple components, including photovoltaic modules,  
23 mechanical and electrical connections and mountings and means of regulating and/or  
24 modifying the electrical output. Solar arrays are typically either freestanding or mounted  
25 on an existing structure.

26  
27 **STORAGE FACILITIES:** A structure containing self-service separate, individual and  
28 private storage spaces of varying sizes leased or rented on individual leases for varying  
29 periods of time.

30  
31 **STRUCTURAL ALTERATION:** Any change in either the supporting members of a  
32 building, such as bearing walls, columns, beams, and girders, or in the dimensions or  
33 configurations of the roof or exterior walls.

34  
35 **STRUCTURE:** A combination of materials to form a construction for use, occupancy, or  
36 ornamentation whether installed on, above, or below the surface of land or water.  
37 Structures include but are not limited to buildings, signs, fences, carports, porches,  
38 patios, swimming pools, freestanding solar arrays, freestanding towers, and lean-tos.  
39 Specifically not included are sidewalks, driveways, underground utilities, and softscape  
40 landscaping such as trees, plants, groundcover, and mulching.

41  
42 **STRUCTURE/USE, ACCESSORY:** An incidental or subordinate structure and/or use  
43 that is secondary or ancillary to the primary use of the same lot. Accessory structures  
44 include garages, sheds, barns, pump houses, and other out buildings, antennae,  
45 towers, swimming pools, and other structures  
46

- 1 **STRUCTURE/USE, PRINCIPAL:** A use and/or structure directly involved with the  
2 primary purpose of ownership on a particular lot.  
3
- 4 **STRUCTURE/USE, TEMPORARY:** A use and/or structure established for a limited  
5 duration with the intent to discontinue that use upon the expiration of a specified time  
6 period.  
7
- 8 **TRAVEL TRAILER PARK/CAMP:** See Campground.  
9
- 10 **WIND ENERGY GENERATION SYSTEM (SMALL OFF-GRID):** A wind energy  
11 generation system consisting of a wind turbine, a tower, and associated control or  
12 conversion electronics, which has a rated capacity of not more than 100 kW and that is  
13 not connected to the electric utility system grid and therefore not a net-metered system.  
14
- 15 **YACHT CLUB:** A facility similar to a marina but operated on a non-profit basis for the  
16 benefit of members or associates. The land may be held or controlled by either an  
17 individual or a business entity. A yacht club may also include services ancillary to the  
18 yacht club such as retail, repair, food, laundry facilities, etc.  
19
- 20 **YOUTH CLUB OR CAMP:** Parcel used wholly or partially for education or recreation  
21 exclusively for members or accommodating five or more children under the age of 18 for  
22 a period of or portion of two or more days.  
23
- 24 **WIRELESS TELECOMMUNICATIONS FACILITY:** A tower or other support structure,  
25 including antennae, related equipment, and base structures, which will extend 20 or  
26 more feet vertically, and be used primarily for communication or broadcast purposes to  
27 transmit or receive, communicate on or broadcast signals.  
28  
29  
30  
31  
32