



## Cover Sheet

### Please complete this page ONCE and return with your Grant Category Application(s)

Town/Organization:

Huntington

Primary Contact Person:

Barbara Elliott, Town Administrator

Address:

4930 Main Road, Huntington VT 05462

Primary Contact Person Email:

townhunt@gmavt.net Phone: (802) 434-4779

SAM unique ID #:

5WGE7

Fiscal Year End Month (MM): 06

Town Clerk / Admin email:

Heidi Racht, huntingtonclerk@gmavt.net

Road Foreman Name:

Clinton 'Yogi' Alger, huntington.vt.roads@gmail.com





## CATEGORY B/C/D

Please complete one application per project you are applying for.

Please check the C	ategory you are	applying for
--------------------	-----------------	--------------

В.	Corre	ction	of a	Road	Related	d E	ros	ion	Problem	and/	or	Sto	orm	water	Mitigation
 _	_		c	٥.	- 1			~ 1		_					

C. Correction of a Stream Bank, Lake Shore or Slope Related Problem

X D. Structure/culvert 36" diameter or greater

Municipality: Town of Huntington

Road Name: Handy Road TH #: 14 Structure # (if applicable): # 25

Road Type: Unpaved Road Class: 3

### Description of the erosion/water quality problem

This large culvert on Handy Road serves as a crossing over Fargo Brook, which feeds directly into the Huntington River. It was the most critical finding from a hydraulic capacity standpoint according to the Town's 2021 McFarland Johnson bridge capital development plan. "The culvert exhibits signs of initial failure, with numerous locations of interior deformation along the culvert length. This results in a reduced hydraulic opening, creating an increase chance of debris accumulation within the CMP and developing a dam effect which could seriously affect Handy Road." The slope of the roadway segment (108,311.00) at the culvert is 4.67%, which is located just below the road's steepest segment (108,312.00) at a slope of 11.64%.

The initial REI assessment of Handy Road was 'does not meet' with a priority ranking of 'very high'. The Town Road Crew has completed all work on Handy Road to bring all segments into compliance with the MRGP standards, with the exception of the culvert replacement. Completing this project will complete the job of protecting this area of Fargo Brook from further erosion and sedimentation.

Has the town completed an MRGP compliant road erosion inventory? Yes

Project Length (linear feet along roadway): n/a


Number of structures/culverts replaced/repaired: Grant is to replace 1 culvert

Average slope of roadway: The slope on Handy Road ranges from 0.35% to 11.64%





Provide a VERY detailed map of project location showing start and end points: Included Provide a sketch of project location showing distances and project details: Included









Please provide the Road Segment ID (RSID) for your project. If several, please list all. In addition to the RSID please indicate what the resulting rating of each segment before construction as well as after construction in accordance with the MRGP.\* (i.e., Fully Meets Standard, Partially Meets, Does Not Meet) For assistance, please contact Better Roads Staff (802)828-4585.

	Hydro	logically ected?		onstruction Conformanc		Post-	st-construction MRGP Conformance			
	Conn	T								
DCID	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		Fully	Partially	Does Not	Fully	Partially	Does Not		
RSID	Yes	No	Meets	Meets	Meet	Meets	Meets	Meet		
108,311.00	Х				X					
			-							
1 10000										
V						****				
300MM-1						s metalonomia ta de				
MANAGER BY AND ADDRESS OF THE PARTY OF THE P										
*****										
-7490-00										
MANGOO		WA 77-100								





\*In order to "Fully Meet" the standards the road segment must have proper crown, removal of shoulder berms, proper ditching, proper conveyance and no erosion present at culvert inlets and outlets.

Environmental Concerns:

All projects require a review of potential impacts by our environmental team. To expedite the review process, please check the boxes below that describe existing structures/conditions to be replaced/maintained (if any) and the project description that applies (if any).

Existing Structures:							
Steel/Plastic Culvert	Concrete Box Culvert						
Stone Culvert – Take pictures	☐ Concrete Bridge						
☐ Ditch	Rolled Beam/Plate Girder Bridge						
Foundation remains, mill ruins, stone walls, other –	Stone abutments or piers – Take pictures						
Take pictures							
Buildings within 300 feet of work - <b>Take pictures</b>							
Project De	scription:						
New ditches will be established	All work will be completed from the existing						
	road or shoulder						
Reestablishing existing ditches only	There will be excavation within 300 feet or a						
	river or stream – <b>Take pictures</b>						
▼ The structure is being replaced on existing	Road reclaiming, reconstruction, or widening						
location/alignment							
Excavation within a floodplain – <b>Take pictures</b>	Temporary off-road access is required						
Tree cutting/clearing – Take pictures	The roadway will be realigned						

Please describe the project and how it will create a positive water quality benefit (ex. Reshape 500' of ditch and line with 12 inch minus stone, to prevent sediment from entering the Lamoille River at the bottom of the hill): The project will be to replace the existing damaged and undersized 6' culvert with a 12' steel culvert in order to reestablish better water flow and eliminate erosion.

Please list any professionals or partners that assisted with planning this project (ANR River Management Engineer, Army Corps of Engineers, VTrans staff, Basin Planner, RPC staff, etc.):

- McFarland-Johnson, Inc. (Engineering Consultant)
- Chittenden County Regional Planning Commission
- Jaron Borg, ANR River Management Engineer
- Tim Parent, Parent Construction

Is the project located in the town "Right of Way? (select one)









Please be aware, Municipalities are required to have an Agreement for Entry & Liability Release for any impacted properties (prior to the start of construction.)

<b>Budget:</b>									
Please attach a project budget and confirm below that is attached:									
Project budget IS attached									
Are you applying to other grant programs to Better Roads requires a 20% <u>local</u> match and federally funded programs.		If so, what programs? Please note that may not be used as match for other state or							
Requested Grant Amount: + Local Match:	\$ 60,000.00 \$ <b>55,508.10</b>	Requested Grant Amount Max: \$20,000 Category B \$40,000 Category C \$60,000 Category D							
= Total Project Cost:	\$ 115,508.10	See page 6 for more information or calculating match							
Estimated Completion Date: August 30, 2024									
REQUIRED ATTACHMENTS:									
Please use the documentation checklist below have been included. It is preferred that your a									
<ul> <li>□ Grant application cover sheet</li> <li>□ Grant application form, including characteristics</li> <li>□ completion</li> </ul>	art with RSID and MRG	P compliance before and after project							
Itemized Cost estimate for labor, equipment, and materials (see enclosed Cost Estimate Worksheet). If applicable, please break down funding by source (i.e. different grant sources).									
<ul> <li>Detailed Project Location Map</li> <li>Sketch of proposed project and erosion control measures or other management practices, including distances in feet</li> </ul>									
<ul> <li>Also show approximate location of town/other right-of-way and/or property lines and limits of work</li> </ul>									
<ul> <li>Photos must be color and clear to see.</li> <li>Please make sure there are enough photos to get a good idea of the project area</li> </ul>									
<ul> <li>Other appropriate supporting docume</li> </ul>									
By signing this application, I certify that all the will comply with all the requirements of the gr									

SIGNATURE OF APPLICANT:

Name: pubara fu Eliott Title: Town Administrator

Cost Estimate Work	sheet: Hand	y Road Culve	ert #25	
Labor	Rate	# Hours	Total (Rate x Hours)	
JD	\$ 36.58	80	\$ 2,926.40	
RL	\$ 32.22	80	\$ 2,577.60	
RT	\$ 31.13	80	\$ 2,490.40	
TBD	\$ 27.00	80	\$ 2,160.00	
TBD	\$ 27.00	40	\$ 1,080.00	
Excavator Operator	\$ 45.00	40	\$ 1,800.00	
			\$ 13,034.40	Labor Total
Equipment	Rate	# Hours	Total (Rate x Hours	
Truck 1	\$ 78.59	80	\$ 6,287.20	
Truck 2	\$ 78.59	80	\$ 6,287.20	
Truck 3	\$ 52.96	80	\$ 4,236.80	
Truck 4	\$ 26.24	10	\$ 262.40	
grader	\$ 100.61	5	\$ 503.05	
Excavator	\$ 82.48	70	\$ 5,773.60	
chain saw	\$ 2.07	5	\$ 10.35	
chipper	\$ 32.26	5	\$ 161.30	(27 to 25 to
Loader	\$ 30.36	30	\$ 910.80	
			\$ 24,432.70	Equipment Total
-			· · · · · · · · · · · · · · · · · · ·	
Materials	Rate	Amount	Total (Rate x Amount	:)
culvert	\$30,000.00	1	\$ 30,000.00	
gravel	\$ 300.00	50	\$ 15,000.00	
4-6	\$ 11.85	100	\$ 1,185.00	
6-12	\$ 13.65	240	\$ 3,276.00	
large rock	\$ 280.00	10	\$ 2,800.00	
concrete			\$ 10,000.00	TOTAL CONTRACTOR OF THE PROPERTY OF THE PROPER
guardrails	\$ 9,500.00	1	\$ 9,500.00	
	4.000		\$ 71,761.00	Materials Total
Miscellaneous	Rate	Amount	Total (Rate x Hours)	
excavator	\$ 5,280.00	1	\$ 5,280.00	
hauling	\$ 100.00	10	\$ 1,000.00	
			\$ 6,280.00	Miscellaneous Total
	1862		\$ 115,508.10	Grand Total
	PROPERTY.			STATIA TOTAL
W. W. 1997. A		ļ	\$ 60,000.00	Grant Request

# TOWN OF HUNTINGTON, VERMONT CULVERT INSPECTION FORM

	Han	114)	FEATURE CROSSED Fargo Brook				
STRUCTURE NO.	JCTURE NO. 25					Culvert	
	NO CRANC	4	•	OTAL OLEAD ODAN			
	NO. SPANS		N/A	OTAL CLEAR SPAN		TOTAL LENGTH	
ABU	JTMENT TYPE		N/A	DECK TYPE			
# BARRELS	1	NO. LANES		TOTAL WIDTH		WIDTH (RAIL-TO-RAIL)	
HEADWALL TYPE	Rock	BARREL DIA		COVER		WIDTH (CURB-TO-CURB)	
DETOUR LENGTH	MILES	CKEM		ADT % TRUCK			
DETOUR LENGTH	_ MILES	SIVEW		ADI, % INUCK			
APPROACH ROA							
		APP	ROACH ALIGNMENT				
FLOOD HISTORY							
INSPECTION DATE	10/7/2020	BR	IDGE INSPECTOR(S)		DI	MK & CLG	
II .			ces, see Notes at botto				
		ND.	SUPERSTE		COND.	CULVERTS	COND.
ABUTMENTS	No. 1	No. 2		The second secon			00115.
Stem	-	-	Paint		-	Barrel	4
Wingwalls	-	-	Bridge Deck (Timb		-	Headwall (US / DS)	7/4
Backwalls	-	-	Bridge Deck (Conc	rete)	-	Wingwall	-
Pedestals Bridge Seat		-	Bridge Drainage		-	Cutoff Wall	-
Parapet & Capstones			Expansion Devices	Current2	-	Footings Settlement	-
Pointing			Bridge Railing Bridge Geometry	Current	-	Invert Damage	4
Footing			Collision Damage			Sediment/Debris Build-up	6
Settlement		-	Comsion Damage			Sediment/Debits Build-up	
WATERWAY							COND.
Alignment	Fair						5
low	Low, unders	ized hydraulid	c opening		4		4
Scour	Minor downs						6
Riprap	None			,			
Bank Slough			nd downstream				5
APPROACHES	DESCRIPTIO						COND.
Approach Alignment	Fair, sag cur	ve.					6
Guardrail Terminals Beam Guardrail	Collision dar					Current?	
Transition Guardrail	Collision dan	nage				Current?	
	None noted					Current?	N/-
		n on both une	stream and downstre	am due to readwe	av rupoff		6
Pavement Condition	N/A	ii on both up	stream and downstre	sam due lo roadwa	ay runon.		0
- arement community							
				STRUCT	LIBAL CO	NDITION RATING =	4
NOTES:				OTHOOT	OTTAL OC	ADITION HATING =	7
1 Recommend re	enlacement N	Major culvert	damana				
2 Increase hydra	ulic opening	on future etru	icture				
3	unc opening	on luture stru	icture.				
4							
5							
6							
7							
8							
9							
10							-
1							
<b>McFarl</b>	and Jo	hnson	PREPARED BY:	CLG		BRIDGE INSPECT	OR

McFarland	Johnson
IVECE CELECULAR	JUILLIOUIL

REPARED BY: CLG	BRIDGE INSPECTOR
	BRIDGE DESIG
REVIEWED: DMK	SUPERVISOR



Photo 1 (25)
General Topside View (looking east)



<u>Photo 2 (25)</u> Inlet Elevation Significant Culvert Damage/Debris Build-Up






Photo 3 (25)
Outlet Elevation
Severe Culvert Failure (1/2)



Photo 4 (25)
Outlet Elevation
Severe Culvert Failure (2/2)



### Structure Replacements/Rehabilitations

The following structures are recommended for replacement/rehabilitation.

### Handy Road over Fargo Brook - Culvert 25

Culvert 25 was the most critical finding from a hydraulic capacity standpoint. The culvert is approximately a six-foot diameter buried Corrugated Metal Pipe (CMP), approximately ten feet below Handy Road. The culvert exhibits signs of initial failure, with numerous locations of interior deformation along the culvert length. This results in a reduced hydraulic opening, creating an increased chance of debris accumulation within the CMP and developing a dam effect which could seriously affect Handy Road.



Figure 3: Culvert 25 - View of Crushed CMP Outlet (Handy Hill Road 0.26 Miles North of The Intersection with Bert White Road)

