

<b>Town Name</b>	Westminster
<b>Route Name</b>	FAS 0126
<b>Bridge Number</b>	5

	Floor Beams (TONS)							
	H20	HS20	3S2	6AT	3AT	4AT	5AT	
Inventory		18	26	34	33	20	21	33
Operating		28	41	55	52	32	34	53
	Stringers (TONS)							
	H20	HS20	3S2	6AT	3AT	4AT	5AT	
Inventory		17	31	39	35	22	23	39
Operating		29	53	66	59	36	39	65
	Girders (TONS)							
	H20	HS20	3S2	6AT	3AT	4AT	5AT	
Inventory		36	31	38	44	27	28	34
Operating		43	52	63	73	46	34	53

<b>Notes</b>	Floorbeams were evaluated using working stress. Stringers and Girders were evaluated using Load Factor. Steel strength was assumed to be 33ksi on all members. Assumed that the deck was non-composite for evaluation.
--------------	--