Moretown BF 0167(16)

Alternatives Presentation Meeting

Vermont Route 100B – Bridge #2 over Mad River January 17, 2017

Introductions

J. B. McCarthy Structures Bridge Maintenance Engineer jb.mccarthy@vermont.gov 802-505-1451

Rob Young Design Project Manager rob.young@vermont.gov 802-828-0052

Purpose of Meeting

- Discuss alternatives that were considered
- Describe the project constraints
- Provide an opportunity to ask questions and voice concerns

Meeting Overview

- VTrans Project Development Process
- Project Overview
 - Existing Conditions Roadway alignment and Bridge
 - Summary of Alternatives Studied with costs
 - Recommended Alternative
 - Maintenance of Traffic during construction
 - Design and Construction Schedule
 - Questions?????

VTrans Project Development Process



Description of Terms Used



Location Map – Bridge #2



Existing Site Constraints



Existing Bridge Information

Bridge Type: Concrete T-Beam
Bridge Span: 59 Feet
Constructed in 1928
Ownership: State of Vermont

Existing Conditions

- 1. Curbs, deck fascia and bridge railing posts significant section loss.
- 2. Concern with the structural capacity of the bridge rail system to properly protect the traveling public.
- **3.** The shoulder width is substandard in the roadway and on the bridge.
- 4. Existing bridge approach alignments are posted for advisory speeds.



Existing Bridge Railing Posts







North Abutment



South Abutment



Upstream Wingwall



Upsream Channel



Downstream Channel

Old Mill Foundation



Old Mill Foundation



Location Map – Bridge #2



Existing Roadway Conditions

- The shoulder width is substandard in the roadway and on the bridge.
- Existing bridge approach alignments are posted for advisory speeds
- Reduced the traveled way of this bridge to 15'-6"
- Limited the bridge to alternating one-lane of traffic.



North Approach (looking south)



Looking South Through Bridge



South Approach (looking north)

Design Criteria and Considerations

- Substandard Functional Features:
 - Existing 1 ft shoulder and 9 ft lanes.
 - Functionally obsolete 20 ft bridge rail to rail width
- ADT = 3300 vehicles per day
- DHV (Design Hourly Volume) = 400
- % Trucks: 5.7
- Design Speed of 30 mph
- Vermont State Design Standards require
 - 4 ft. shoulders
 - 11 ft. travel lanes

Alternatives Considered

No Action



Alternatives Considered

Rehabilitation

Alt. 1 – Existing alignment with minor widening

New Bridge on Revised Alignment,

Alt 2A - 300 ft. radius (~30 mph) with a new 90 ft. single span bridge.

Alt 2B - 415 ft. radius (meets 30 mph) with a new 90 ft. single span bridge.

Alt 2C - 350 ft. radius (~30 mph) with a new 90 ft. single span bridge

Alternative 1 – Rehabilitation Typical Bridge Section

10-15 years of service life Areas of structural concern on the existing superstructure



FLOW

New Bridge Typical Section



_FLOW

Alternative – 1 Rehabilitation

MAD RIVE

Alternative – 2A New Bridge 25-30mph design

MAD RIVE

Alternative 2A – Vertical Profile



PROJECT NAME MORE TOWN

Alternative – 2B New Bridge 30mph design

MAD BIVE

Alternative – 2C New Bridge 25-30 mph alignment design



Recommend Alternative 2A

- Complete Bridge Replacement, 25-30mph design
 - Minor, positive improvements to the horizontal and vertical alignment
 - Abutments founded on bedrock (economical)
 - Traffic maintained on off-site detour, 3 month closure proposed

Alternative – 2A New Bridge 25-30mph design

MAD RIVE

Road Closure

- 3 month closure
- Detour:
 - Through distance:
 - Detour distance:
 - Added distance:
 - End to end distance:
- One local bypass:
 - Bypass distance:
 - Added distance:

0.5 miles	1 min
18.3 miles	24 min
17.8 miles	21 min
19.5 miles	27 min
4.6 miles	9 min
3.4 miles	6 min

ROAD

CI UCED



0)

Off-Site Detour

 North on Route 100, East on Route 2, South on Route 100B







Alternatives Matrix

			Alt 1	Alt 2a	Alt 2b	Alt 2c		
M	pretown BF 0167(16)	Do Nothing	Superstructure Rehab		w Structure on Revised Alignments			
178		Donothing	Alt 1 Alt 2a Alt 2b Alt 2c Superstructure Rehab New Structure on Revised Alignments Existing Bridge as Temporary \$375,000 \$1,250,000 \$1,320,000 \$1,320,000 \$80,000 \$75,000 \$1,320,000 \$1,320,000 \$80,000 \$75,000 \$75,000 \$1,200,000 \$80,000 \$500,000 \$690,000 \$1,200,000 \$820,000 \$30,000 \$30,000 \$50,000 \$820,000 \$1,855,000 \$2,115,000 \$2,645,000 \$820,000 \$1,855,000 \$2,115,000 \$2,645,000 \$820,000 \$1,855,000 \$2,115,000 \$2,645,000 \$1,070,000 \$2,415,000 \$2,755,000 \$3,500,000 \$1,070,000 \$2,415,000 \$3,330,000 \$440,000 \$1,235,000 \$2,840,000 \$3,3330,000 \$44,430,000 \$1,235,000 \$2,840,000 \$3,333,000 \$4,430,000 \$1,235,000 \$2,840,000 \$3,333,000 \$4,430,000 \$1,235,000 \$2,840,000 \$3,333,0,000 \$4,43					
COST ¹	Bridge Cost	\$0	\$375,000	\$1,250,000	\$1,320,000	\$1,320,000		
	Removal of Structure	\$0	\$80,000	\$75,000	\$75,000	\$75,000		
	Roadway	\$0	\$315,000 \$500,000		\$690,000	\$1,200,000		
	Maintenance of Traffic	\$0	\$50,000	\$30,000	\$30,000	\$50,000		
	Construction Costs	\$0	\$820,000	\$1,855,000	\$2,115,000	\$2,645,000		
	Construction Engineering +	¢0	¢250.000	¢560.000	¢c10.000	000 000		
I	Contingencies	φυ	\$ 200,000	<i>\$200,000</i>	40.0,000	4000,000		
	Total Construction Costs w CEC	\$0	\$1,070,000	\$2,415,000	\$2,755,000	\$3,500,000		
L	Fremunary Engineering ²	\$ 0	\$165,000	\$275,000	\$4 25 ,000	\$520,000		
	Right of Way	\$0	\$0	\$50,000	\$150,000	\$400,000		
	Total Project Costs	\$0	\$1,235,000	\$2,840,000	\$3,330,000	\$4,430,000		
SCHEDULING	Project Development Duration ³	N/A	6 months	2 years	3 years	3 years		
	Construction Duration	N/A	6 weeks	3 months	3 months	5 months		
	Closure Duration (If Applicable)	N/A	4 weeks	3 months	3 months	0		
ENGINEERING	Typical Section - Roadway (feet)	35 ft.	22 ft.	30 ft.	30 ft.	30 ft.		
	Typical Section - Bridge (feet)	3.9-11-11-3.9	1-10-10-1	4-11-11-4	4-11-11-4	4-11-11-4		
	Geometric Design Criteria	Substandard width and banking,	Substandard width, 25 mph	Standard width, alignment	Standard width, alignment	Standard width, alignment		
	Compare Design Chiefin	western approach	alignment	meets 25 mph	meets 30 mph	meets 25 mph		
	Traffic Safety	No Change	Minimal Improvement	Improved	Improved	Improved		
	Alignment Change	No	No	Yes - minor	Yes	Yes - minor		
	Bicycle Access	No Change	No Change	Improved	Improved	Improved		
	Hydraulic Performance	Meets standard	No Change	Meets Standard	Meets Standard	Meets standard		
	Pedestrian Access	No Change	No Change	Improved	Improved	Improved		
	Utility	No Change	No Change	Relocated	Relocated	Relocated		
OTHER	ROW Acquisition	No	No	Yes - minor	Yes - moderate	Yes - major		
	Road Closure	No	Yes	Yes	Yes	No		
	Design Life	<10 years	<10 years		100 years			

Project Design Schedule

- Conceptual Plans March 2017
- Property owner visits August 2017
- Preliminary Plans September 2017
- Permits August 2018
- Final Plans July 2018
- Contract Plans February 2019
- Advertising September 2019

Project : 16B010(0) Project of 2 MORETOWN BF 0167(16) Date: 13 Jan 2017 Time: 02:14:47											
								2017	2018	2019	
tivityName	Activity Description	Orig. Dur.	sctual start date	actual finish date	early start date	early finish date	Current Duration				
0.01	PE.P re-Approisal Authorization	22	11Jan17		11Jan17	10Feb17	22	,			
0.04.02	Alternatives Presentation/Refinement	22	07Dec16		07Dec16	17Jan17	27	•			
0.04.03	Alternative Accepted	0			01Feb17	01Feb17	0	v			
0.04	NEPADocument	88			03May17	07Sep17	88		_		
0.01	Develop Conceptual Plans	22			13Feb17	16Mar17	22	-			
3.02	Public Meeting/Hearing/Refinement	33			27Dec17	13Feb18	33		r .		
0.01	Develop Prelin inary Plans	96			18Apr17	01Sep17	96				
0.011	Prelin inary Risk Registry	66			31May17	01Sep17	66				
0.012	Preliminary Transportation Management Plan	66			31May17	01Sep17	68	. 4			
0.0125	Prelin inary Plans Internal Revie w	22			05Sep17	040d17	22	+			
013	Prelin inary Plans QAU ReviewPeriod	22			200ct17	21Nov17	22				
.014	Prelininary Plans Constructability Review-Meeting	0			30Nov17	30Nov17	0		₹		
.03	Geotechnical Analysis	110			17Mar17	22Aug17	110	╟┶╍╪╪╪╪┥║║			
.04	Hydraulics - Final	33			10AJ17	01Sep17	33	\+			
.05	Environmental Permits	132			30Jan18	07Aug18	132				
.06	Utility Relocation Routing	27			17Mar17	24Apr17	27				
.07	Property Owner Contact	44			27Jun17	29Aug17	44	∥ՐԿ┓			
.08	Address Prelin plans comments	22			22Nov17	26Dec17	22	11 64			
.005	Prelininary ROW Estimate/ROW STIP Verification	44			27Dec17	01Mar10	44				
.09	ROW Acquisition Authorization	22			02Mar18	03Apr18	22		Fg		
.11	Utility Agreements	44			25Apr17	07Jun17	44	[]			
.12	Access Permits	22			17Mari 7	07Apr17	22				
15	Railroad Assreements & Special Provisions	88			17Mar17	20Jul17	88				
0.01	Develop ROW Plans and Titles	88			30Aug17	08Jan18	88				
1.02	Legal Document Preparation	33			09Jan18	26Feb18	33		GH		
0.03	Final ROW Plans and Documents Complete	0			26Feb18	26Feb18			-¶•		
1022	Waiver Valuation Estimates	22			02Mar18	03Apr18	22		He II		
0.03	Neadiation	88			044or18	07Aug18	88		L C		
0.037	Minor Alterations Condemnation	68			17,3,418	180 418	68				
104	Compensation	16			19Oct18	08Nov18	15		1 1		

For more information:

https://outside.vermont.gov/agency/vtrans/external/Projects/Structures/16b010

Moretown BF 0167(16) Questions and Comments

Vermont Route 100B – Bridge #2 over Mad River January 17, 2017