

STATE OF VERMONT AGENCY OF TRANSPORTATION



PROPOSED IMPROVEMENT BRIDGE PROJECT



TOWN OF PLYMOUTH
COUNTY OF WINDSOR

ROUTE NO : VT RTE 100; MINOR ARTERIAL BRIDGE NO : 107



PROJECT LOCATION: LOCATED ON VT100 IN THE TOWN OF PLYMOUTH APPROXIMATELY 1.5 MILES
SOUTH OF THE JUNCTION WITH VT ROUTE 100A

PROJECT DESCRIPTION: CONSTRUCTION OF A NEW BRIDGE DECK ON THE EXISTING STEEL BEAMS
WITH RELATED ROADWAY APPROACH WORK.

LENGTH OF STRUCTURE: 89.00 FEET
LENGTH OF ROADWAY: 161.00 FEET
LENGTH OF PROJECT: 250.00 FEET



PLYMOUTH
STP DECK (52)




CONSTRUCTION IS TO BE CARRIED ON IN ACCORDANCE WITH THESE PLANS AND THE STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED 2018, AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION ON APRIL 13, 2018 FOR USE ON THIS PROJECT, INCLUDING ALL SUBSEQUENT REVISIONS AND SUCH REVISED SPECIFICATIONS AND SPECIAL PROVISIONS AS ARE INCORPORATED IN THESE PLANS.

QUALITY ASSURANCE PROGRAM : LEVEL 2	
SURVEYED BY :	R. GILMAN
SURVEYED DATE :	01/10/2020
DATUM	
VERTICAL	NAVD88
HORIZONTAL	NAD83 (2011)

SCALE 1" = 40'-0"

FINAL PLANS
24-AUG-2022

HIGHWAY DIVISION, CHIEF ENGINEER	
APPROVED _____	DATE _____
PROJECT MANAGER : J. B. MCCARTHY, P. E.	
PROJECT NAME : PLYMOUTH	
PROJECT NUMBER : STP DECK (52)	
SHEET 1 OF 29 SHEETS	



PROPOSED VT ROUTE 100 TYPICAL SECTION

SCALE 3/8" = 1'-0"

PAVEMENT SPECIFICATIONS


DESIGN LANE/DESIGN LIFE ESALS	303,520
PERFORMANCE GRADE ASPHALT BINDER	70-28
DESIGN NUMBER OF GYRATIONS	65

EMULSION SHALL BE APPLIED PER THE APPLICATION RATES IN TABLE 406.12A OF THE STANDARD SPECIFICATIONS.

MATERIAL TOLERANCES
(IF USED ON PROJECT)


SURFACE	
- PAVEMENT (TOTAL THICKNESS)	+/- 1/4"
- AGGREGATE SURFACE COURSE	+/- 1/2"
SUBBASE	+/- 1"
SAND BORROW	+/- 1"

- * BITUMINOUS CONCRETE PAVEMENT (ROADWAY)
2 - 1 1/2" LIFTS TYPE IVB
1 - 3/2" LIFT TYPE IIS
- BITUMINOUS CONCRETE PAVEMENT (DECK)
2 - 1 1/2" LIFTS TYPE IVB
- ** SPECIAL PROVISION
(PERFORMANCE-BASED CONCRETE, CLASS PCO)



EXISTING BRIDGE TYPICAL SECTION


SCALE 3/8" = 1'-0"



SAWED PAVEMENT JOINT DETAIL

(NOT TO SCALE)

*JOINT IS TO BE LOCATED ACCURATELY BY STRING LINING, OR OTHER MEANS, PRIOR TO PAVING, SO THAT THE SAW CUTS WILL BE MADE DIRECTLY OVER THE END OF CONCRETE DECK. JOINT SHALL BE CUT DRY IN A SINGLE PASS AND BE SEALED WITHIN 24 HOURS OR PRIOR TO EXPOSURE TO TRAFFIC. JOINT SHALL BE CLEANED PRIOR TO APPLYING THE JOINT SEALER.



PROPOSED BRIDGE TYPICAL SECTION

SCALE 3/8" = 1'-0"

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8b007typical.dgn	DESIGNED BY:	F. BARROWS
PROJECT LEADER:	J.B. McCARTHY	CHECKED BY:	F. BARROWS
TYPICAL SECTIONS		SHEET	3 OF 29

GENERAL

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE STATE OF VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION 2018, AND ITS LATEST REVISIONS, AND THE AASHTO LRFD BRIDGE DESIGN SPECIFICATION, DATED 2017, AND ITS LATEST REVISIONS.
2. ALL DIMENSIONS SHOWN IN THE PLANS ARE HORIZONTAL OR VERTICAL AND ARE GIVEN AT 68 DEGREES FAHRENHEIT, UNLESS NOTED OTHERWISE
3. ITEM 529.20, "PARTIAL REMOVAL OF STRUCTURE" WILL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS NEEDED TO COMPLETELY REMOVE THE EXISTING DECK DOWN TO THE TOP FLANGE OF THE EXISTING BEAMS TO INCLUDE BUT NOT LIMITED TO THE CURBS, BRIDGE RAILING, SHEAR STUDS (IF ANY), WOOD FORMS, THE PAVEMENT AND WING WALLS TO THE LIMITS SHOWN ON THE PLANS.
4. THE CONTRACTOR SHALL MAINTAIN ALL SECTIONS OF THE HIGHWAY UNDER CONSTRUCTION SATISFACTORY TO THE ENGINEER TO ENSURE THE SAFETY OF THE TRAVELING PUBLIC. PAYEMENT WILL BE UNDER CONTRACT ITEM 527.10 "MAINTENANCE OF STRUCTURES AND APPROACHES" WHICH WILL INCLUDE BUT NOT LIMITED TO PERFORMING THE WORK AND FOR FURNISHING ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, AND INCIDENTALS NECESSARY TO MAINTAIN ALL SUBSTRUCTURES, SUPERSTRUCTURES AND APPROACHES.

TEMPORARY ROADWAY AND TRAFFIC CONTROL

5. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN, SUBMITTAL, AND IMPLEMENTATION OF THE SITE-SPECIFIC TRAFFIC CONTROL PLAN. THE SITE-SPECIFIC TRAFFIC CONTROL PLAN SHALL BE DESIGNED IN ACCORDANCE WITH SECTION 641.
6. THE CONTRACTOR'S SITE-SPECIFIC TRAFFIC CONTROL PLAN SHALL MEET THE SPECIFIED DIMENSIONS HEREIN. REFERENCE PHASE 1 LAYOUT, PHASE 2 LAYOUT, AND PHASING TYPICAL SECTIONS FOR ADDITIONAL DETAILS AND REQUIRMENTS.
7. ANY REMOVAL, COVERING AND/OR RESETTNG OF EXISTING TRAFFIC SIGNS, AS DEEMED NECESSARY BY THE RESIDENT ENIGNEER, WILL BE INCIDENTAL TO ITEM 641.11 TRAFFIC CONTROL, ALL-INCLUSIVE.
8. ANY TEMPORARY MEANS OF SUPPORTING EXCAVATION NECESSARY TO MAINTAIN TRAFFIC WILL BE INCLUDED IN THE PAYMENT OF ITEM 641.11 TRAFFIC CONTROL, ALL-INCLUSIVE CONSTRUCTION DRAWINGS SHALL BE REQUIRED AS PER SUBSECTION 105.03.

TEMPORARY TRAFFIC SIGNALS

9. TEMPORARY TRAFFIC SIGNAL SYSTEM SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM" AND IN COMPLIANCE WITH THE LATEST EDITION OF THE MUTCD.
10. SIGNAL FACES SHALL BE LED AND CONSIST OF 12 INCH LENSES (RED, YELLOW AND GREEN)
11. LUMINAIRES SHALL BE INSTALLED AT EACH OF THE APPROACHES TO ADEQUATELY LIGHT THE STOP BAR AREAS. PAYMENT WILL BE CONSIDERED INCIDENTAL TO ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM"
12. ALL TEMPORARY SIGNAL EQUIPMENT, SIGNS, ETC. SHALL BELONG TO THE CONTRACTOR AT THE END OF THE PROJECT AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR REMOVAL INCLUDING UTILITY POLES, WIRES, ETC. PAYMENT WILL BE CONSIDERED INCIDENTAL TO ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM".
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING SIGNAL PHASING AND TIMING. THE CONTRACTOR SHALL SUBMIT A PHASING DIAGRAM AND TIMING SCHEDULE TO THE ENIGNEER FOR APPROVAL. THE CONTRACTOR SHALL MAKE THE SIGNALS OPERATIONAL ONLY AFTER RECEIVING APPROVAL OF BOTH THE PHASING DIAGRAM AND TIMING SCHEDULE BY THE ENGINEER. DEVELOPMENT OF THE PHASING DIAGRAM AND TIMING SCHEDULE WILL BE CONSIDERED INCIDENTAL TO ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM". ADDITIONAL ADJUSTMENTS TO SIGNAL TIMING OR PHASING REQUESTED BY THE ENGINEER SHALL BE COMPLETED WITHIN 48 HOURS OF THE REQUEST. PAYMENT FOR ADDITIONAL ADJUSTMENTS TO SIGNAL TIMING OR PHASING WILL BE CONSIDERED INCIDENTAL TO ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM".

14. THE SUBMITTAL FOR ITEM 678.40 "TEMPORARY TRAFFIC SIGNAL SYSTEM" SHALL BE IN CONJUNCTION WITH THE SUBMITTAL FOR ITEM 641.11 "TRAFFIC CONTROL, ALL-INCLUSIVE" AND SHALL INCLUDE AS A MINIMUM, THE SIGNAL LOCATION, TIMING, AND PHASING PLAN, VEHICLE DETECTION SYSTEM, AND EMERGENCY VEHICLE PREEMPTION SYSTEM.

EPSC

15. THIS PROJECT WILL UTILIZE THE VT DEC LOW RISK SITE HANDBOOK FOR EPSC. NO SITE-SPECIFIC EPSC PLAN IS INCLUDED. THE CONTRACTOR SHALL SUBMIT A SITE-SPECIFIC EPSC PLAN, IN ACCORDANCE WITH SECTION 653 OF THE STANDARD SPECIFICATIONS, FOR CONSTRUCTION. ESTIMATED QUANTITIES FOR EPSC WORK HAVE BEEN INCLUDED IN THE CONTRACT FOR BIDDING PURPOSES. IF THE CONTRACTORS EPSC PLAN REQUIRES ITEMS OF WORK THAT ARE NOT INCLUDED IN THE PLANS, IT SHALL BE PAID FOR AS PART OF ITEM 653.03 MAINTENANCE OF EPSC PLAN.
16. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT SILTATION OR POLLUTION, IN PARTICULAR THE DISCHARGE OF RAW CONCRETE INTO THE BALDWIN CREEK, AS DIRECTED BY THE RESIDENT ENGINEER AND STANDARD SPECIFICATIONS SECTION 105.
17. THE EXISTING CONDITIONS SHEET HAS BEEN INCLUDED FOR THE CONTRACTOR TO USE FOR SUBMITTALS.

STRUCTURAL STEEL

18. THE EXISTING STRUCTURAL STEEL IS PAINTED WITH A MATERIAL THAT MAY CONTAIN LEAD. THE CONTRACTOR SHALL FOLLOW ALL APPLICABLE REGULATIONS WHEN HANDLING AND WORKING WITH THIS STEEL, AND WHEN HANDLING ANY PAINT REMOVED INTENTIONALLY OR NOT. ANY REMOVED STRUCTURAL STEEL OR PAINT IS THE PROPERTY OF THE CONTRACTOR. THE CONTRACTOR SHALL INDEMNIFY AND HOLD THE STATE, IT'S OFFICERS AND EMPLOYEES HARMLESS CONCERNING THE CONTRACTOR'S USE OR DISPOSITION OF THE REMOVED STRUCTURAL STEEL OR PAINT.
19. IMMEDIATELY AFTER THE EXISTING CONCRETE DECK AND SHEAR STUDS (IF ANY) HAVE BEEN REMOVED, THE CONTRACTOR SHALL TAKE ELEVATIONS ALONG THE TOP OF THE BEAMS, AT 5'-0" INTERVALS. THE ELEVATIONS SHALL THEN BE SENT TO THE PROJECT MANAGER FOR USE IN DETERMINING THE HAUNCH DEPTHS. THE CONTRACTOR SHOULD EXPECT 4 WORKING DAYS FOR VTRANS TO PREPARE THE HAUNCH DEPTH CALCULATIONS.
20. FLEMING BRACKETS OR SIMILAR FALSEWORK SHALL BE SPACED AS REQUIRED BY DESIGN BUT SHALL BE LIMITED TO A MAXIMUM SPACING OF 4 FEET. THE DESIGN OF FALSEWORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL EXTEND AT LEAST 75% OF THE WEB DEPTH.
21. THE LOCATION OF THE SHEAR CONNECTORS SHALL BE MARKED OUT BEFORE SURFACE PREPARATION BEGINS. THE CONTACT AREAS SHALL BE CLEANED TO AN EXTENT 1 INCH BEYOND THE BORDER OF EACH OF THE CONNECTED PARTS IN ACCORDANCE WITH ITEM 900.645 "SPECIAL PROVISION (REMOVAL, CONTAINMENT, AND DISPOSAL OF LEAD PAINT) (TYPE II)". THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY LEAD ABATEMENT PERMITS. PAYMENT FOR THIS WORK SHALL BE MADE UNDER ITEM 900.645 "SPECIAL PROVISION (REMOVAL, CONTAINMENT, AND DISPOSAL OF LEAD PAINT) (TYPE II)".
22. THE NEW SHEAR CONNECTORS SHALL BE SPACED AS PER PLANS. PAYMENT FOR THE NEW CONNECTORS WILL BE MADE UNDER ITEM 508.15, "SHEAR CONNECTORS".

CONCRETE

23. THE DECK, CURTAIN WALLS AND CURB CONCRETE SHALL BE SPECIAL PROVISION (PERFORMANCE-BASED CONCRETE, CLASS PCD) AND SHALL BE PAID FOR UNDER ITEM 900.608.
24. THE APPROACH SLAB SHALL BE SPECIAL PROVISION (PERFORMANCE-BASED CONCRETE, CLASS PCS) AND SHALL BE PAID FOR UNDER ITEM 900.608.
25. EACH PHASE OF THE DECK IS TO BE POURED IN ONE CONTINUOUS POUR WITH A MAXIMUM DURATION OF EIGHT HOURS. IF CIRCUMSTANCES BEYOND THE CONTRACTOR'S CONTROL PREVENT THIS FROM BEING ACCOMPLISHED, A TRANSVERSE CONSTRUCTION JOINT SHALL BE USED BETWEEN ADJACENT POURS. A MINIMUM 96 HOUR DELAY BETWEEN ADJACENT POURS SHALL BE OBSERVED.
26. ITEM 514.10, "WATER REPELLENT, SILANE, SHALL BE APPLIED TO ALL EXPOSED CONCRETE ON THE BRIDGE SUPERSTRUCTURE INCLUDING THE DECK, FASCIAS, AND EXISTING SUBSTRUCTURE, WITH THE EXCEPTION OF THE BOTTOM OF THE DECK BETWEEN DRIP NOTCHES.

27. ITEM 520.10, "MEMBRANE WATERPROOFING, SPRAY APPLIED" SHALL BE APPLIED TO THE BRIDGE DECK AFTER THE ENTIRE DECK IS COMPLETE. EXTEND MEMBRANE 3 INCHES UP THE CONCRETE RAIL BASE AND ONTO THE APPROACH SLABS 2 FEET BEYOND BEGIN BRIDGE.
28. "REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS 1 AND CLASS 2" ARE INCLUDED TO BE USED AT THE DISCRETION OF THE ENGINEER.
29. CORK BETWEEN THE ABUTMENT CHEEK WALL AND DECK FASCIA SHALL BE INCLUDED IN THE ADJACENT CONCRETE ITEM.
30. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 1 INCH X 1 INCH.
31. ALL APPROACH SLAB REINFORCING STEEL SHALL BE REINFORCING STEEL, LEVEL I AND PAID FOR UNDER ITEM 507.11, "REINFORCING STEEL, LEVEL I (EPOXY COATED)".
32. ALL SUPERSTRUCTURE REINFORCING STEEL AND WING WALL STEEL SHALL BE REINFORCING STEEL, LEVEL II AND PAID FOR UNDER ITEM 507.12, "REINFORCING STEEL, LEVEL II".
33. REINFORCING STEEL PLACEMENT TOLERANCES SHALL BE:

SPACING: +/- 1 INCH
 CLEARANCE: +/- 1/4 INCH

PROJECT NAME: PLYMOUTH
 PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007notes.dgn PLOT DATE: 24-AUG-2022
 PROJECT LEADER: J.B. McCARTHY DRAWN BY: R. PELLETT
 DESIGNED BY: F. CHECKED BY: K.
 PROJECT NOTES SHEET 4 OF 29

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							1011 - ROADWAY	1051 - EROSION CONTROL	1211 - BRIDGE NO. 1	1999 - FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							590				590		CY	COMMON EXCAVATION	203.15				
							5				5		CY	SOLID ROCK EXCAVATION	203.16				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							330				330		SY	COARSE-MILLING, BITUMINOUS PAVEMENT	210.10				
							520				520		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
							45				45		CY	AGGREGATE SURFACE COURSE	401.10				
							12				12		CWT	EMULSIFIED ASPHALT	404.65				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									7879		7879		LB	REINFORCING STEEL, LEVEL I (EPOXY COATED)	507.11				
									23168		23168		LB	REINFORCING STEEL, LEVEL II	507.12				
									36		36		LF	DRILLING AND GROUTING DOWELS	507.16				
									1		1		LS	SHEAR CONNECTORS (1044 - 7/8" X 7")	508.15				
									10		10		GAL	WATER REPELLENT, SILANE	514.10				
									33		33		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
									357		357		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									47		47		LF	JOINT SEALER, HOT POURED	524.11				
									178		178		LF	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	525.335				
							1				1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									5		5		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	580.13				
									5		5		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14				
							10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							255				255		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
							1				1		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
							3				3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							218				218		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							800				800		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LS	TESTING EQUIPMENT, GROUT	631.19				
										3000	3000		DL	FIELD OFFICE COMMUNICATIONS (N.A.B.I.)	631.26				
							5				5		EACH	CPM SCHEDULE	633.10				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL, ALL-INCLUSIVE	641.11				
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							700				700		LF	4 INCH WHITE LINE, WATERBORNE PAINT	646.201				
							700				700		LF	4 INCH YELLOW LINE, WATERBORNE PAINT	646.2111				
																			N.A.B.I. = NOT A BID ITEM

PROJECT NAME: PLYMOUTH
PROJECT NUMBER: STP DECK(52)
FILE NAME: sl8b00705.dgn PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. McCARTHY DRAWN BY: K. LIHC
DESIGNED BY: K. LIHC CHECKED BY: F. BARROWS
QUANTITY SHEET 1 SHEET 5 OF 29

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							1011 - ROADWAY	1051 - EROSION CONTROL	1211 - BRIDGE NO. 1	1999 - FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							970				970		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				N.A.B.I. = NOT A BID ITEM
								10			10		LB	SEED	651.15				
								25			25		LB	FERTILIZER	651.18				
								0.25			0.25		TON	AGRICULTURAL LIMESTONE	651.20				
								10			10		CY	TOPSOIL	651.35				
								1			1		LS	EPSC PLAN	653.01				
								40			40		HR	MONITORING EPSC PLAN	653.02				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	653.03				
								0.25			0.25		TON	HAY MULCH	653.10				
								30			30		CY	STABILIZED CONSTRUCTION ENTRANCE	653.35				
								550			550		LF	SILT FENCE, TYPE I	653.475				
								525			525		LF	BARRIER FENCE	653.50				
							1.26				1.26		SF	TRAFFIC SIGN, TYPE A	675.20				
							20				20		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							3				3		EACH	REMOVING SIGNS	675.50				
							4				4		EACH	DELINEATOR WITH STEEL POST	678.10				
							3				3		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
									111		111		CY	SPECIAL PROVISION (PERFORMANCE-BASED CONCRETE, CLASS PCD)	900.608				
									36		36		CY	SPECIAL PROVISION (PERFORMANCE-BASED CONCRETE, CLASS PCS)	900.608				
							4				4		EACH	SPECIAL PROVISION (GUARDRAIL THRIE BEAM APPROACH SECTION, GALVANIZED 3 R	900.620				
									1		1		LS	SPECIAL PROVISION (REMOVAL, CONTAINMENT, AND DISPOSAL OF LEAD PAINT) (TYPE	900.645				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							300				300		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	K. LIHIC
FILE NAME:	sl8b00705.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. McCARTHY	QUANTITY SHEET 2	SHEET 6 OF 29
DESIGNED BY:	K. LIHIC		

GENERAL INFORMATION

SYMBOLGY LEGEND NOTE

THE SYMBOLGY ON THIS SHEET IS INTENDED TO COVER STANDARD CONVENTIONAL SYMBOLGY. THE SYMBOLGY IS USED FOR EXISTING & PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROJECT ANNOTATION, AS NOTED ON PROJECT PLAN SHEETS. THIS LEGEND SHEET COVERS THE BASICS. SYMBOLGY ON PLANS MAY VARY, PLAN ANNOTATIONS AND NOTES SHOULD BE USED TO CLARIFY AS NEEDED.

R.O.W. ABBREVIATIONS (CODES) & SYMBOLS

POINT CODE	DESCRIPTION
BF	BARRIER FENCE
CH	CHANNEL EASEMENT
CONST	CONSTRUCTION EASEMENT
CUL	CULVERT EASEMENT
D&C	DISCONNECT & CONNECT
DIT	DITCH EASEMENT
DR	DRAINAGE EASEMENT
DRIVE	DRIVEWAY EASEMENT
EC	EROSION CONTROL
HWY	HIGHWAY EASEMENT
I&M	INSTALL & MAINTAIN EASEMENT
LAND	LANDSCAPE EASEMENT
PDF	PROJECT DEMARCATION FENCE
R&RES	REMOVE & RESET
R&REP	REMOVE & REPLACE
R.T.& I.	RIGHT, TITLE, AND INTEREST
SR	SLOPE RIGHT
UE	UTILITY EASEMENT
(P)	PERMANENT EASEMENT
(T)	TEMPORARY EASEMENT
■	BNDNS BOUND SET
▣	BNDNS BOUND TO BE SET
⊙	IPNF IRON PIN FOUND
●	IPNS IRON PIN TO BE SET
⊠	CALC EXISTING ROW POINT
○	PROW PROPOSED ROW POINT
[LENGTH]	LENGTH CARRIED ON NEXT SHEET

COMMON TOPOGRAPHIC POINT SYMBOLS

POINT CODE	DESCRIPTION
⊕	APL BOUND APPARENT LOCATION
◻	BM BENCHMARK
◻	BND BOUND
⊠	CB CATCH BASIN
⊕	COMB COMBINATION POLE
⊠	DITHR DROP INLET THROATED DNC
⊕	EL ELECTRIC POWER POLE
◊	FPOLE FLAGPOLE
○	GASFIL GAS FILLER
○	GP GUIDE POST
×	GSO GAS SHUT OFF
◊	GUY GUY POLE
◊	GUYW GUY WIRE
×	GV GATE VALVE
⊗	H TREE HARDWOOD
△	HCTRL CONTROL HORIZONTAL
▲	HVCTRL CONTROL HORIZ. & VERTICAL
◇	HYD HYDRANT
◊	IP IRON PIN
●	IPIPE IRON PIPE
⊕	LI LIGHT - STREET OR YARD
⊕	MB MAILBOX
○	MH MANHOLE (MH)
◻	MM MILE MARKER
◻	PM PARKING METER
◻	PMK PROJECT MARKER
◊	POST POST STONE/WOOD
⊠	RRSIG RAILROAD SIGNAL
⊕	RRSL RAILROAD SWITCH LEVER
⊗	S TREE SOFTWOOD
◊	SAT SATELLITE DISH
⊗	SHRUB SHRUB
⊕	SIGN SIGN
⊕	STUMP STUMP
⊕	TEL TELEPHONE POLE
◊	TIE TIE
⊕	TSIGN SIGN W/DOUBLE POST
⊕	VCTRL CONTROL VERTICAL
◊	WELL WELL
×	WSO WATER SHUT OFF

THESE ARE COMMON VAOT SURVEY POINT SYMBOLS FOR EXISTING FEATURES, ALSO USED FOR PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROPOSED ANNOTATION.

PROPOSED GEOMETRY CODES

CODE	DESCRIPTION
PC	POINT OF CURVATURE
PI	POINT OF INTERSECTION
CC	CENTER OF CURVE
PT	POINT OF TANGENCY
PCC	POINT OF COMPOUND CURVE
PRC	POINT OF REVERSE CURVE
POB	POINT OF BEGINNING
POE	POINT OF ENDING
STA	STATION PREFIX
AH	AHEAD STATION SUFFIX
BK	BACK STATION SUFFIX
D	CURVE DEGREE OF (100FT)
R	CURVE RADIUS OF
T	CURVE TANGENT LENGTH
L	CURVE LENGTH OF
E	CURVE EXTERNAL DISTANCE
CB	CHORD BEARING

UTILITY SYMBOLGY

UNDERGROUND UTILITIES

— UGU —	UTILITY (GENERIC-UNKNOWN)
— UT —	TELEPHONE
— UE —	ELECTRIC
— UC —	CABLE (TV)
— UEC —	ELECTRIC+CABLE
— UET —	ELECTRIC+TELEPHONE
— UCT —	CABLE+TELEPHONE
— UECT —	ELECTRIC+CABLE+TELEPHONE
— G —	GAS LINE
— W —	WATER LINE
— S —	SANITARY SEWER (SEPTIC)

ABOVE GROUND UTILITIES (AERIAL)

— AGU —	UTILITY (GENERIC-UNKNOWN)
— T —	TELEPHONE
— E —	ELECTRIC
— C —	CABLE (TV)
— EC —	ELECTRIC+CABLE
— ET —	ELECTRIC+TELEPHONE
— AER E&T —	ELECTRIC+TELEPHONE
— CT —	CABLE+TELEPHONE
— ECT —	ELECTRIC+CABLE+TELEPHONE
—	UTILITY POLE GUY WIRE

PROJECT CONSTRUCTION SYMBOLGY

PROJECT DESIGN & LAYOUT SYMBOLGY

— CZ —	CLEAR ZONE
—	PLAN LAYOUT MATCHLINE

PROJECT CONSTRUCTION FEATURES

—	TOP OF CUT SLOPE
—	TOE OF FILL SLOPE
⊗	STONE FILL
—	BOTTOM OF DITCH
—	CULVERT PROPOSED
—	STRUCTURE SUBSURFACE
PDF	PROJECT DEMARCATION FENCE
BF	BARRIER FENCE
XXXXXXXXXXXXXXXXXXXX	TREE PROTECTION ZONE (TPZ)
////	STRIPING LINE REMOVAL
~~~~	SHEET PILES

**CONVENTIONAL BOUNDARY SYMBOLGY**

**BOUNDARY LINES**

— TOWN LINE —	TOWN BOUNDARY LINE
— COUNTY LINE —	COUNTY BOUNDARY LINE
— STATE LINE —	STATE BOUNDARY LINE
—	PROPOSED STATE R.O.W. (LIMITED ACCESS)
—	PROPOSED STATE R.O.W.
—	STATE ROW (LIMITED ACCESS)
—	STATE ROW
—	TOWN ROW
—	PERMANENT EASEMENT LINE (P)
—	TEMPORARY EASEMENT LINE (T)
—	SURVEY LINE
P	PROPERTY LINE (P/L)
L	SLOPE RIGHTS
SR	6F PROPERTY BOUNDARY
6f	4F PROPERTY BOUNDARY
4f	HAZARDOUS WASTE
HAZ	

**EPSC LAYOUT PLAN SYMBOLGY**

**EPSC MEASURES**

ONNOONNOONNO	FILTER CURTAIN
—	SILT FENCE
—	SILT FENCE WOVEN WIRE
—	CHECK DAM
—	DISTURBED AREAS REQUIRING RE-VEGETATION
—	EROSION MATTING

SEE EPSC DETAIL SHEETS FOR ADDITIONAL SYMBOLGY

**ENVIRONMENTAL RESOURCES**

—	WETLAND BOUNDARY
—	RIPARIAN BUFFER ZONE
—	WETLAND BUFFER ZONE
—	SOIL TYPE BOUNDARY
— T&E —	THREATENED & ENDANGERED SPECIES
HAZ	HAZARDOUS WASTE AREA
AG	AGRICULTURAL LAND
HABITAT	FISH & WILDLIFE HABITAT
FLOOD PLAIN	FLOOD PLAIN
OHW	ORDINARY HIGH WATER (OHW)
—	STORM WATER
—	USDA FOREST SERVICE LANDS
—	WILDLIFE HABITAT SUIT/CONN

**ARCHEOLOGICAL & HISTORIC**

— ARCH —	ARCHEOLOGICAL BOUNDARY
— HISTORIC DIST —	HISTORIC DISTRICT BOUNDARY
— HISTORIC —	HISTORIC AREA
(H)	HISTORIC STRUCTURE

**CONVENTIONAL TOPOGRAPHIC SYMBOLGY**

**EXISTING FEATURES**

—	ROAD EDGE PAVEMENT
—	ROAD EDGE GRAVEL
—	DRIVEWAY EDGE
—	DITCH
—	FOUNDATION
x	FENCE (EXISTING)
□	FENCE WOOD POST
○	FENCE STEEL POST
—	GARDEN
—	ROAD GUARDRAIL
—	RAILROAD TRACKS
—	CULVERT (EXISTING)
—	STONE WALL
—	WALL
—	WOOD LINE
—	BRUSH LINE
—	HEDGE
—	BODY OF WATER EDGE
—	LEDGE EXPOSED

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007legend.dgn PLOT DATE: 24-AUG-2022  
PROJECT LEADER: J.B. McCARTHY DRAWN BY: R. PELLETT  
DESIGNED BY: F. BARROWS CHECKED BY: F. BARROWS  
CONVENTIONAL SYMBOLGY LEGEND SHEET 7 OF 29

PRIMARY CONTROL

HVCTRL #1  
 NORTH = 370104.4570  
 EAST = 1578936.5990  
 ELEV. = 1183.7900

TO REACH FROM THE INTERSECTION OF ROUTES 100 AND 100A IN PLYMOUTH, GO SOUTH ALONG ROUTE 100 FOR 1.1 MI (1.8 KM) TO THE SITE OF THE MARK ON THE RIGHT AT A DRIVE LEADING TO A CAMP.

THE MARK IS A 3/4 INCH (19 MM) REBAR WITH RED PLASTIC CAP SET 2 INCHES (5 CM) BELOW GROUND SURFACE.

IT IS 29.0 FT (8.8 M) WEST OF AND ABOUT 1 FT (0.3 M) LOWER THAN THE CENTERLINE OF ROUTE 100, 62.0 FT (18.9 M) WEST-NORTHWEST OF AND ACROSS THE ROAD FROM POLE NUMBER 14/400IF, 47.0 FT (14.3 M) EAST OF A 12 INCH (30 CM) HEMLOCK AND ABOUT 135 FT (41.1 M) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF THE WING WALL FOR BRIDGE 108.






HVCTRL #2  
 NORTH = 368203.7550  
 EAST = 1580138.8870  
 ELEV. = 1155.2900

TO REACH FROM THE INTERSECTION OF ROUTES 100 AND 100A IN PLYMOUTH, GO SOUTH ALONG ROUTE 100 FOR 1.6 MI (2.6 KM) TO THE SITE OF THE MARK ON THE RIGHT JUST PAST BRIDGE 107 AND ACROSS FROM A WOODS ROAD.

THE MARK IS A 3/4 INCH (19 MM) REBAR WITH RED PLASTIC CAP SET 2 INCHES (5 CM) BELOW GROUND SURFACE.

IT IS 23.0 FT (7.0 M) WEST-SOUTHWEST OF AND ABOUT 1 FT (0.3 M) LOWER THAN THE CENTERLINE OF ROUTE 100, 25.5 FT (7.8 M) SOUTH-SOUTHEAST OF POLE NUMBER 242/34, 28.8 FT (8.8 M) EAST-NORTHEAST OF 3 SMALL DEAD ELM TREES AND 7.0 FT (2.1 M) SOUTH OF THE END OF A STEEL GUARD RAIL.

SECONDARY CONTROL



* MAIN TRAVERSE COMPLETED ON 1/10/2020 BY R.GILMAN AND B.HERRING


ALIGNMENT TIES

	VT ROUTE 100	
STATION	NORTHING	EASTING
POB 19765.802	368110.646	1580251.344
POE 20315.802	368523.395	1579887.836

DATUM	
VERTICAL	NAVD 88
HORIZONTAL	NAD83 (2011)
ADJUSTMENT	COMPASS

PROJECT NAME: PLYMOUTH	
PROJECT NUMBER: STP DECK(52)	
FILE NAME: sl8b0071ie.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. McCARTHY	DRAWN BY: B. HERRING
DESIGNED BY: VTRANS	CHECKED BY: H. MCGOWAN
TIE SHEET	SHEET 8 OF 29





RIPARIAN BUFFER

N/F  
DUMAS, DANIEL

N/F  
PINGREE, RODNEY I.  
& KATHIE L.

N/F  
RUTLEDGE, KAREN  
AND MICHAEL

N/F  
SMYTH, GERARD

RUMNEY  
0%-3% SLOPES  
FINE SANDY LOAM  
K=0.24

BERKSHIRE/MONADNOCK  
35%-65% SLOPES  
VERY STONY  
K=0.24/0.28

SCALE 1" = 20'-0"  
20 0 20

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8b007epsc.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. McCARTHY	SHEET	9 OF 29
DESIGNED BY:	R. PELLETT		
EPSC EXISTING SITE PLAN			

APPROX. EXISTING R.O.W.

BLACK RIVER  
FLOW

APPROX. EXISTING R.O.W.

VT ROUTE 100  
TO LUDLOW

VT ROUTE 100  
TO BRIDGEWATER

199+00

200+00

201+00

202+00

RIPARIAN BUFFER

VT STATE PLANE GRID

APPROX. EXISTING R.O.W.

RIPARIAN BUFFER

**CONSTRUCT DRIVE:**

STA 198+83.50 - 199+13.00 RT  
(4' PAVED APRON)

**REMOVE SIGNS:**

STA 199+54.00 RT  
STA 200+95.00 LT

**WATERBORNE 4 INCH WHITE LINE:**

STA 198+75.00 - STA 202+25.00 LT & RT

**WATERBORNE 4 INCH YELLOW LINE:**

STA 198+75.00 - STA 202+25.00 LT & RT


**TRAFFIC SIGN, TYPE A:**

STA 199+94.00 RT (VD-701)  
STA 200+63.00 LT (VD-700)  
STA 200+63.00 LT (VD-701)

**DELINEATOR WITH STEEL POST:**

STA 198+56.00 LT (GREEN)  
STA 199+14.00 RT (BLUE)  
STA 201+85.00 LT (BLUE)  
STA 201+71.00 RT (GREEN)

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS		NEW SIGN "A"	NEW SIGN POSTS SQUARE STEEL (in)					REMARKS	SIGN DETAIL	
		WIDTH (in)	HEIGHT (in)		NO. OF POSTS			ANCHOR	SLEEVE		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
					1.75	2.0	2.5					
199+94.00 RT	BRIDGE 107 VT 100	6	10	0.42	1	10			X		VD-701	T-42
200+63.00 RT	BRIDGE 107 VT 100	6	10	0.42	1	10			X		VD-701	T-42
200+63.00 RT	0100 1412 0380	6	10	0.42	-	-			-		VD-700	T-44
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS & THE VTRANS "SIGN POST DESIGN GUIDELINE."					TOTAL	SF	1.26	FT	20	EA	SHSM = FHWA STANDARD HIGHWAY SIGNS & MARKINGS BOOK	



**SIGN LEGEND**

	EXISTING SIGNS
	NEW SIGNS
	N = NEW
	R = REMOVE

EXISTING BRIDGE INFORMATION  
BUILT 1954,  
SINGLE SPAN STEEL BEAM BRIDGE  
CAST-IN-PLACE CONCRETE DECK  
87' MAXIMUM SPAN



SCALE 1" = 20'-0"  
20 0 20

PROJECT NAME: PLYMOUTH	PLOT DATE: 24-AUG-2022
PROJECT NUMBER: STP DECK(52)	DRAWN BY: R. PELLETT
FILE NAME: sl8b007border.dgn	CHECKED BY: F. BARROWS
PROJECT LEADER: J.B. MCCARTHY	SHEET 10 OF 29
DESIGNED BY: F. BARROWS	
DECK REPLACEMENT LAYOUT	

BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM  
 STA 199+67.87 LT - STA 200+56.87 LT  
 STA 200+00.54 RT - STA 200+89.54 RT


GUARDRAIL APPROACH SECTION  
 STA 199+38.29 LT - STA 199+67.87 LT  
 STA 199+70.95 RT - STA 200+00.54 RT  
 STA 200+56.87 LT - STA 200+86.45 LT  
 STA 200+89.54 RT - STA 201+19.12 RT

HD STEEL BEAM GUARDRAIL, GALVANIZED  
 STA 198.55.47 LT - 199+38.29 LT  
 STA 199+13.33 RT - 199+70.95 RT  
 STA 200+86.45 LT - 201+83.46 LT  
 STA 201+19.12 RT - 201+70.84 RT



BRIDGE RAIL LAYOUT

SCALE 1" = 20'-0"




ACUTE CORNER BRIDGE END

SCALE 1" = 2'-0"

PROJECT NAME: PLYMOUTH  
 PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007rail.dgn  
 PROJECT LEADER: J.B. MCCARTHY  
 DESIGNED BY: F. BARROWS  
 RAIL LAYOUT

PLOT DATE: 24-AUG-2022  
 DRAWN BY: R. PELLETT  
 CHECKED BY: F. BARROWS  
 SHEET II OF 29



L = 130.00 FT  
 K = 144  
 SSD = INF FT  
 G1 = -0.4622% ; G2 = 0.4397%


L = 120.00 FT  
 K = 112  
 SSD = INF FT  
 G1 = -0.7056% ; G2 = 0.3619%

L = 169.47 FT  
 K = 148  
 SSD = 1027 FT  
 G1 = 0.4397% ; G2 = -0.7056%

### VT 100 PROFILE

HORIZONTAL SCALE 1" = 20'.0"  
 VERTICAL SCALE 1" = 10'.0"

PROJECT NAME: PLYMOUTH	
PROJECT NUMBER: STP DECK(52)	
FILE NAME: sl8b007Pro.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J. B. MCCARTHY	DRAWN BY: K. LIHIC
DESIGNED BY: K. LIHIC	CHECKED BY: F. BARROWS
VT ROUTE 100 PROFILE	SHEET 12 OF 29




**VT 100 MATERIAL TRANSITION**


HORIZONTAL SCALE: 1" = 20'-0"  
 VERTICAL SCALE: 1" = 2'-0"

*SEE ROADWAY TYPICAL SECTION FOR PAVEMENT DESIGN INFORMATION

PROJECT NAME: PLYMOUTH	
PROJECT NUMBER: STP DECK(52)	
FILE NAME: sl8b007Pro.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. MCCARTHY	DRAWN BY: K. LIHIC
DESIGNED BY: K. LIHIC	CHECKED BY: F. BARROWS
MATERIAL TRANSITION DIAGRAM	SHEET 13 OF 29




EXISTING BRIDGE TYPICAL SECTION




EXISTING MIDDLE DIAPHRAGM


THE CONTRACTOR SHALL REMOVE THE SECOND AND THIRD DIAPHRAGMS IN THE CENTER BAY OF THE BRIDGE AS SHOWN




PHASE 1 TYPICAL



PLAN OF EXISTING DIAPHRAGMS TO BE CUT



PHASE 2 TYPICAL



PROPOSED BRIDGE TYPICAL SECTION

SCALE  $\frac{3}{8}$ " = 1'-0"






TRAFFIC CONTROL NOTES


1. PHASING LAYOUTS ARE CONCEPTUAL ONLY. PHASING LAYOUT IS INTENDED TO COMMUNICATE BASIC SITE CONDITIONS THAT INCLUDE LANE, BARRIER, SUPPORT OF EXCAVATION, AND TRAFFIC LIGHT LOCATIONS. REFERENCE MUTCD SECTION 6H.01 FIGURE 6H-12 FOR CONCEPT APPROACH SIGNAGE AND SPACING.
2. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AND TOWN HIGHWAYS THAT ACCESS VT-100 WITHIN THE PROJECT LIMITS AT ALL TIMES, FOR ALL PHASES OF CONSTRUCTION. IF ACCESS CANNOT BE MAINTAINED, THE CONTRACTOR SHALL COORDINATE ACCESS WITH THE PROPERTY OWNER AND OBTAIN APPROVAL OF THE ENGINEER.
3. CONCRETE BARRIER SIDE EXPOSED TO TRAFFIC TO BE DELINEATED. DELINEATION COLOR TO MATCH CORRESPONDING TEMPORARY PAVEMENT MARKING.

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007phaseTyp.dgn PLOT DATE: 24-AUG-2022  
PROJECT LEADER: J.B. McCARTHY DRAWN BY: R. PELLETT  
DESIGNED BY: F. BARROWS CHECKED BY: F. BARROWS  
PHASING TYPICAL SECTIONS SHEET 14 OF 29




**LEGEND**

-  CRASH ATTENUATOR
-  TEMPORARY STOP BAR
-  SIGN
-  CONCRETE BARRICADE
-  TRAFFIC SIGNAL



BLACK ON FLORESENT ORANGE (B/FO) "IN LANE " D






**IN LANE SIGN DETAIL**  
NOT TO SCALE




SCALE 1" = 20'-0"  
20 0 20

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8b007phaseLayout.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. MCCARTHY	SHEET	15 OF 29
DESIGNED BY:	R. PELLETT		
PHASING LAYOUT 1			

**LEGEND**

-  CRASH ATTENUATOR
-  TEMPORARY STOP BAR
-  SIGN
-  CONCRETE BARRICADE
-  TRAFFIC SIGNAL



SCALE 1" = 20'-0"  
 20 0 20

PROJECT NAME: PLYMOUTH	PLOT DATE: 24-AUG-2022
PROJECT NUMBER: STP DECK(52)	DRAWN BY: R. PELLETT
FILE NAME: sl8b007phaseLayout.dgn	CHECKED BY: F. BARROWS
PROJECT LEADER: J.B. MCCARTHY	SHEET 16 OF 29
DESIGNED BY: R. PELLETT	
PHASING LAYOUT 2	



33 - S501.2 @ 6" TOP  
 22 - S501.2 @ 9" BOTTOM  
 USE CUT OFFS AT ABUT 2

140 - S501.2 @ 6" TOP  
 94 - S501.2 @ 9" BOTTOM

174 - S504.2 @ 6"

ABUT 1

ABUT 2

CL BEARING ABUT 2  
 STA 200+97.58

END BRIDGE  
 STA 200+89.00  
 EL. 1156.63

VT 100  
 STATIONING

BEGIN BRIDGE  
 STA 200+00.00  
 EL. 1156.78

CL BEARING ABUT 1  
 STA 200+01.41

13 - S502.2 @ 12"  
 TOP & BOTTOM

7 - S502.2 @ 6"  
 TOP & BOTTOM

3 - S506.2 @ 6"  
 TOP & BOTTOM

7 - S502.2 @ 6"  
 TOP & BOTTOM

13 - S506.2 @ 12"  
 TOP & BOTTOM


174 - S507.2 @ 6"

140 - S505.2 @ 6" TOP  
 94 - S505.2 @ 9" BOTTOM

33 - S505.2 @ 6" TOP  
 22 - S505.2 @ 9" BOTTOM  
 USE CUT OFFS AT ABUT 1

DECK REINFORCING PLAN

SCALE 3/16" = 1'-0"



BRIDGE TYPICAL SECTION

SCALE 3/8" = 1'-0"

** SPECIAL PROVISION  
 (CONCRETE, HIGH PERFORMANCE CLASS PC4)



NOTE:

- NF = NEAR FACE
- FF = FAR FACE
- EF = EACH FACE
- ▲ = CUT TO FIT IN FIELD
- 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
- MINIMUM LAP SPLICE LENGTH #5 = 2'-4"


PROJECT NAME: PLYMOUTH  
 PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007super.dgn  
 PROJECT LEADER: J.B. McCARTHY  
 DESIGNED BY: F. BARROWS  
 DECK REINFORCING


PLOT DATE: 24-AUG-2022  
 DRAWN BY: R. PELLETT  
 CHECKED BY: F. BARROWS  
 SHEET 17 OF 29



BRIDGE END TYPICALS AT BEAM  
SCALE 1" = 1'-0"




CURTAINWALL ELEVATION ABUTMENT #1




CURTAINWALL ELEVATION ABUTMENT #2

NOTE:  
 NF = NEAR FACE  
 FF = FAR FACE  
 EF = EACH FACE  
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS  
 ▲ = CUT TO FIT  
 2'-4" LAP BAR UNLESS OTHERWISE SPECIFIED ON THE PLANS


PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8B007subt.dgn	DESIGNED BY:	F. BARROWS
PROJECT LEADER:	J.B. McCARTHY	CHECKED BY:	F. BARROWS
BRIDGE END DETAILS		SHEET	18 OF 29



ELEVATION BEARING BOX OUT  
SCALE 1" = 1'-0"




ELEVATION BEARING BOX OUT  
SCALE 1" = 1'-0"




BEARING BOX OUT DETAIL  
SCALE 1" = 1'-0"

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8B007sub1.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. McCARTHY	SHEET	19 OF 29
DESIGNED BY:	F. BARROWS		
BEARING DETAILS			



ASPHALTIC PLUG  
JOINT DETAIL "B"  
SEE "BRIDGE JOINT  
ASPHALTIC PLUG S-400"




APPROACH SLAB ELEVATION  
SCALE 1/2" = 1'-0"


NOTE:  
NF = NEAR FACE  
FF = FAR FACE  
EF = EACH FACE  
3" CLEAR, UNLESS OTHERWISE  
SPECIFIED ON THE PLANS  
▲ = CUT TO FIT  
2'-2" LAP BAR UNLESS OTHERWISE  
SPECIFIED ON THE PLANS

APPROACH SLAB LAYOUT  
SCALE 3/8" = 1'-0"


PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8b007super.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. MCCARTHY	APPROACH SLAB DETAILS	SHEET 20 OF 29
DESIGNED BY:	F. BARROWS		




WINGWALL SECTION TYPICAL  
SCALE 1" = 1'-0"



WINGWALL ELEVATION TYPICAL  
SCALE 1" = 1'-0"




WINGWALL PLAN TYPICAL  
SCALE 1" = 1'-0"




BEAM ELEVATION  
SCALE 1" = 1'-0"

NOTE:  
NF = NEAR FACE  
FF = FAR FACE  
EF = EACH FACE  
3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS  
▲ = CUT TO FIT  
2'-4" LAP BAR UNLESS OTHERWISE SPECIFIED ON THE PLANS

PROJECT NAME:	PLYMOUTH
PROJECT NUMBER:	STP DECK(52)
FILE NAME:	sl8B007sub1.dgn
PROJECT LEADER:	J.B. MCCARTHY
DESIGNED BY:	F. BARROWS
WINGWALL AND BEAM DETAILS	
PLOT DATE:	24-AUG-2022
DRAWN BY:	R. PELLETT
CHECKED BY:	F. BARROWS
SHEET	21 OF 29



RAILING TRANSITION PLAN





RAILING TRANSITION ELEVATION

NOTES:


1. ALL APPROACH RAIL SPLICES SHALL BE LAPPED IN THE DIRECTION OF TRAFFIC FLOW.
2. TUBE AND STEEL POST MATERIALS, DIMENSION SIZES AND NOTES SHALL BE THE SAME AS THOSE OF THE BRIDGE RAIL, UNLESS OTHERWISE NOTED.
3. APPROACH RAIL BOLTS SHALL BE ASTM A307 GRADE A AND NUTS SHALL BE AASHTO M291 (ASTM A563 GRADE A OR BETTER) (GALVANIZED). WASHERS SHALL BE ASTM F844.
4. PRIOR TO GALVANIZING, GRIND ALL EDGES TO A MINIMUM RADIUS OF 1/16".

PROJECT NAME: PLYMOUTH  
 PROJECT NUMBER: STP DECK(52)


FILE NAME: sl8b007rail.dgn PLOT DATE: 24-AUG-2022  
 PROJECT LEADER: J.B. MCCARTHY DRAWN BY: R. PELLETT  
 DESIGNED BY: F. BARROWS CHECKED BY: F. BARROWS  
 RAIL DETAIL SHEET 1 SHEET 22 OF 29




**DETAIL "C"**  
SCALE: 3" = 1' - 0"




**END CAP PLATE DETAIL**  
SCALE: 3" = 1' - 0"




**THRIE-BEAM TERMINAL CONNECTION PLAN VIEW**  
SCALE: 1" = 1' - 0"



**CONNECTION PLATE**  
SCALE: 1 1/2" = 1' - 0"



**SECTION B-B**  
SCALE: 1" = 1' - 0"



**DETAIL A - TERMINAL CONNECTION ELEVATION VIEW**  
SCALE: 1" = 1' - 0"

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007rail.dgn  
PROJECT LEADER: J.B. MCCARTHY  
DESIGNED BY: F. BARROWS  
RAIL DETAIL SHEET 2


PLOT DATE: 24-AUG-2022  
DRAWN BY: R. PELLETT  
CHECKED BY: F. BARROWS  
SHEET 23 OF 29

# REINFORCING STEEL SCHEDULE

ITEM	EACH	SIZE	LENGTH	MARK	TYPE	A	B	C	D	E	F	G	H	J	K	R	O	ITEM	EACH	SIZE	LENGTH	MARK	TYPE	A	B	C	D	E	F	G	H	J	K	R	O						
<b>DECK</b>																																									
▲	289	5	18'- 10"	S501.2	STR	18'- 10"																																			
	120	5	30'- 9"	S502.2	STR	30'- 9"																																			
	174	5	3'- 10"	S504.2	S5	0'- 10"	0'- 6"	1'- 2"	0'- 6"			0'- 10"																													
▲	289	5	18'- 10"	S505.2	STR	18'- 10"																																			
	138	5	30'- 9"	S506.2	STR	30'- 9"																																			
	174	5	3'- 10"	S507.2	S5	0'- 10"	0'- 6"	1'- 2"	0'- 6"			0'- 10"																													
	32	8	4'- 4"	S801.2	22		1'- 9"	2'- 7"	---				1'- 3"	---	1'- 3"	---																									
<b>APPROACH SLAB 1</b>																																									
	5	5	17'- 3"	AS501.2	STR	17'- 3"																																			
▲	11	5	16'- 11"	AS502.2	STR	16'- 11"																																			
▲	54	5	17'- 2"	AS503.2	STR	17'- 2"																																			
	1	5	23'- 10"	AS504.2	STR	23'- 10"																																			
	1	5	24'- 3"	AS505.2	STR	24'- 3"																																			
	3	5	7'- 0"	AS506.2	22		3'- 6"	3'- 6"	---				2'- 6"	---	2'- 6"	---																									
▲	31	5	21'- 1"	AS601.2	1	1'- 10"	19'- 3"																																		
▲	35	10	39'- 0"	AS1001.2	1	1'- 10"	37'- 2"																																		
<b>CURTAIN WALL 1</b>																																									
	20	5	23'- 10"	1A501.2	STR	23'- 10"																																			
	34	5	4'- 2"	1A502.2	22		1'- 6"	0'- 7"	2'- 1"																																
	38	5	11'- 7"	1A503.2	S5	2'- 2"	3'- 7"	0'- 6"	3'- 2"				2'- 2"	1'- 6"	---	1'- 6"	---																								
<b>CURTAIN WALL 2</b>																																									
	14	5	23'- 10"	2A501.2	STR	23'- 10"																																			
<b>WINGWALL 1</b>																																									
▲	11	5	1'- 9"	1W501.2	STR	1'- 9"																																			
▲	3	5	9'- 6"	1W502.2	S10		4'- 0"	1'- 6"	4'- 0"																																
▲	6	6	3'- 6"	1W601.2	STR	3'- 6"																																			
<b>WINGWALL 2</b>																																									
▲	11	5	1'- 9"	2W501.2	STR	1'- 9"																																			
▲	3	5	9'- 6"	2W502.2	S10		4'- 0"	1'- 6"	4'- 0"																																
▲	6	6	3'- 6"	2W601.2	STR	3'- 6"																																			
<b>WINGWALL 3</b>																																									
▲	11	5	1'- 9"	3W501.2	STR	1'- 9"																																			
▲	3	5	9'- 6"	3W502.2	S10		4'- 0"	1'- 6"	4'- 0"																																
▲	6	6	3'- 6"	3W601.2	STR	3'- 6"																																			
<b>WINGWALL 4</b>																																									
▲	11	5	1'- 9"	4W501.2	STR	1'- 9"																																			
▲	3	5	9'- 6"	4W502.2	S10		4'- 0"	1'- 6"	4'- 0"																																
▲	6	6	3'- 6"	4W601.2	STR	3'- 6"																																			

~ NOTES ~

- UNLESS OTHERWISE DESIGNATED, ALL BAR REINFORCEMENT FOR CONCRETE IN SIZES UP TO AND INCLUDING NO. 18 SHALL CONFORM TO THE REQUIREMENTS OF THE "SPECIFICATIONS FOR DEFORMED BILLET-STEEL BARS FOR CONCRETE REINFORCEMENT", AASHTO M31 (ASTM A 615-S1). ALL BARS SHALL BE GRADE 60, UNLESS OTHERWISE DESIGNATED.
- FOR TYPICAL BENDING DETAILS, RECOMMENDED PIN DIAMETER "D" OF BENDS AND HOOKS, AND OTHER STANDARD PRACTICE, SEE CURRENT CONCRETE REINFORCING STEEL INSTITUTE "MANUAL OF STANDARD PRACTICE".
- BARS WHICH REQUIRE MORE ACCURATE BENDING THAN STANDARD PRACTICES SHOULD HAVE LIMITS INDICATED.
- ALL DIMENSIONS ARE OUT TO OUT OF BAR EXCEPT "A" AND "G" ON STANDARD 180 DEGREE AND 135 DEGREE HOOKS.
- "J" DIMENSION ON 180 DEGREE HOOKS TO BE SHOWN ONLY WHERE NECESSARY TO RESTRICT HOOK SIZE. OTHERWISE, STANDARD HOOKS ARE TO BE USED.
- "H" DIMENSION ON STIRRUPS TO BE SHOWN ONLY WHEN NECESSARY TO MAINTAIN CLEARANCES.
- WHERE SLOPE DIFFERS FROM 45 DEGREES, DIMENSIONS "H" AND "K" MUST BE SHOWN.
- ▲ DENOTES BARS TO BE CUT IN FIELD.
- * DENOTES ONE EXTRA BAR ADDED FOR TESTING PURPOSES.
- △ DENOTES TWO EXTRA BARS ADDED FOR TESTING PURPOSES.
- E IN BAR MARK PREFIX DENOTES EPOXY COATED REINFORCING STEEL.



ASTM STANDARD REINFORCING BARS				
BAR SIZE DESIGNATION	WEIGHT POUNDS PER FOOT	NOMINAL DIMENSIONS ROUND SECTION		
		DIAMETER INCHES	AREA INCHES ²	PERIMETER INCHES
#3	0.376	0.375	0.11	1.178
#4	0.668	0.500	0.20	1.571
#5	1.043	0.625	0.31	1.963
#6	1.502	0.750	0.44	2.356
#7	2.04	0.875	0.60	2.749
#8	2.670	1.000	0.79	3.14
#9	3.400	1.13	1.00	3.54
#10	4.3	1.270	1.27	3.990
#11	5.31	1.410	1.56	4.430
#14	7.65	1.69	2.25	5.32
#18	13.60	2.26	4.00	7.09

~ REINFORCING STEEL CORROSION RESISTANCE LEVEL ~







THE REINFORCING STEEL MARKS IN THIS SCHEDULE INDICATE THE REQUIRED BAR CORROSION RESISTANCE LEVEL. CORROSION RESISTANCE LEVEL IS DENOTED WITH A .2 FOR LEVEL TWO SUFFIX OR .3 FOR LEVEL THREE SUFFIX. .1 FOR LEVEL ONE IS TO BE OMITTED. THE BAR MATERIAL TYPE AND BAR STEEL GRADE PROVIDED FOR EACH CORROSION LEVEL WILL BE RECORDED ON THE PLAN SET P1 SHEET FOR AS-BUILT RECORD PLAN ARCHIVES.

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: STP DECK(52)







FILE NAME: sl8b007r.ss.dgn  
PROJECT LEADER: J.B. McCARTHY  
DESIGNED BY: K. LIHC  
REINFORCING STEEL SCHEDULE

PLOT DATE: 24-AUG-2022  
DRAWN BY: R. PELLETT  
CHECKED BY: F. BARROWS  
SHEET 24 OF 29








PROJECT NAME: PLYMOUTH	
PROJECT NUMBER: STP DECK(52)	
FILE NAME: s18b007xs.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. MCCARTHY	DRAWN BY: K. LIHIC
DESIGNED BY: K. LIHIC	CHECKED BY: F. BARROWS
MAINLINE CROSS SECTIONS 1	SHEET 25 OF 29



PROJECT NAME: PLYMOUTH	
PROJECT NUMBER: STP DECK(52)	
FILE NAME: si8b007xs.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. MCCARTHY	DRAWN BY: K. LIHC
DESIGNED BY: K. LIHC	CHECKED BY: F. BARROWS
MAINLINE CROSS SECTIONS 2	SHEET 26 OF 29



PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	K. LIHIC
FILE NAME:	sl8b007xs.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. MCCARTHY	MAINLINE CROSS SECTIONS	3
DESIGNED BY:	K. LIHIC	SHEET	27 OF 29

VAOT LOW GROW/FINE FESCUE MIX						
LBS/AC						
WEIGHT	BROADCAST	HYDROSEED	NAME	LATIN NAME	GERM	PURITY
38%	57	95	CREEPING RED FESCUE	FESTUCA RUBRA VAR. RUBRA	90%	98%
29%	43.5	72.5	HARD FESCUE	FESTUCA LONGIFOLIA	85%	95%
15%	22.5	37.5	CHEWINGS FESCUE	FESTUCA RUBRA VAR. COMMUTATA	87%	95%
15%	22.5	37.5	ANNUAL RYEGRASS	LOLIUM MULTIFLORUM	90%	95%
3%	4.5	7.5	INERTS			
100%	150	250				

VAOT RURAL AREA MIX						
LBS/AC						
WEIGHT	BROADCAST	HYDROSEED	NAME	LATIN NAME	GERM	PURITY
37.5%	22.5	45	CREEPING RED FESCUE	FESTUCA RUBRA VAR. RUBRA	85%	98%
37.5%	22.5	45	TALL FESCUE	FESTUCA ARUNDINACEA	90%	95%
5.0%	3	6	RED TOP	AGROSTIS GIGANTEA	90%	95%
15.0%	9	18	WHITE FIELD CLOVER	TRIFOLIUM REPENS	85%	98%
5.0%	3	6	ANNUAL RYE GRASS	LOLIUM MULTIFLORUM	85%	95%
100%	60	120				

GENERAL AMENDMENT GUIDANCE		
FERTILIZER	LIME	
10/20/10	AG LIME	PELLITIZED
500 LBS/AC	2 TONS/AC	1 TONS/AC

#### CONSTRUCTION GUIDANCE

1. SEED MIX: THE CONTRACTOR SHALL COORDINATE WITH THE RESIDENT ENGINEER ON WHICH SEED MIX TO USE.
2. SEED MIX: USE AS INDICATED IN THE PLANS AND/OR FOR ALL ESTABLISHED UPLAND (NON WETLAND) AREAS DISTURBED BY THE CONTRACTOR.
3. ALL SEED MIXTURES: SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS SEED.
4. FERTILIZER AND LIMESTONE: SHALL FOLLOW RATES SHOWN ON PLAN OR AS DIRECTED BY THE ENGINEER.
5. HAY MULCH: TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS/ACRE, ACHIEVE 90% GROUND COVER OR AS DIRECTED BY THE ENGINEER.
6. HYDROSEEDING: ALTHOUGH GUIDANCE IS GIVEN ABOVE THE SITE CONDITIONS AND THE TYPE OF HYDROSEED PROPOSED FOR USE WILL ULTIMATELY DICTATE THE AMOUNTS AND TYPES OF SOIL AMENDMENTS TO BE APPLIED.
7. TURF ESTABLISHMENT: PLACING SEED, FERTILIZER, LIME AND MULCH PRIOR TO SEPTEMBER 15 AND AFTER APRIL 15 CAN BETTER ENSURE A VIGOROUS GROWTH OF GRASS.

ADAPTED FROM VTRANS TECHNICAL LANDSCAPE MANUAL FOR ROADWAYS AND TRANSPORTATION FACILITIES

TURF ESTABLISHMENT

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 651 FOR SEED (PAY ITEM 651.15)

REVISIONS	
JANUARY 12, 2015	WHF

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: STP DECK(52)

FILE NAME: sl8b007epsc.dgn	PLOT DATE: 24-AUG-2022
PROJECT LEADER: J.B. McCARTHY	DRAWN BY: R. PELLETT
DESIGNED BY: R. PELLETT	CHECKED BY: F. BARROWS
EPSC DETAIL	SHEET 28 OF 29

**CONSTRUCT DRIVE:**

STA 198+83.50 - 199+13.00 RT  
(4' PAVED APRON)

**REMOVE SIGNS:**

STA 199+54.00 RT  
STA 200+95.00 LT

**WATERBORNE 4 INCH WHITE LINE:**

STA 198+75.00 - STA 202+25.00 LT & RT

**WATERBORNE 4 INCH YELLOW LINE:**

STA 198+75.00 - STA 202+25.00 LT & RT

**TRAFFIC SIGN, TYPE A:**

STA 199+94.00 RT (VD-701)  
STA 200+63.00 LT (VD-700)  
STA 200+63.00 LT (VD-701)

**DELINEATOR WITH STEEL POST:**

STA 198+56.00 LT (GREEN)  
STA 199+14.00 RT (BLUE)  
STA 201+85.00 LT (BLUE)  
STA 201+71.00 RT (GREEN)

**N/F  
DUMAS, DANIEL**

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS		NEW SIGN "A"	NEW SIGN POSTS SQUARE STEEL (in)						REMARKS	SIGN DETAIL	
		WIDTH (in)	HEIGHT (in)		NO. OF POSTS			ANCHOR	SUPPORT	DETAIL ON SHEET NUMBER		STD. SHEET NUMBER	
					1.75	2.0	2.5						
199+94.00 RT	BRIDGE 107 VT 100	6	10	0.42	1	10			X		VD-701		T-42
200+63.00 RT	BRIDGE 107 VT 100	6	10	0.42	1	10			X		VD-701		T-42
200+63.00 RT	0100 1412 0380	6	10	0.42	-	-			-		VD-700		T-44
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS & THE VTRANS "SIGN POST DESIGN GUIDELINE."					TOTAL	SF	1.26		EA		FT	20	


**N/F  
PINGREE, RODNEY I.  
& KATHIE L.**

EXISTING SIGNS

NEW SIGNS

SIGN LEGEND

N	=	NEW
R	=	REMOVE



**N/F  
RUTLEDGE, KAREN  
AND MICHAEL**

**N/F  
SMYTH, GERARD**

SCALE 1" = 20'-0"  
20 0 20

PROJECT NAME:	PLYMOUTH	PLOT DATE:	24-AUG-2022
PROJECT NUMBER:	STP DECK(52)	DRAWN BY:	R. PELLETT
FILE NAME:	sl8b007row.dgn	CHECKED BY:	F. BARROWS
PROJECT LEADER:	J.B. MCCARTHY	SHEET	29 OF 29
DESIGNED BY:	F. BARROWS		
R.O.W. LAYOUT SHEET			