

Wolcott BF 1446(38) Alternatives Presentation Meeting

Town Highway 3 – Bridge 6 over Lamoille River

December 1, 2021



AGENCY OF TRANSPORTATION

Introductions

Bob Klinefelter, P.E.

VTrans Design Project Manager

Laura Stone, P.E.

VTrans Scoping Engineer



Purpose of Meeting

- Provide an understanding of our approach to the project
- Provide an overview of project constraints
- Discuss alternatives that were considered
- Discuss our recommended alternative
- Provide an opportunity to ask questions and voice concerns





Location Map

Wolcott United Methodist Church

Wolcott Store

Jones Rc

Lamoille River bille Valley Rail Trail (h)

United States Postal Service

Bridge 6 Project Location

Wolcott Town Office

Lamoille River

chool/St



¹amoille River

-1

EHIIIRd

ENIIR

Meeting Overview

- VTrans Project Development Process
- Project Overview
 - Existing Conditions
 - Alternatives Considered
 - Recommended Alternative
- Maintenance of Traffic
- Schedule
- Summary
- Next Steps
- Questions



VTrans Project Development Process



AGENCY OF TRANSPORTATION

Description of Terms Used





ACT 153 of the 2012 Legislative Session

	Local Share						
	Road Closed	Road Open During					
	During						
	Construction	Construction					
Rehabilitation	2.5%	5%					
Replacement	5%	10%					

- Per Act 153, the local share is reduced by 50% for rehabilitating versus replacement
- Per Act 153, the local share is reduced by 50% for closing the road to traffic during construction



Looking South over Bridge 6



Existing Conditions – Bridge #6

08/09/2017

- Roadway Classification Local Road
- Bridge Type 100' Span Parker Pony Truss
- Ownership Town of Wolcott
- Constructed in 1928, reconstructed in 2004

Looking North over Bridge 6

Existing Conditions – Bridge #6

Utilities (aerial and future sewer)

08/13/20

Existing Conditions – Bridge #6

- The bridge was closed to traffic in 2018 and a temporary bridge was placed on top of the existing pony truss. During the annual inspection, it was discovered that the gusset connection, located at the bottom chord end of abutment #1 upstream bearing, had deteriorated to the point where it completely cracked through with some deformation seen.
- The shoulder width on Bridge 6 is substandard.
- Bridge 6 does not span bank full width.



Condition Ratings

Existing Conditions - Bridge #6

- Deck Rating
- Superstructure Rating
- Substructure Rating

8 (Very Good) Failed – Temporary in place 6 (Satisfactory)

Southern Abutment

Existing Conditions - Bridge #6

08/09/2017

Upstream Fascia

08/09/2017 **Existing Conditions - Bridge #6**

2018 Inspection Finding Photo



2018 Inspection Finding Photo

Existing Conditions - Bridge #6

Resources – Looking Upstream



08/09/2017

Existing Conditions – Bridge #6

- Wetland 130' upstream on northern bank
- Archaeologically sensitive south of the river
- Wildlife Habitat
- Historic Resources Bridge 6 and 10-4(f) properties



Design Criteria and Considerations

- Average Daily Traffic
 - 350 vehicles per day
- Design Hourly Volume
 - 55 vehicles per hour
- % Trucks
 - 10.6%



Alternatives Considered – Bridge #6

- No Action
 - Additional maintenance required within 10 years
- Truss Rehabilitation
 - Structural deficiencies would be addressed
 - Matches existing typical (9'/1')
 - 30-year design life
- Full Bridge Replacement with New Pony Truss (On and Off Alignment)
 - 120' span (minimum) for improved hydraulics
 - Widen to meet minimum standard (9'/3') with sidewalk option
 - 75-year design life
- Full Bridge Replacement with Steel Beam Bridge (On and Off Alignment)
 - 120' span (minimum) for improved hydraulics
 - Widen to meet minimum standard (9'/3') with sidewalk option VEDN
 - 75-year design life



Alternative 1 Typical Section





Truss Rehabilitation - Bridge #6

9'/1' typical



IOOH 12

Alternative 1 Layout

LAMOILLE RIVER

Truss Rehabilitation - Bridge #6

- 30-year design life
- 100' span
- Cleaning, repair or replacement of deteriorated truss members, strengthening of members, and repainting.
- Replacement of existing bridge seats and backwalls
- Construct new floor system and deck





New Parker Pony Truss - Bridge #6

• 9'/3' typical with a sidewalk





Alternative 3 On-Alignment Typica VERMONT AGENCY OF TRANSPORTATION



New Steel Beam Bridge - Bridge #6

• 9'/3' typical with a sidewalk





Recommended Alternative - Bridge #6

- A new 120-foot span (minimum) parker pony truss constructed on an improved alignment
 - Original pony truss is narrow for the traffic volumes present and does not meet the minimum hydraulic standards warranting replacement.
 - Abutments to be aligned better with the channel
 - Lengthened to 120' span to improve the hydraulic condition and reduce water surface elevations during flood events
 - -75-year design life



Maintenance of Traffic Options Considered

- Offsite Detour
- Temporary Bridge

ROAD CLOSED

Road Closure

- Detour chosen and signed by Town
- Construction Season duration
- Shortest Detour Route is 1.8 miles end-to-end

Traffic Control – Detour

Regional Detour
Route: School Street to
Flat Iron Road, and VT
Route 15, back to
School Street

- End-to-End Distance: 1.8 miles
- Through Distance: 0.6 miles
- Detour Distance: 1.2 miles
- Added Distance: 0.6 miles



Temporary Bridge/Roadway

 One Lane Temporary Bridge constructed either Upstream or Downstream side of School Street

Upstream Temporary Bridge Layout





Recommendation: Bridge 6

- A new 120-foot span (minimum) parker pony truss constructed on an improved alignment with traffic maintained on an Offsite Detour
 - 120' span for improved hydraulics
 - -9'/3' typical to match corridor
 - 9'/2' is standard
 - Addition of sidewalk
 - Abutments to be aligned better with the channel
 - -75-year design life
 - Utility Relocation (Aerial), future sewer to go through project site
 - Right-of-Way needed
 - Construction Year: 2025



Alternatives Matrix

Wolcott BO 1446(38)	Alternative 1		Alternative 2				Alternative 3			
	Truss Rehabilitation		Full Bridge Replacement with New Parker Pony Truss			Full Bridge Replacement with Steel Beam Bridge				
	On-Alignment		On-alignment		Off-Alignment		On-alignment		Off-Alignment	
	a. Offsite Detour	b. Temporary Bridge	a. Offsite Detour	b. Temporary Bridge	c. Offsite Detour	d. Temporary Bridge	a. Offsite Detour	b. Temporary Bridge	c. Offsite Detour	d. Temporary Bridge
Total Project Costs	1,800,700	2,210,133	5,410,433	6,612,829	6,101,193	7,402,329	4,670,937	5,791,129	5,176,137	6,351,129
Annualized Costs	60,023	73,671	72,139	88,171	81,349	98,698	62,279	77,215	69,015	84,682
Town Cost	45,018	110,507	270,522	661,283	305,060	740,233	233,547	579,113	258,807	635,113
Town Share	2.50%	5%	5%	10%	5%	10%	5%	10%	5%	10%
Project Development Duration	4 years	4 years	4 years	4 years	4 years	4 years	4 years	4 years	4 years	4 years
Construction Duration	6 months	8 months	6 months	8 months	6 months	8 months	6 months	8 months	6 months	8 months
Closure Duration (If Applicable)	Construction Season	NA	Construction Season	NA	Construction Season	NA	Construction Season	NA	Construction Season	NA
Typical Section - Roadway (feet)	24	24	24	24	24	24	24	24	24	24
Typical Section - Bridge (feet)	20	20	24	24	24	24	24	24	24	24
Geometric Design Criteria	Substandard Width		Meets Minimum Standard		Meets Minimum Standard		Meets Minimum Standard		Meets Minimum Standard	
Alignment Change	No Change	No Change	No Change		Northern Approach Shifted 75 feet east		No Change		Northern Approach Shifted 75 feet east	
Bicycle Access	No Change	No Change	Improved	Improved	Improved	Improved	Improved	Improved	Improved	Improved
Pedestrian Access	No Change	No Change	Improved	Improved	Improved	Improved	Improved	Improved	Improved	Improved
Hydraulics	Substandard BFW		Meets Minimum Standard		Meets Minimum Standard		Meets Minimum Standard		Meets Minimum Standard	
Utilities	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation	Aerial Relocation
ROW Acquisition	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Road Closure	Yes	No	Yes	No	Yes	No	Yes	No	Yes	No
Design Life (years)	30	30	75	75	75	75	75	75	75	75

Preliminary Project Schedule

- Construction Start 2025
 - Total Cost Estimate: \$6,100,000
 - Town Share: \$305,000



Next Steps – Bridge #6

This is a list of a few important activities expected in the near future and is not a complete list of activities.

- Wait for Town response to recommendation on proposed project
 - Develop Conceptual plans and distribute for comment
 - Process local agreements
 - Right-of-Way process
 - Updates on project plans and estimates at each submittal



For more information:

https://outside.vermont.gov/agency/vtrans/external/Projects/Structures/19J222



Wolcott BF 1446(38) Questions and Comments Town Highway 3 – Bridge 6 over Lamoille River

December 1, 2021

