

FROM EXISTING GRADE FORM 3" DIAMETER MOUND AND CONTINUOUS SAUCER ON LOWER SIDES OF PLANTING. FIRMLY PACK TO RETAIN ITS SHAPE FOR REPEATED WATERING. MOUND WILL BLEND BACK INTO UPPER BANK.

2" BARK MULCH TAPER AS SHOWN FROM TRUNK.

FINISHED GRADE

EXISTING GRADE

VARIES

LANDSCAPE BACKFILL. SEE SHRUB PLANTING DETAIL FOR NOTES.

ORIGINAL GRADE SHALL PASS THROUGH THE POINT WHERE THE BASE MEETS SOILS/SUBSTRATE AS SHOWN.

12" (MIN)  
SEE PLAN FOR SPACING  
WIDTH OF PLANTING PIT IF SINGLE ROW IS EQUAL TO THE ROOTBALL DIAMETER X 3.

SHRUB PLANTING ON SLOPE DETAIL

2" BARK MULCH TAPER AS SHOWN FROM TRUNK.

FROM EXISTING GRADE FORM A CONTINUOUS SAUCER WITH 3" DIAMETER MOUND AND FIRMLY PACK TO RETAIN ITS SHAPE FOR REPEATED WATERING.

FINISHED GRADE

EXISTING GRADE

VARIES

LANDSCAPE BACKFILL, TAMP TO REMOVE AIR POCKETS. FOR MULTIPLE SHRUBS, PLANT IN AN ALTERNATING PATTERN AND IN A CONTINUOUS PLANTING PIT.

PLACE SHRUB IN THE PLANTING PIT AT THE LEVEL IT WAS GROWN IN AT THE NURSERY OR SLIGHTLY HIGHER. AVOID PLANTING TOO DEEP. TOP OF ROOTBALL SHOULD BE AT FINISHED GRADE.

PLACE ROOTBALL ON TAMPED OR LIGHTLY COMPACTED SUBGRADE. REMOVE ALL PACKAGING.

12" (MIN)  
SEE PLAN FOR SPACING  
WIDTH OF PLANTING PIT IF SINGLE ROW IS EQUAL TO THE ROOTBALL DIAMETER X 3.

SHRUB PLANTING DETAIL

GENERAL NOTES:

1. PLANTINGS SHALL BE PLANTED WITHIN 24 HOURS OF EXCAVATION OF PLANTING PIT.
2. WATER IN ACCORDANCE WITH SECTION 656 OF THE CURRENT VTRANS SPECIFICATIONS FOR CONSTRUCTION AND ITS LATEST REVISIONS.
3. ALL CONTAINERS, NURSERY TAGS, STRING, WIRE OR SURVEYORS TAPE SHALL BE REMOVED AT THE TIME OF PLANTING.
4. ALL PLANT MATERIAL SHALL COMPLY WITH AMERICAN STANDARD FOR NURSERY STOCK ANSI Z60.
5. LAYOUT AND PLANT IN ALTERNATING ROWS AT SPACING SHOWN ON PLANS.

REV.	DATE	DESCRIPTION
0	JUL. II, 2017	ORIGINAL APPROVAL

OTHER STANDARDS REQUIRED: NONE

SHRUB PLANTING DETAILS



STANDARD  
E-2