STATE OF VERMONT
AGENCY OF TRANSPORTATION

PRELIMINARY INFORMATION SHEET (BRIDGE)

Version 11.06.15

LRFD

INDEX OF SHEETS

PLAN SHEETS

1	TITLE SHEET
2	PRELIMINARY INFORMATION
3 - 4	TYPICAL SECTIONS 1 - 2
5 - 6	GENERAL NOTES 1-2
7 - 9	QUANTITY 1 - 3
10	BRIDGE QUANTITY
11	TIE SHEET
12	ALIGNMENT
13	LAYOUT
14	MAINLINE PROFILE
15	DRAINAGE LAYOUT
16	DRAINAGE DETAIL
17	EXISTING UTILITY LAYOUT
18	PROPOSED UTILITY LAYOUT
19	BRIDGE STREET GRAVITY SEWER BRIDGE CROSSING PLAN
20	BRIDGE STREET GRAVITY SEWER BRIDGE CROSSING PROFILE
21	BRIDGE STREET GRAVITY SEWER BRIDGE CROSSING SEWER DETAILS
22	SIGN LAYOUT
23	BORING INFORMATION
24 - 28	BORING LOGS 1 - 5
29	PLAN AND ELEVATION
30	BRIDGE RAIL ELEVATIONS
31	BRIDGE RAIL CONCRETE DETAILS
32	METAL HAND RAILING DETAILS
33	BRIDGE RAIL REINFORCING
34	APPROACH RAIL DETAILS
35	DECK PLAN
36	FRAMING & CROSS FRAME DETAILS
37	GIRDER DETAILS
38 - 39	SPLICE DETAIL 1 - 2
40	BRACING DETAILS
41	FIXED BEARING DETAILS
42	EXPANSION BEARING DETAILS
43	APPROACH SLAB DETAILS
44	ABUTMENT 1
45	ABUTMENT 1 REINFORCING PLAN
46	WING WALLS 1 & 2
47	BACKWALL ABUTMENT 1
48	ABUTMENT 2
49	ABUTMENT 2 REINFORCING AND PILE LAYOUT
50	WING WALLS 3 & 4
51	ABUTMENT 2 BACKWALL DETAILS
52	RETAINING WALL
53	REINFORCING STEEL SCHEDULE SHEET #1
54 - 58	MAINLINE CROSS SECTIONS 1 - 5
59	MATERIAL TRANSITION DIAGRAM
60 - 61	CHANNEL CROSS SECTIONS 1 - 2
62	EPSC NARRATIVE
63	EPSC EXISTING CONDITIONS
64	EPSC DURING CONSTRUCTION
65	EPSC FINAL CONDITIONS
66 - 68	EPSC DETAILS 1 - 3
69	RIGHT OF WAY LAYOUT SHEET
70	RIGHT OF WAY DETAIL SHEET

STANDARDS LIST

A-78	SHARED USE PATH TYPICAL	03-31-2004
A-80	SHARED USE PATH / HIGHWAY INTERSECTION DETAILS	03-31-2004
C-3A	SIDEWALK RAMPS	03-10-2008
C-10	CURBING	02-11-2008
D-1	PRECAST REINFORCED CONCRETE DROP INLET DETAILS	06-01-1994
D-11	STEEL OR IRON GRATES& COVERS (TYPE A)	06-01-1994
D-15	PRECAST REINF CONC. MH-GRATES, CAST IRON GRATE WITH FRAME, TYPE D & E	06-01-1994
E-100	CONSTRUCTION APPROACH SIGNS	01-02-2004
E-102	CONSTRUCTION SIGN DETAILS	06-30-2003
E-102A	CONSTRUCTION SIGN DETAILS	05-01-2004
E-107	DELINEATION, BARRICADES AND DETOURS FOR CONSTRUCTION AREAS	06-30-2003
E-107A	BREAKAWAY BARRICADE DETAILS	06-08-2009
E-121	STANDARD SIGN PLACEMENT - CONVENTIONAL ROAD	08-08-1995
E-134	BRIDGE NUMBER PLAQUE	08-08-1995
E-164	SQUARE STEEL SIGN POST	06-08-2009
E-193	PAVEMENT MARKING DETAILS	08-18-1995
E-195	SHARED USE PATH PAVEMENT MARKINGS AND SIGN DETAILS	06-09-2008
F-2	CHAIN LINK FENCE, TYPE I DETAILS	06-01-1994
G-1	STEEL BEAM GUARDRAIL DETAILS (POST, DELINEATOR, TYPICALS)	01-03-2000
G-1D	STEEL BEAM GUARDRAIL DETAILS (END TERMINAL, ANCHOR, MEDIAN)	01-03-2000

STRUCTURAL DETAIL SHEETS

SD-501.00	CONCRETE DETAILS AND NOTES
SD-502.00	CONCRETE DETAILS AND NOTES
SD-516.10	BRDGE JOINT, ASPHALTIC PLUG
SD-601.00	STRUCTURAL STEEL DETAILS AND NOTES
SD-602.00	STRUCTURAL STEEL PLATE GIRDER AND NOTES

TRAFFIC DATA

YEAR	ADT	DHV	% D	% T	ADTT					
2013	3400	380	53	3	180	20 year ESAL for flexible pavement from	2013	to	2033 :	594000
2033	4100	460	53	3.6	260	40 year ESAL for flexible pavement from	2013	to	2053 :	1323000
						Design Speed :	25	mph		

FINAL HYDRAULIC REPORT

HYDROLOGIC DATA

Date: vised October 2010

DRAINAGE AREA : 34.0 sq. mi.
CHARACTER OF TERRAIN : Hilly to mountainous, mostly rural, mostly forested
STREAM CHARACTERISTICS : Sinuous, incised, gorge at bridge site
NATURE OF STREAMBED : Mixed upstream, ledge at bridge

PEAK FLOW DATA

Q 2.33 =	1600 cfs	Q 50 =	5950 cfs
Q 10 =	3325 cfs	Q 100 =	7225 cfs
Q 25 =	4750 cfs	Q 500 =	10,850 cfs

DATE OF FLOOD OF RECORD 1927
ESTIMATED DISCHARGE: unknown
WATER SURFACE ELEV.: unknown
NATURAL STREAM VELOCITY : @ Q25 = 25.2 fps
ICE CONDITIONS : moderate
DEBRIS: moderate
DOES THE STREAM REACH MAXIMUM HIGHWATER ELEV. RAPIDLY? no
IS ORDINARY RISE RAPID? no
IS STAGE AFFECTED BY UPSTREAM OR DOWNSTREAM CONDITIONS? no
IF YES, DESCRIBE:

WATERSHED STORAGE: < 1%
HEADWATERS:
UNIFORM: X
IMMEDIATELY ABOVE SITE:

EXISTING STRUCTURE INFORMATION

STRUCTURE TYPE: Single span steel beam bridge
YEAR BUILT: 1949
CLEAR SPAN(NORMAL TO STREAM): 89'
VERTICAL CLEARANCE ABOVE STREAMBED: 36' +/-
WATERWAY OF FULL OPENING: 1965 sq. ft.
DISPOSITION OF STRUCTURE: Replace
TYPE OF MATERIAL UNDER SUBSTRUCTURE: See borings

WATER SURFACE ELEVATIONS AT:

Q2.33 =	707.9'	VELOCITY =	21.2 fps
Q10 =	710.1'	"	24.1 fps
Q25 =	711.5'	"	25.8 fps
Q50 =	712.6'	"	26.8 fps
Q100 =	713.7'	"	27.7 fps

LONG TERM STREAMBED CHANGES: None noted

IS THE ROADWAY OVERTOPPED BELOW Q100: No
FREQUENCY: N/A
RELIEF ELEVATION: 732.6'
DISCHARGE OVER ROAD @Q100: N/A

UPSTREAM STRUCTURE

TOWN:	Barre Town	DISTANCE:	2000'
HIGHWAY # :	VT 63	STRUCTURE #:	BR 5
CLEAR SPAN:	15' + 15' = 30'	CLEAR HEIGHT:	12'
YEAR BUILT:	1970	FULL WATERWAY:	360 sf
STRUCTURE TYPE:	Twin cell RC Box		

DOWNSTREAM STRUCTURE

TOWN:	Barre Town	DISTANCE:	3200'
HIGHWAY # :	Parkside Terrace	STRUCTURE #:	BR 13
CLEAR SPAN:	82'	CLEAR HEIGHT:	26'
YEAR BUILT:	1997	FULL WATERWAY:	1750 sf
STRUCTURE TYPE:	Welded plate girder		

LRFR LOAD RATING FACTORS

LOADING LEVELS	TRUCK						
	H-20	HL-93	3S2	6 AXLE	3A. STR.	4A. STR.	5A. SEMI
TONNAGE	20	36	36	66	30	34.5	38
INVENTORY	2.47	1.1					
POSTING							
OPERATING	3.2	1.42	2.11	1.46	2.2	2.11	2.15
COMMENTS:							

PILE DRIVING AND TESTING REQUIREMENTS

1. NOMINAL PILE DRIVING CAPACITY	Rndr:	627.00 KIP
2. PILE TEST RESISTANCE FACTOR	ϕ:	0.65
3. MAXIMUM PILE TIP ELEVATION		VARIES
4. THREE DYNAMIC PILES TESTS REQUIRED		

PROPOSED STRUCTURE

STRUCTURE TYPE: Single span curved steel girder

CLEAR SPAN(NORMAL TO STREAM): 116'
VERTICAL CLEARANCE ABOVE STREAMBED: 38'
WATERWAY OF FULL OPENING: 2145 sq. ft.

WATER SURFACE ELEVATIONS AT:

Q2.33 =	#REF!	VELOCITY=	21.2 fps
Q10 =	#REF!	"	24.1 fps
Q25 =	#REF!	"	25.8 fps
Q50 =	#REF!	"	26.8 fps
Q100 =	#REF!	"	27.7 fps

IS THE ROADWAY OVERTOPPED BELOW Q100: No
FREQUENCY: N/A
RELIEF ELEVATION: 734.3'
DISCHARGE OVER ROAD @Q100: N/A

AVERAGE LOW ELEVATION OF SUPERSTRUCTURE: 732.3'
VERTICAL CLEARANCE: @ Q25 = 20.8'

SCOUR: Abutments to be founded on ledge

REQUIRED CHANNEL PROTECTION: Stone Fill, Type II

PERMIT INFORMATION

AVERAGE DAILY FLOW:	70 cfs	DEPTH OR ELEVATION:
ORDINARY LOW WATER:	30 cfs	1.5'
ORDINARY HIGH WATER:	700 cfs	4.0'

TEMPORARY BRIDGE REQUIREMENTS

STRUCTURE TYPE: None required
CLEAR SPAN (NORMAL TO STREAM):
VERTICAL CLEARANCE ABOVE STREAMBED:
WATERWAY AREA OF FULL OPENING:

ADDITIONAL INFORMATION

TRAFFIC MAINTENANCE NOTES

1. MAINTAIN TRAFFIC ON AN OFF SITE DETOUR.
2. TRAFFIC SIGNALS ARE NOT NECESSARY.
3. SIDEWALKS ARE NOT NECESSARY

DESIGN VALUES

1. DESIGN LIVE LOAD		HL-93
2. FUTURE PAVEMENT	d_p:	3.0 INCH
3. DESIGN SPAN	L:	120.00 FT
4. MIN. MID-SPAN POS. CAMBER @ RELEASE (PRESTRESSED UNITS)	Δ:	--- INCH
5. PRESTRESSING STRAND (0.60 INCH DIAMETER - LOW RELAX)	f_y:	270 KSI
6. PRESTRESSED CONCRETE STRENGTH	f'_c:	6.0 KSI
7. PRESTRESSED CONCRETE RELEASE STRENGTH	f'_{ci}:	5.0 KSI
8. CONCRETE, HIGH PERFORMANCE CLASS AA	f'_c:	- - -
9. CONCRETE, HIGH PERFORMANCE CLASS A	f'_c:	4.0 KSI
10. CONCRETE, HIGH PERFORMANCE CLASS B	f'_c:	3.5 KSI
11. CONCRETE, CLASS C	f'_c:	3.0 KSI
12. REINFORCING STEEL	f_y:	60 KSI
13. STRUCTURAL STEEL AASHTO M270 (WEATHERING)	f_y:	50 KSI
14. SOIL UNIT WEIGHT	γ:	0.140 KCF
15. NOMINAL BEARING RESISTANCE OF SOIL	q_n:	- - -
16. SOIL BEARING RESISTANCE FACTOR (REFER TO AASHTO LRFD)	ϕ:	- - -
17. NOMINAL BEARING RESISTANCE OF ROCK	q_n:	22.2 KSF
18. ROCK BEARING RESISTANCE FACTOR (REFER TO AASHTO LRFD)	ϕ:	0.45
19. NOMINAL AXIAL PILE RESISTANCE	q_p:	
20. PILE YIELD STRENGTH ASTM A572	f_y:	50 KSI
21. PILE SIZE		HP 14X117
22. EST. AVG. PILE LENGTH	L_p:	25 FT
23. PILE RESISTANCE FACTOR	ϕ:	0.65
24. LATERAL PILE DEFLECTION	Δ:	- - -
25. BASIC WIND SPEED	V_{3s}:	- - -
26. MINIMUM GROUND SNOW LOAD	p_g:	- - -
27. SEISMIC DATA PGA: - - -	S_s:	- - -
	S_1:	- - -

PROJECT NAME: **BARRE TOWN**
PROJECT NUMBER: **BRF 6100(7)**

FILE NAME:	s06j002pi.xls	PLOT DATE:	9/19/2012
PROJECT LEADER:	J. LACROIX	DRAWN BY:	R. PELLETT
DESIGNED BY:	T. FILLBACH	CHECKED BY:	T. FILLBACH
PRELIMINARY INFORMATION SHEET 1		SHEET	2 OF 70