


STATE OF VERMONT AGENCY OF TRANSPORTATION



PROPOSED IMPROVEMENT BRIDGE PROJECT TOWN OF BRATTLEBORO COUNTY OF WINDHAM


TH 12, CLASS III (LOCAL ROAD), BRIDGE NO. 7



PROJECT LOCATION: LOCATED IN THE COUNTY OF WINDHAM, TOWN OF BRATTLEBORO, ON SUNSET LAKE ROAD (TH 12); BRIDGE NO. 7 OVER HALLADAY BROOK, APPROXIMATELY 0.20 MILES NORTH OF THE INTERSECTION OF VT 9 AND SUNSET LAKE RD (TH 12).

PROJECT DESCRIPTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES REMOVAL AND REPLACEMENT OF BRIDGE NO. 7, ON THE EXISTING ALIGNMENT, WITH ASSOCIATED ROADWAY AND CHANNEL WORK.

LENGTH OF ROADWAY: 272.17 FEET
LENGTH OF BRIDGE: 47.83 FEET
LENGTH OF PROJECT: 320.00 FEET



THESE PLANS ARE SUBJECT TO SUCH ENGINEERING CHANGES AS MAY BE REQUIRED BY THE FEDERAL HIGHWAY ADMINISTRATION OR THE DIRECTOR OF PROGRAM DEVELOPMENT.

CONSTRUCTION IS TO BE CARRIED ON IN ACCORDANCE WITH THESE PLANS AND THE STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED 2011, AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION ON JULY 20, 2011 FOR USE ON THIS PROJECT, INCLUDING ALL SUBSEQUENT REVISIONS AND SUCH REVISED SPECIFICATIONS AND SPECIAL PROVISIONS AS ARE INCORPORATED IN THESE PLANS.




QUALITY ASSURANCE PROGRAM : LEVEL 2
SURVEYED BY : VHB
SURVEYED DATE : NOV 2010
DATUM
VERTICAL NAVD 88
HORIZONTAL NAD 83 (07)

VHB Vanasse Hangen Brustlin, Inc.

DIRECTOR OF PROGRAM DEVELOPMENT	
APPROVED _____	DATE _____
PROJECT MANAGER :	TODD A. SUMNER, P.E.
PROJECT NAME :	BRATTLEBORO
PROJECT NUMBER :	BRO 1442 (35)
SHEET 1 OF 68 SHEETS	

INDEX OF SHEETS						FINAL HYDRAULIC REPORT																	
PLAN SHEETS						STANDARDS LIST						HYDROLOGIC DATA						PROPOSED STRUCTURE					
1	TITLE SHEET	E-121	STANDARD SIGN PLACEMENT - CONVENTIONAL ROAD	08-08-1995	DRAINAGE AREA : 5.5 sq. mi. Date: 5/31/2013						STRUCTURE TYPE: Single span precast, prestressed concrete non-voided slab bridge												
2	PRELIMINARY INFORMATION SHEET	G-1	STEEL BEAM GUARDRAIL DETAILS (POST, DELINEATOR, TYPICALS)	01-03-2000	CHARACTER OF TERRAIN : Hilly to mountainous, mostly forested						CLEAR SPAN(NORMAL TO STREAM): 25'-0"												
3	TYPICAL BRIDGE SECTION	G-1D	STEEL BEAM GUARDRAIL DETAILS (END TERMINAL, ANCHOR, MEDIAN)	01-03-2000	STREAM CHARACTERISTICS : Sinuous, slightly incised with minimal floodplain						VERTICAL CLEARANCE ABOVE STREAMBED: 6'-0"												
4	TYPICAL ROADWAY SECTIONS	S-367B	GUARDRAIL APPROACH SECTION, GALVANIZED HD STEEL BEAM	05-24-2012	NATURE OF STREAMBED : Gravel, cobbles, boulders and ledge						WATERWAY OF FULL OPENING: 129.4 sq. ft.												
5	TYPICAL EARTHWORK SECTIONS	T-1	TRAFFIC CONTROL GENERAL NOTES	08-06-2012	PEAK FLOW DATA						WATER SURFACE ELEVATIONS AT:												
6 - 7	PROJECT NOTES	T-10	CONVENTIONAL ROADS CONSTRUCTION APPROACH SIGNING	08-06-2012	Q 2.33 = 300 cfs Q 50 = 1100 cfs						Q2.33 = 536.3 ft VELOCITY= 8.4 fps												
8 - 9	QUANTITY SHEETS	T-30	CONSTRUCTION SIGN DETAILS	08-06-2012	Q 10 = 650 cfs Q 100 = 1275 cfs						Q10 = 537.9 ft " 9.8 fps												
10	BRIDGE QUANTITY SHEET	T-35	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS	08-06-2012	Q 25 = 900 cfs Q 500 = 1785 cfs						Q25 = 538.8 ft " 10.5 fps												
11	CONVENTIONAL SYMBOLOLOGY LEGEND	T-36	CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS FOR PAVING	08-06-2012	DATE OF FLOOD OF RECORD 1927						Q50 = 539.5 ft " 11.2 fps												
12	TIE SHEET				ESTIMATED DISCHARGE: Unknown						Q100 = 541.2 ft " 9.3 fps												
13	ALIGNMENT LAYOUT SHEET				WATER SURFACE ELEV.: Unknown						IS THE ROADWAY OVERTOPPED BELOW Q100: No												
14	LAYOUT SHEET				NATURAL STREAM VELOCITY : @ Q25 = 5.8 fps						FREQUENCY: Above Q100												
15	PROFILE SHEET				ICE CONDITIONS : Moderate						RELIEF ELEVATION: 541.1 ft												
16 - 18	TRAFFIC CONTROL PLANS				DEBRIS: Moderate						DISCHARGE OVER ROAD @Q100: None												
19	PLANTING PLAN				DOES THE STREAM REACH MAXIMUM HIGHWATER ELEV. RAPIDLY? Yes						AVERAGE LOW ELEVATION OF SUPERSTRUCTURE: 539.2 ft												
20	PLANTING AREA 1 PLAN AND SCHEDULE				IS ORDINARY RISE RAPID? Yes						VERTICAL CLEARANCE: @ Q25 = 0.4 ft												
21	PLANTING AREA 2 PLAN AND SCHEDULE				IS STAGE AFFECTED BY UPSTREAM OR DOWNSTREAM CONDITIONS? No						SCOUR: Footings are bearing on bedrock												
22	PLANTING DETAILS				IF YES, DESCRIBE:						REQUIRED CHANNEL PROTECTION: Stone Fill, Type III												
23	TRAFFIC SIGNS & LINE STRIPING SHEET				WATERSHED STORAGE: < 1% HEADWATERS: UNIFORM: X						PERMIT INFORMATION												
24	TRAFFIC SIGN SUMMARY SHEET				IMMEDIATELY ABOVE SITE:						AVERAGE DAILY FLOW: 10 cfs DEPTH OR ELEVATION:												
25	BORING INFORMATION SHEET				EXISTING STRUCTURE INFORMATION						ORDINARY LOW WATER: 2 cfs 0.5 ft												
26 - 28	BORING LOGS				STRUCTURE TYPE: Single span concrete encased steel beam bridge						ORDINARY HIGH WATER: 80 cfs 2.0 ft												
29	PLAN AND ELEVATION				YEAR BUILT: 1920						TEMPORARY BRIDGE REQUIREMENTS												
30	FRAMING PLAN				CLEAR SPAN(NORMAL TO STREAM): 11'-6"						STRUCTURE TYPE: Single span bridge*												
31 - 32	NON-VOIDED SLAB DETAILS TYPE I				VERTICAL CLEARANCE ABOVE STREAMBED: 5'-0"						CLEAR SPAN (NORMAL TO STREAM): 44'-0"												
33 - 34	NON-VOIDED SLAB DETAILS TYPE II				WATERWAY OF FULL OPENING: 54.5 sq. ft.						VERTICAL CLEARANCE ABOVE STREAMBED: 4'-0"												
35 - 36	NON-VOIDED SLAB DETAILS TYPE III				DISPOSITION OF STRUCTURE: Remove and replace structure						WATERWAY AREA OF FULL OPENING: 176 sq. ft.												
37	PRESTRESSED BEAM DETAILS				TYPE OF MATERIAL UNDER SUBSTRUCTURE: See borings						ADDITIONAL INFORMATION												
38	OVERLAY REINFORCING DETAILS				WATER SURFACE ELEVATIONS AT:						*The temporary bridge may be in place through the winter.												
39	BEARING DETAILS				Q2.33 = 538.1 ft VELOCITY = 9.1 fps						TRAFFIC MAINTENANCE NOTES												
40	APPROACH SLAB DETAILS				Q10 = 542.1 ft " 9.5 fps						1. MAINTAIN ONE-WAY ALTERNATING TRAFFIC ON A TEMPORARY BRIDGE.												
41	ABUTMENT NO. 1 PLAN & ELEVATION				Q25 = 542.6 ft " 9.7 fps						2. TRAFFIC SIGNALS ARE NECESSARY.												
42	WINGWALL NO. 1 ELEVATION & DETAILS				Q50 = 542.7 ft " 10.8 fps						3. SIDEWALKS ARE NOT NECESSARY												
43	WINGWALL NO. 2 ELEVATION & DETAILS				Q100 = 543.1 ft " 8.5 fps						4. THE APPROACHES FOR THE TEMPORARY BRIDGE SHALL BE PAVED.												
44	ABUTMENT NO. 1 FOOTING PLAN				UPSTREAM STRUCTURE						DESIGN VALUES												
45	ABUTMENT NO. 2 PLAN & ELEVATION				TOWN: Brattleboro DISTANCE: 8450 ft						1. DESIGN LIVE LOAD HL-93												
46	WINGWALL NO. 3 ELEVATION & DETAILS				HIGHWAY #: TH 4 (Halladay Brook Road) STRUCTURE #: 16						2. FUTURE PAVEMENT d_p : 3.0 INCH												
47	WINGWALL NO. 4 ELEVATION & DETAILS				CLEAR SPAN: 20' CLEAR HEIGHT: 9'						3. DESIGN SPAN L: 45.00 FT												
48	ABUTMENT NO. 2 FOOTING PLAN				YEAR BUILT: 2005 FULL WATERWAY:						4. MIN. MID-SPAN POS. CAMBER @ RELEASE (PRESTRESSED UNITS) Δ : SEE NOTES												
49 - 50	REINFORCING STEEL SCHEDULES				STRUCTURE TYPE: Single span concrete slab						5. PRESTRESSING STRAND (0.60 INCH DIAMETER - LOW/RELAX) f_y : 270 KSI												
51	BRIDGE RAIL DETAILS				DOWNSTREAM STRUCTURE						6. PRESTRESSED CONCRETE STRENGTH f'_{ci} : 6.0 KSI												
52	BRIDGE RAIL LAYOUT SHEET				TOWN: Brattleboro DISTANCE: 1340'						7. PRESTRESSED CONCRETE RELEASE STRENGTH f'_{ci} : 4.8 KSI												
53 - 56	ROADWAY CROSS SECTIONS				HIGHWAY #: Private Road (Winding Hill Road) STRUCTURE #: Private						8. CONCRETE, HIGH PERFORMANCE CLASS AA f'_{ci} : 4.0 KSI												
57 - 59	CHANNEL CROSS SECTIONS				CLEAR SPAN: CLEAR HEIGHT:						9. CONCRETE, HIGH PERFORMANCE CLASS A f'_{ci} : 4.0 KSI												
60	EPSC NARRATIVE				YEAR BUILT: FULL WATERWAY:						10. CONCRETE, HIGH PERFORMANCE CLASS B f'_{ci} : 3.5 KSI												
61	EPSC EXISTING CONDITIONS PLAN				LRFR LOAD RATING FACTORS						11. CONCRETE, CLASS C f'_{ci} : ---												
62	EPSC CONSTRUCTION CONDITIONS PLAN				LOADING LEVELS						12. REINFORCING STEEL f_y : 60 KSI												
63	EPSC FINAL CONDITIONS PLAN				TONNAGE						13. STRUCTURAL STEEL AASHTO M270 f_y : ---												
64 - 66	EROSION CONTROL DETAILS				INVENTORY						14. SOIL UNIT WEIGHT γ : 0.140 KCF												
67	R.O.W. DETAIL SHEET #1				POSTING						15. NOMINAL BEARING RESISTANCE OF SOIL q_n : ---												
68	ROW LAYOUT SHEET 1 OF 1				OPERATING						16. SOIL BEARING RESISTANCE FACTOR (REFER TO AASHTO LRFD) ϕ : ---												
STRUCTURES DETAILS						AS BUILT "REBAR" DETAIL						LRFR LOAD RATING FACTORS											
SD-501.00	CONCRETE DETAILS AND NOTES	05-10-2010	LEVEL I			LEVEL II			LEVEL III			TRUCK											
SD-502.00	CONCRETE DETAILS AND NOTES	06-04-2010	TYPE:			TYPE:			TYPE:			H-20 HL-93 3S2 6 AXLE 3A STR. 4A STR. 5A SEMI											
SD-516.10	BRIDGE JOINT ASPHALTIC PLUG	05-07-2010	GRADE:			GRADE:			GRADE:			20 36 36 66 30 34.5 38											
TRAFFIC DATA						TEMPORARY BRIDGE PROFILE ALONG TEMP CL						LOADING LEVELS											
YEAR	ADT	DHV	% D	% T	ADTT	20 year ESAL for flexible pavement from 2012 to 2032 : 40000						INVENTORY											
2012	460	50	76	2.1	10	40 year ESAL for flexible pavement from 2012 to 2052 : 93000						POSTING											
2032	490	55	76	3.6	20	Design Speed : 25 mph						OPERATING											
TRAFFIC DATA						TEMPORARY BRIDGE PROFILE ALONG TEMP CL						LOADING LEVELS						DESIGN VALUES					
																		17. NOMINAL BEARING RESISTANCE OF ROCK q_n : 70.0 KSF					
																		18. ROCK BEARING RESISTANCE FACTOR (REFER TO AASHTO LRFD) ϕ : 0.45					
																		19. NOMINAL AXIAL PILE RESISTANCE q_p : ---					
																		20. PILE YIELD STRENGTH ASTM A572 f_y : ---					
																		21. PILE SIZE ---					
																		22. EST. PILE LENGTH L _p : ---					
																		23. PILE RESISTANCE FACTOR ϕ : ---					
																		24. LATERAL PILE DEFLECTION Δ : ---					
																		25. BASIC WIND SPEED V _{3s} : ---					
																		26. MINIMUM GROUND SNOW LOAD p _g : ---					
																		27. SEISMIC DATA PGA: --- S _s : --- S ₁ : ---					
																		PROJECT NAME: BRATTLEBORO					
																		PROJECT NUMBER: BRO 1442(35)					
																		FILE NAME: z10j062pi.dgn PLOT DATE: 10/14/2013					
																		PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA					
																		DESIGNED BY: VHB CHECKED BY: S.E. BURBANK					
																		PRELIMINARY INFORMATION SHEET SHEET 2 OF 68					
																		PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA					
																		DESIGNED BY: VHB CHECKED BY: S.E. BURBANK					
																		PRELIMINARY INFORMATION SHEET SHEET 2 OF 68					





TYPICAL BRIDGE SECTION


SCALE 1/2" = 1'-0"

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062typ.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: S.E. BURBANK
TYPICAL BRIDGE SECTION

PLOT DATE: 10/14/2013
DRAWN BY: B.J. MASSE
CHECKED BY: S.E. BURBANK
SHEET 3 OF 68






TYPICAL ROADWAY SECTION
SCALE 3/8" = 1'-0"


MATERIAL TOLERANCES

SURFACE	
- PAVEMENT (TOTAL THICKNESS)	+/- 1/4"
- SUBBASE	+/- 1"




NOTE: ALL WORK ASSOCIATED WITH THE INSTALLATION AND REMOVAL OF THE DETOUR WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 528.10.

TYPICAL ONE-WAY DETOUR ROADWAY SECTION
SCALE 3/8" = 1'-0"




NOTE: ALL WORK ASSOCIATED WITH THE INSTALLATION AND REMOVAL OF THE TEMPORARY DRIVEWAY WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 528.10.

TYPICAL TEMPORARY DRIVEWAY SECTION
SCALE 3/8" = 1'-0"



NOTE: COST FOR FORMING AND COMPACTING SAFETY EDGE SHALL BE INCIDENTAL TO ITEM 900.680, "SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)".

SAFETY EDGE DETAIL
NOT TO SCALE




NOTE: SEE TYPICAL ROADWAY SECTION FOR INFORMATION NOT SHOWN.

TYPICAL DRIVEWAY SECTION
SCALE 3/8" = 1'-0"


PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062typ.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: S.E. BURBANK
TYPICAL ROADWAY SECTIONS

PLOT DATE: 10/14/2013
DRAWN BY: B.J. MASSE
CHECKED BY: S.E. BURBANK
SHEET 4 OF 68





COFFERDAM AND EARTHWORK SECTION
(NOT TO SCALE)




TYPICAL WINGWALL SECTION
(NOT TO SCALE)

- COFFERDAM NOTES**
1. COFFERDAM DIMENSIONS TO BE DETERMINED BY THE CONTRACTOR.
 2. THE PAY LIMITS OF EITHER "COFFERDAM EXCAVATION, EARTH" OR "COFFERDAM EXCAVATION, ROCK" SHALL BE 2'-0" OUTSIDE THE PERIMETER OF THE FOOTING AND FROM BOTTOM OF EXCAVATION UP TO THE EXISTING GROUND OR BOTTOM OF SUBBASE, WHICHEVER IS LOWER.
 3. IF A COFFERDAM IS CONSTRUCTED WHICH IS LARGER THAN THE INDICATED COFFERDAM EXCAVATION PAY LIMITS, PAYMENT FOR ALL UNCLASSIFIED CHANNEL EXCAVATION, INCLUDING THAT PORTION WHICH IS INSIDE THE COFFERDAM BUT OUTSIDE THE COFFERDAM PAY LIMITS, WILL BE MADE AT THE CONTRACT UNIT PRICE FOR UNCLASSIFIED CHANNEL EXCAVATION. NO MEASUREMENT AND PAYMENT WILL BE MADE FOR COFFERDAM EXCAVATION AND GRANULAR BACKFILL FOR STRUCTURES OUTSIDE THE PAY LIMITS DEFINED IN NOTE 2.



TYPICAL APPROACH SECTION
NOT TO SCALE



TYPICAL CHANNEL SECTION
(NOT TO SCALE)

*GRUBBING MATERIAL SHALL NOT BE PLACED ON THE STONE FILL IN THE AREA UNDER THE BRIDGE. WHENEVER CHANNEL SLOPE INTERSECTS ROADWAY SUBBASE, GRUBBING MATERIAL SHALL BEGIN AT THE BOTTOM OF SUBBASE.

- * (2) 1 1/2" LIFTS OF TYPE IVS OVER (1) 3" LIFT OF TYPE IIS
- ** (2) 1 1/2" LIFTS OF TYPE IVS

NOTE: EMULSIFIED ASPHALT IS TO BE APPLIED AT A RATE OF 0.040 GAL/SY BETWEEN ALL LIFTS OF BITUMINOUS CONCRETE PAVEMENT, ON ALL COLD PLANED SURFACES, AND ON THE APPROACH SLAB PRIOR TO PLACING THE FIRST LIFT OF PAVEMENT, AS DIRECTED BY THE ENGINEER.

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062typ.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	S.E. BURBANK
TYPICAL EARTHWORK SECTIONS	
PLOT DATE:	10/14/2013
DRAWN BY:	B.J. MASSE
CHECKED BY:	S.E. BURBANK
SHEET	5 OF 68

PROJECT NOTES

GENERAL

- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE STATE OF VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION, DATED 2011, AND ITS LATEST REVISIONS, AND THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 5TH EDITION, AND ITS LATEST REVISIONS.
- THE BRIDGE IS DESIGNED FOR HL-93 LIVE LOAD WITH A 3.0 INCH ALLOWANCE FOR FUTURE PAVEMENT.
- SALVAGED SIGNS NOT REUSED SHALL REMAIN THE PROPERTY OF THE TOWN OF BRATTLEBORO. THE CONTRACTOR SHALL DELIVER THE SIGNS TO THE TOWN AT THE DEPT. OF PUBLIC WORKS GARAGE LOCATED AT 211 FAIRGROUND ROAD.
- ALL DIMENSIONS ARE HORIZONTAL OR VERTICAL AND ARE GIVEN AT 68 DEGREES FAHRENHEIT UNLESS NOTED OTHERWISE.
- THE LIMITS OF THE COFFERDAM ARE TO BE DETERMINED BY THE CONTRACTOR.
- ITEM 529.15 "REMOVAL OF STRUCTURE" IS FOR THE COMPLETE REMOVAL AND DISPOSAL OF THE EXISTING BRIDGE SUBSTRUCTURE AND SUPERSTRUCTURE, INCLUDING ALL BRIDGE RAIL, BEARINGS AND ANCHOR BOLTS, WHERE THE REMOVAL IS OUTSIDE OF THE AREAS COVERED BY ANY OF THE EXCAVATION ITEMS.
- THE EXISTING BRIDGE CONTAINS STRUCTURAL STEEL ENCASED IN CONCRETE. THE STRUCTURAL STEEL MAY BE PAINTED WITH A MATERIAL THAT MAY CONTAIN LEAD. THE CONTRACTOR SHALL FOLLOW ALL APPLICABLE REGULATIONS WHEN HANDLING AND WORKING WITH THIS STEEL. THE REMOVED STRUCTURAL STEEL IS THE PROPERTY OF THE CONTRACTOR. THE CONTRACTOR SHALL INDEMNIFY AND HOLD THE STATE, ITS OFFICERS, AND EMPLOYEES HARMLESS CONCERNING THE CONTRACTOR'S USE OR DISPOSITION OF THE REMOVED EXISTING STRUCTURAL STEEL.
- REMOVAL OF EXISTING BRIDGE PAVEMENT SHALL BE PAID AS ITEM 529.10, "REMOVAL OF BRIDGE PAVEMENT".
- THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL BURIED AND AERIAL UTILITIES AND POLES PRIOR TO STARTING WORK. SOME UTILITIES HAVE BEEN RELOCATED DURING THE PREPARATION OF THESE PLANS AND THE CONTRACTOR WILL NEED TO COORDINATE WITH ALL UTILITY OWNERS TO CONFIRM ACTUAL LOCATIONS PRIOR TO CONSTRUCTION. SEE THE UTILITY SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

EARTHWORK AND RELATED ITEMS

- TEMPORARY CONSTRUCTION FILLS WITHIN THE WATERCOURSE FOR ANY PURPOSE SHALL CONSIST OF CLEAN STONE FILL ONLY. NO OTHER FILLING IN THE STREAM SHALL OCCUR WITHOUT THE APPROVAL OF THE STREAM ALTERATION ENGINEER.
- A COFFERDAM IS REQUIRED FOR THE CONSTRUCTION OF THE ABUTMENTS. REFER TO THE "TYPICAL EARTHWORKS SECTIONS" FOR COFFERDAM NOTES.
- STONE FILL, TYPE III SHALL BE PLACED IN FRONT OF THE ABUTMENTS BEFORE THE NEW BEAMS ARE SET, AS SHOWN ON THE PLANS.
- ANY TEMPORARY MEANS OF SUPPORTING EXCAVATION NECESSARY TO MAINTAIN TRAFFIC SHALL BE INCIDENTAL TO ITEM 528.10, "ONE-WAY TEMPORARY BRIDGE", AND SHALL MEET THE REQUIREMENTS OF SECTION 204. ASSOCIATED CONSTRUCTION DRAWINGS SHALL BE SUBMITTED IN ACCORDANCE WITH SECTION 105.
- THE HEIGHT OF THE FILL BEHIND ABUTMENTS SHALL BE LIMITED TO THE BRIDGE SEAT ELEVATION UNTIL THE OVERLAY HAS BEEN POURED AND THE CURING PERIOD IS UP.
- THE AREA DISTURBED BY THE TEMPORARY DETOUR SHALL BE RESTORED TO ITS ORIGINAL GRADE AND VEGETATED IF NECESSARY. ALL COSTS WILL BE INCIDENTAL TO ITEM 528.10, "ONE-WAY TEMPORARY BRIDGE".
- NEW TREES WILL BE PLANTED AT THE SITE WHERE TREES WERE REMOVED FOR THE TEMPORARY DETOUR AND WILL FOLLOW THE PLANTING SCHEDULE INCLUDED IN THE PLANS.

TRAFFIC MAINTENANCE DURING CONSTRUCTION

- THE CONTRACTOR SHALL IMPLEMENT THE ROAD CLOSURE, TRAFFIC CONTROL, AND DETOUR AS SHOWN ON THE PLANS.
- THE CONTRACTOR SHALL NOTIFY THE TOWN A MINIMUM OF TWO (2) WEEKS PRIOR TO CLOSING THE ROAD AND IMPLEMENTING THE DETOUR.
- DURING CONSTRUCTION, TRAFFIC SHALL BE MAINTAINED ON A ONE-WAY TEMPORARY BRIDGE LOCATED UPSTREAM OF THE NEW STRUCTURE. THE TEMPORARY BRIDGE AND DETOUR SHALL BE PAVED. CONSTRUCTION AND MAINTENANCE OF THE TEMPORARY BRIDGE AND ITS APPROACHES SHALL BE PAID FOR UNDER ITEM 528.10, "ONE-WAY TEMPORARY BRIDGE".
- FULL ACCESS TO ALL SIDE ROADS AND DRIVES WITHIN THE PROJECT LIMITS SHALL BE MAINTAINED AT ALL TIMES. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO ITEM 641.10, "TRAFFIC CONTROL".

- UNLESS COVERED UNDER INDIVIDUAL PAY ITEMS OR NOTED OTHERWISE, ALL COSTS FOR WORK SHOWN ON THE TRAFFIC CONTROL SHEETS AND FOR TEMPORARY TRAFFIC CONTROL DEVICES WILL BE CONSIDERED TO BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR TRAFFIC CONTROL, ITEM 641.10, "TRAFFIC CONTROL". THIS INCLUDES, BUT IS NOT LIMITED TO, THE FOLLOWING ITEMS:

RETROREFLECTIVE DRUMS
PORTABLE TRAFFIC LIGHTS
PORTABLE LUMINAIRE
TYPE III BARRICADES
ENERGY ABSORPTION ATTENUATOR
SIGNS
SIGN POSTS

ENERGY ABSORPTION ATTENUATOR(S) SHALL BE FURNISHED IN ACCORDANCE WITH SECTION 621.

- ALL SIGNS SHALL BE IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) AND THE "STANDARD HIGHWAY SIGNS AND MARKINGS" BOOK (SHSM) PUBLISHED BY THE FEDERAL HIGHWAY ADMINISTRATION (FHWA).
- ALL TEMPORARY PORTABLE TRAFFIC CONTROL SIGNALS AND PORTABLE LIGHT TOWERS SHALL BE IN ACCORDANCE WITH SECTION 678 AND THE CURRENT EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD).
- SIGNAL TIMING/TIMING ADJUSTMENTS REQUESTED BY THE ENGINEER SHALL BE ACCOMPLISHED WITHIN 24 HOURS AFTER BEING REQUESTED. PAYMENT SHALL BE INCIDENTAL TO ITEM 641.10 "TRAFFIC CONTROL". THE CONTRACTOR, AT THE DIRECTION OF THE ENGINEER, SHALL MAKE SEVERAL TRIAL RUNS TO DETERMINE THE PROPER ALL-RED CLEARANCE INTERVAL.

CONCRETE

- CONCRETE FOR THE OVERLAY SHALL BE ITEM 501.32, "CONCRETE, HIGH PERFORMANCE, CLASS AA". CONCRETE FOR THE CURBS SHALL BE ITEM 501.33, "CONCRETE, HIGH PERFORMANCE, CLASS A". SUBSTRUCTURE CONCRETE SHALL BE ITEM 501.34, "CONCRETE, HIGH PERFORMANCE CLASS B", UNLESS OTHERWISE NOTED.
- THE KEY IN CONCRETE CONSTRUCTION JOINTS SHALL BE MONOLITHIC AND CONTINUOUS FOR THE FULL LENGTH OF THE JOINT.
- ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 1" BY 1".
- JOINTS AND SCORE MARKS IN CONCRETE SHALL BE CONSTRUCTED AS INDICATED ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- ALL REINFORCING STEEL SHALL BE DETAILED AND FABRICATED USING PROCEDURES AND TOLERANCES IN ACCORDANCE WITH APPLICABLE PUBLICATIONS OF THE CONCRETE REINFORCING STEEL INSTITUTE (CRSI).
- REINFORCING STEEL PLACEMENT TOLERANCES SHALL BE:

SPACING	± 1"
CLEARANCE	± ¼"
- MINIMUM COVER FOR REINFORCING STEEL SHALL BE 2" ALONG THE BACK FACES OF WALLS AGAINST EARTH AND 3" ELSEWHERE, UNLESS OTHERWISE NOTED.
- NO CONCRETE IN THE ABUTMENTS OR WINGWALLS SHALL BE PLACED ABOVE THE BRIDGE SEAT ELEVATIONS UNTIL THE BEAMS OR SLABS HAVE BEEN PROFILED AND THE FINISHED GRADE OF THE DECK HAS BEEN DETERMINED.
- RELATIVE TO GRADE, ALL DECK POURS SHALL BEGIN FROM THE LOW ELEVATION END AND PROCEED TOWARDS THE HIGH ELEVATION END.
- SURFACES OF BRIDGE SEATS UNDER BEARING DEVICES SHALL BE LEVEL IN THE LONGITUDINAL DIRECTION (FROM THE APPROACH SLAB SEAT TO THE FRONT FACE OF THE ABUTMENT). ALL OTHER AREAS SHALL BE SLOPED DOWN 1/2 INCH PER FOOT FROM THE APPROACH SLAB SEAT TOWARD THE NEAREST OUTSIDE FACE OF THE SUBSTRUCTURE UNIT, SUCH AS TO PREVENT PONDING ON THE BRIDGE SEAT AREA. THE ENTIRE BRIDGE SEAT SURFACE SHALL BE SMOOTH STEEL TROWEL FINISHED.
- WATER REPELLENT, SILANE, SHALL BE APPLIED TO ALL EXPOSED CONCRETE SURFACES EXCEPT THE UNDERSIDE OF THE DECK BETWEEN THE DRIP NOTCHES.
- ½" SACRIFICIAL WEARING SURFACE HAS BEEN ADDED TO THE TOP OF THE CONCRETE OVERLAY. SEE SECTION 501 FOR DETAILS ON PROVIDING TEXTURING.
- ALL SUPERSTRUCTURE REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507 FOR LEVEL II REINFORCEMENT. REINFORCEMENT FOR OVERLAY SHALL BE PAID FOR UNDER ITEM 507.12, "REINFORCING STEEL, LEVEL II". REINFORCEMENT FOR PRESTRESSED CONCRETE NON-VOIDED SLABS SHALL BE PAID FOR UNDER ITEM 900.640, "SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)". REINFORCING FOR THE SUBSTRUCTURE SHALL BE PAID FOR UNDER ITEM 507.11, "REINFORCING STEEL, LEVEL I" AND ITEM 507.12, REINFORCING STEEL, LEVEL II". CUTTING AND REPAIRING DAMAGED AREAS OF COATED REINFORCING STEEL SHALL BE PERFORMED IN ACCORDANCE WITH SUBSECTION 507.

SUBSTRUCTURE ON LEDGE

- FOOTINGS AND SUB-FOOTINGS SHALL BE FOUNDED ON LEDGE WHICH HAS BEEN CLEANED OF ALL LOOSE ROCK AND DEBRIS TO ENSURE THAT SUBSTRUCTURES ARE PLACED ON COMPETENT ROCK.
- UPON COMPLETION OF THE EXCAVATION FOR SUBSTRUCTURES FOUNDED ON BEDROCK AND PRIOR TO PLACING FORMWORK, THE ENGINEER SHALL NOTIFY THE PROJECT MANAGER AND THE VTRANS STATE GEOLOGIST. THE GEOLOGIST WILL DETERMINE IF THE BEDROCK IS COMPETENT TO OBTAIN THE NOMINAL BEARING RESISTANCE AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL NOTIFY THE GEOLOGIST 72 HOURS PRIOR TO WHEN THE ANALYSIS WILL BE NEEDED.
- LEDGE THAT IS EXCAVATED FOR PLACEMENT OF FOOTINGS SHALL BE EXCAVATED TO PROVIDE A LEVEL SURFACE OR AS DIRECTED BY THE ENGINEER.
- A MAXIMUM OF 6" OVER BREAKAGE WILL BE REPLACED WITH "HIGH PERFORMANCE CLASS B CONCRETE". OVER BREAKAGE BEYOND 6" SHALL BE REPLACED WITH HIGH PERFORMANCE CLASS B CONCRETE" AT THE EXPENSE OF THE CONTRACTOR.
- THE LIMITS OF THE SUBFOOTING SHALL BE 1'-0" OUTSIDE THE LIMITS OF THE FOOTING.
- THE SUBSTRUCTURE UNITS HAVE BEEN DESIGNED FOR THE TOP OF FOOTING ELEVATIONS SHOWN ON THE PLANS. IF THE LEDGE ELEVATION IS GREATER THAN 1'-0" BELOW THE DESIGN BOTTOM OF FOOTING, A SUBFOOTING SHALL BE POURED SO THAT THE DESIGN TOP OF FOOTING IS AT THE REQUIRED ELEVATION.
- FOR ALL SUBSTRUCTURES, WHERE LEDGE IS WITHIN ONE FOOT FROM THE BOTTOM OF THE FOOTING AS DESIGNED, THE FOOTING MAY BE POURED TO THE TOP OF THE LEDGE USING "CONCRETE, HIGH PERFORMANCE CLASS B".
- FOR ALL SUBSTRUCTURE UNITS WHERE LEDGE IS BELOW TOP OF FOOTING BY LESS THAN THE DEPTH OF FOOTING DETAILED IN THE PLANS, THE LEDGE SHALL BE EXCAVATED DOWN TO THE INDICATED BOTTOM OF FOOTING FOR THE FULL WIDTH (TOE TO HEEL) OF THE CONFIGURATION.
- IF LEDGE IS ABOVE THE DESIGN TOP OF FOOTING, THE FOOTING MAY BE RAISED. BEFORE ANY UPWARD ADJUSTMENT IS MADE IN FOOTING ELEVATION, THE PROJECT MANAGER SHALL BE CONTACTED AND PROVIDED WITH A LEDGE PROFILE. NO FURTHER WORK SHALL BE DONE UNTIL APPROVAL OF THE CONFIGURATION IS RECEIVED.
- #8 DOWELS SHALL BE DRILLED AND GROUTED INTO THE LEDGE AS SHOWN ON THE PLANS. THE DOWELS SHALL HAVE A MINIMUM 2'-0" EMBEDMENT INTO THE LEDGE AND SHALL EXTEND INTO THE FOOTING A MINIMUM OF 1'-6". IN AREAS WHERE A SUBFOOTING IS REQUIRED #8 DOWELS WILL ALSO BE USED AT THE INTERFACE BETWEEN SUBFOOTING AND FOOTING. THE DRILLING AND GROUTING SHALL BE PAID FOR UNDER THE ITEM 507.16, "DRILLING AND GROUTING DOWELS".
- PRIOR TO ANY COLD WEATHER CONCRETE PLACEMENT AS DEFINED IN SECTION 501, THE CONTRACTOR SHALL SUBMIT A PLAN TO THE ENGINEER FOR APPROVAL. THE PLAN AT A MINIMUM SHALL PROVIDE METHODS FOR INSULATING, CURING, AND HEATING, TEMPERATURE MONITORING, AND ANY WEATHER RESTRICTIONS FOR CONCRETE PLACEMENT. THE PLAN SHALL BE SPECIFIC TO THE LOCATION OF THE PLACEMENT AND BE SUBMITTED A MINIMUM OF 14 DAYS PRIOR TO THE ANTICIPATED PLACEMENT DATE. COLD WEATHER CONCRETE SHALL NOT BE PLACED PRIOR TO APPROVAL OF THE PLAN.

PRESTRESSED NON-VOIDED SLABS

- PRESTRESSED CONCRETE NON-VOIDED SLABS SHALL BE PAID FOR UNDER ITEM 900.640, "SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x36")" OR ITEM 900.640, "SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x48")".
- ITEM 900.640, "SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLAB)" SHALL:
 - CONFORM TO SECTION 510 "PRESTRESSED CONCRETE".
 - HAVE THE ENDS OF THE STRANDS RECESSED AND GROUTED ACCORDING TO STANDARD PRACTICE.
 - INCLUDE COLD POURED JOINT FILLER AND TRANSVERSE TENDONS.
 - GALVANIZE TRANSVERSE TENDON PLATES AND CHUCKS AFTER FABRICATION ACCORDING TO AASHTO M 232M/M 232.
- ITEM 510.24, "GROUTING SHEAR KEYS": FILL THE JOINTS BETWEEN THE BEAMS WITH MORTAR, TYPE IV, AS DESCRIBED IN SUBSECTION 510.13.

PROJECT NAME: BRATTLEBORO

PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062pn.dgn

PROJECT LEADER: S.E. BURBANK

DESIGNED BY: S.E. BURBANK

PROJECT NOTES (1 OF 2)

PLOT DATE: 10/14/2013

DRAWN BY: E.A. FIALA

CHECKED BY: S.E. BURBANK

SHEET 6 OF 68

PROJECT NOTES CONT'D...

52. DESIGN VALUES:

- A. CONCRETE: $F'c = 6$ ksi AND $Fc = 4.8$ ksi
- B. LIVE LOAD: AASHTO HL-93
- C. PRESTRESSING STRANDS: 0.6" DIAMETER, 270 ksi, LOW-RELAXATION 7-WIRE STRANDS PULLED TO 75% OF THEIR YIELD STRENGTH
- D. POST-TENSIONING STRANDS: 0.6" DIAMETER, 270 ksi, LOW-RELAXATION 7-WIRE STRANDS.
- E. THE ASSUMED MODULUS OF ELASTICITY FOR THE STRAND IS 28,500 ksi.
- F. THERE SHALL BE ONE (1) STRAND PER POST-TENSION DUCT.
- G. TRANSVERSE TENDONS SHALL BE COVERED BY SEAMLESS POLYPROPYLENE SHEATH (WITH CORROSION INHIBITOR GREASE BETWEEN SHEATH AND STRAND) FOR THE LENGTH OF THE STRAND. TIES SHALL BE TENSIONED TO 47 KIPS FOR EACH 0.6" DIAMETER STRAND.
- H. SERVICE LOADS (INT & EXT):

MEMBER MOMENT	189.8 & 142.4 K-FT
SUPERIMPOSED DEAD LOAD MOMENT	142.5 & 101.0 K-FT
LIVE LOAD & IMPACT MOMENT	197.8 & 165.7 K-FT
DEAD LOAD REACTION	27.2 & 18.5 K
LIVE LOAD & IMPACT REACTION	41.7 K & 63.6 K
TOTAL REACTION	68.9 & 82.1 K
RELEASE CAMBER	1.033 & 0.925 IN
ERECTION CAMBER	1.095 & 0.990 IN

53. THE FABRICATOR MAY, WITH THE APPROVAL OF THE PROJECT MANAGER, ALTER THE DESIGN AS DETAILED TO MEET THE PLANT'S PRESTRESSING OPERATION AND MATERIAL REQUIREMENTS. ALTERNATE STRAND, TRANSVERSE TIE AND CROSS-SLOPE CONFIGURATIONS MAY BE SUBMITTED TO THE ENGINEER FOR APPROVAL. ANY DESIGN CHANGES SHALL MEET ALL OF THE APPLICABLE DESIGN CRITERIA AND SHALL BE STAMPED AND SIGNED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF VERMONT.

54. THE PRECASTER SHALL SANDBLAST SHEAR KEY FACES PRIOR TO DELIVERY.

55. ALL TIES AND STIRRUPS IN THE NON-VOIDED SLABS SHALL MEET THE REQUIREMENTS OF SECTION 507 FOR LEVEL II REINFORCEMENT. PAYMENT WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 900.640, "SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)".

56. THE CONTRACTOR IS RESPONSIBLE FOR DESIGN OF ALL LIFTING POINTS, POST TENSIONING ELEMENTS IN THE ANCHORAGE ZONE AND ADDITIONAL REINFORCEMENT IN THE ANCHORAGE ZONE (REQUIRED FOR SPLITTING, BURSTING SPALLING, ETC.) INCLUDING THE LOCAL ZONE (REGION IMMEDIATELY SURROUNDING THE POST TENSIONING DEVICE). THE CONTRACTOR IS RESPONSIBLE FOR CONSIDERATION OF ADDITIONAL STRESSES DUE TO HANDLING. DESIGN MUST CONFORM TO AASHTO LRFD SPECIFICATIONS.

PROPOSED CONSTRUCTION SEQUENCE FOR PRESTRESSED NON-VOIDED SLABS

57. LAY OUT WORKING LINES:

- A. LAY OUT WORKING LINES FOR THE ENTIRE BRIDGE WIDTH ON THE BEAM SEAT.
- B. MEASURE ALL WORKING LINES FROM A COMMON WORKING POINT.
- C. BASE THE WORKING LINES ON THE NOMINAL BEAM WIDTHS.

58. VERIFY BEAM SEAT ELEVATIONS:

- A. MEASURE ELEVATIONS AT BEAM SEATS.
- B. IF SEATS ARE HIGH OR LOW, TAKE CORRECTIVE ACTION.
- C. INSTALL BEARINGS.

59. ERECT BEAMS STARTING AT THE LOWER EXTERIOR BEAM, PLACING ONE BEAM AT A TIME:

- A. PLACE BEAMS TO FIT WITHIN THE WORKING LINES.
- B. PRIOR TO INSTALLING INTERIOR BEAMS IN EACH PHASE OF CONSTRUCTION, INSTALL ANCHORED END OF TRANSVERSE TENDON WITH ENOUGH TENDON TO PASS THROUGH THE NEXT BEAM TO BE PLACED IN THE FOLLOWING PHASE OF CONSTRUCTION.
- C. AS WORK PROGRESSES, INSTALL HARDWOOD WEDGES BETWEEN ADJACENT BEAMS TO MAINTAIN PROPER JOINT OPENING (A MINIMUM OF ONE WEDGE AT EACH TRANSVERSE TENDON).
- D. DRILL ANCHOR BOLT HOLES.
- E. PLACE ANCHOR BOLTS.

60. INSTALL BACKER ROD: PLACE FILLER BELOW THE KEYWAY BOTTOM, AS SHOWN ON THE PLANS.

61. INSTALL TRANSVERSE TENDONS:

- A. FEED TENDONS THROUGH DUCTS.
- B. VERIFY THAT HARDWOOD WEDGES ARE IN PLACE AS REQUIRED TO PREVENT SLIPPAGE OF BEAMS.
- C. USING A CALIBRATED JACK, POST-TENSION TENDONS TO APPROXIMATELY 5 KIPS TO REMOVE SAG IN THE TENDON AND TO SEAT THE CHUCK.

62. GROUT SHEAR KEYS:

- A. CLEAN JOINTS WITH AN OIL FREE AIR-BLAST IMMEDIATELY BEFORE GROUT PLACEMENT. VERIFY THAT THE BACKER ROD IS STILL IN PLACE.
- B. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR ADDITIONAL JOINT PREPARATION AND GROUT PLACEMENT.
- C. CAREFULLY ROD JOINTS TO ELIMINATE ANY POSSIBILITY OF VOIDS.

63. POST-TENSION TRANSVERSE TENDONS:

- A. GROUT SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 1500 PSI, BASED ON THE MANUFACTURER'S RECOMMENDATIONS, PRIOR TO STRESSING. THE GROUT NEED NOT BE CURED FOR THREE DAYS PRIOR TO THE COMMENCING OF POST-TENSIONING.
- B. PROVIDE APPROPRIATE CUBE MOLDS AS DESCRIBED IN AASHTO T106 FOR 3 SETS OF 3 DAY CUBES, 3 SETS OF 28 DAY CUBES AND AT A MINIMUM OF 3 MORE CUBES TO TEST FOR THE 1500 PSI MINIMUM COMPRESSIVE STRENGTH.
- C. POST-TENSION TENDONS TO 47 KIPS USING A CALIBRATED JACK OPERATED BY QUALIFIED PERSONNEL.

64. FOR EACH BEAM, REPEAT THE SEQUENCE SPECIFIED IN NOTES 59-63.

65. END DETAILS:

- A. GROUT ANCHOR BOLTS INTO THE SLEEVES IN THE PRESTRESSED UNITS AT THE FIXED ENDS. BEFORE THE GROUT CURES, PLACE THE WASHER PLATE, AND INSTALL THE NUT ON TOP AND TIGHTEN.
- B. PLACE THE COLD POURED JOINT SEALER IN THE SLEEVES IN THE PRESTRESSED UNITS AT THE EXPANSION ENDS. PLACE THE WASHER PLATE AND INSTALL THE NUT ON TOP. HAND TIGHTEN AND THEN LOOSEN 1/2 TURN.
- C. GROUT OVER THE NUT AND BOLT IN THE ANCHOR BOLT BLOCK OUT ON THE FIXED ENDS. FILL THE ANCHOR BOLT BLOCK OUTS ON THE EXPANSION ENDS WITH COLD POURED JOINT SEALER.

66. FINISH WORK: REMOVE WEDGES, AND PATCH SURFACE AND FASCIA BEAMS AT TRANSVERSE TENDONS.

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	LANDSCAPING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
					630					630		CY	COMMON EXCAVATION	203.15		86	CY	FILL REQUIRED (75 CY *1.15)
								420		420		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				FILL AVAILABLE
					1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22		504	CY	COMMON EXCAVATION (630 CY * 0.80)
								820		820		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30		315	CY	UNCLASSIFIED CHANNEL EXCAVATION (420 CY * 0.75)
								1070		1070		CY	COFFERDAM EXCAVATION, EARTH	208.30		803	CY	COFFERDAM EXCAVATION EARTH (1070 CY * 0.75)
								365		365		CY	COFFERDAM EXCAVATION, ROCK	208.35		181	CY	COFFERDAM EXCAVATION ROCK (365 CY * 0.495)
								1		1		LS	COFFERDAM (ABUTMENT NO. 1)	208.40		1802	CY	SUBTOTAL
								1		1		LS	COFFERDAM (ABUTMENT NO. 2)	208.40		0	CY	ROUNDING
					175					175		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10		1802	CY	TOTAL
					550					550		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				COMMON EXCAVATION
					7					7		CWT	EMULSIFIED ASPHALT	404.65		576	CY	MAINLINE
					1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50		54	CY	DRIVES
								25		25		CY	CONCRETE, HIGH PERFORMANCE CLASS AA	501.32		0	CY	ROUNDING
								5		5		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33		630	CY	TOTAL
								330		330		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				SUBBASE OF CRUSHED GRAVEL, COARSE GRADED
								30280		30280		LB	REINFORCING STEEL, LEVEL I	507.11		490	CY	MAINLINE
								13345		13345		LB	REINFORCING STEEL, LEVEL II	507.12		60	CY	DRIVES
								100		100		LF	DRILLING AND GROUTING DOWELS	507.16		0	CY	ROUNDING
								290		290		LF	GROUTING SHEAR KEYS	510.24		550	CY	TOTAL
								16		16		GAL	WATER REPELLENT, SILANE	514.10				
								68		68		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								69		69		LF	JOINT SEALER, HOT POURED	524.11				
								1		1		LS	ONE-WAY TEMPORARY BRIDGE (880 SF - EST.)	528.10				
								55		55		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								1		1		EACH	REMOVAL OF STRUCTURE (653 SF - EST.)	529.15				
								28		28		EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17				
					20					20		MGAL	DUST CONTROL WTH WATER	609.10				
								410		410		CY	STONE FILL, TYPE III	613.12				
					1					1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
					1					1		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12				
					58					58		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
					113					113		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205				
					4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
					4					4		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM W/8FT POSTS	621.738				
					180					180		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					100					100		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				

PROJECT NAME: BRATTLEBORO

PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10J062qs.dgn

PROJECT LEADER: S.E. BURBANK

DESIGNED BY: E.A. FIALA

QUANTITY SHEET #1

PLOT DATE: 11/11/2013

DRAWN BY: A.J. GOUDREAU

CHECKED BY: S.E. BURBANK

SHEET 8 OF 68



QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	LANDSCAPING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
						1					1		LS	MOBILIZATION/DEMOLITION	635.11		148	TONS	TYPE IVS - WEARING COURSE
						1					1		LS	TRAFFIC CONTROL	641.10		130	TONS	TYPE IIS - BASE COURSE
									1010		1010		SY	GEOTEXTILE UNDER STONE FILL	649.31		278	TONS	TOTAL
								300			300		SY	GEOTEXTILE FOR SILT FENCE	649.51				DRIVES
								300			300		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61		12	TONS	STA. 102+55, LT
								10			10		LB	SEED	651.15		20	TONS	STA. 103+60, RT
								70			70		LB	FERTILIZER	651.18		32	TONS	TOTAL
								0.3			0.3		TON	AGRICULTURAL LIMESTONE	651.20				TOTAL BIT. CONCRETE PAVEMENT, SMALL QUANTITY
								0.3			0.3		TON	HAY MULCH	651.25				
								40			40		CY	TOPSOIL	651.35				
								300			300		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								80			80		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								110			110		SY	TEMPORARY EROSION MATTING	653.20				
								15			15		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								70			70		LF	BARRIER FENCE	653.50				
								650			650		LF	PROJECT DEMARCATION FENCE	653.55				
							7				7		EACH	DECIDUOUS TREES (ACER RUBRUM) (B&B) (2.5" - 3" DIA.)	656.30				
							6				6		EACH	DECIDUOUS TREES (ACER SACCHARINUM) (B&B) (2" - 2.5" DIA.)	656.30				
							58				58		EACH	DECIDUOUS SHRUBS (CORNUS SERICEA) (B&B) (36" - 48" HT.)	656.35				
							7.2				7.2		MGAL	LANDSCAPE WATERING	656.65				
							65				65		CY	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	656.80				
							1				1		LS	TREE PROTECTION	656.85				
						12					12		SF	TRAFFIC SIGNS, TYPE A	675.20				
						30					30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						11					11		EACH	REMOVING SIGNS	675.50				
						1					1		EACH	ERECTING SALVAGED SIGNS	675.60				
									200		200		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVNAIZED HDSB/FASCIA MOUNTED/STEEL TUBING)	900.640				
						175					175		LF	SPECIAL PROVISION (FABRIC SCREENING FENCE)	900.640				
									96		96		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x36")	900.640				
									240		240		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x48")	900.640				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
						1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
						310					310		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: BRATTLEBORO

PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10J062qs.dgn

PROJECT LEADER: S.E. BURBANK

DESIGNED BY: E.A. FIALA

QUANTITY SHEET #2

PLOT DATE: 11/11/2013

DRAWN BY: A.J. GOUDREAU

CHECKED BY: S.E. BURBANK

SHEET 9 OF 68



BRIDGE QUANTITY SHEET 1

SUMMARY OF BRIDGE QUANTITIES										TOTALS	DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES			
					TEMPORARY BRIDGE	APP SLAB 1	ABUTMENT 1	SUPER-STRUCTURE	ABUTMENT 2	APP SLAB 2	BRIDGE TOTAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
							180		240		420	CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27			
							450		370		820	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
							545		525		1070	CY	COFFERDAM EXCAVATION, EARTH	208.30			
							185		180		365	CY	COFFERDAM EXCAVATION, ROCK	208.35			
							1				1	LS	COFFERDAM (ABUTMENT NO. 1)	208.40			
									1		1	LS	COFFERDAM (ABUTMENT NO. 2)	208.40			
								25			25	CY	CONCRETE, HIGH PERFORMANCE CLASS AA	501.32			
								5			5	CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33			
						35	130		130	35	330	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34			
							16660		13620		30280	LB	REINFORCING STEEL, LEVEL I	507.11			
						3570	945	2835	2485	3510	13345	LB	REINFORCING STEEL, LEVEL II	507.12			
							42		58		100	LF	DRILLING AND GROUTING DOWELS	507.16			
								290			290	LF	GROUTING SHEAR KEYS	510.24			
							2.5	9.5	4		16	GAL	WATER REPELLENT, SILANE	514.10			
								68			68	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10			
						34.5				34.5	69	LF	JOINT SEALER, HOT POURED	524.11			
									1		1	LS	ONE-WAY TEMPORARY BRIDGE (880 SF - EST.)	528.10			
								55			55	SY	REMOVAL OF BRIDGE PAVEMENT	529.10			
								1			1	EACH	REMOVAL OF STRUCTURE (653 SF - EST.)	529.15			
							14		14		28	EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17			
							175		235		410	CY	STONE FILL, TYPE III	613.12			
							418		592		1010	SY	GEOTEXTILE UNDER STONE FILL	649.31			
								200			200	LF	SPECIAL PROVISION (BRIDGE RAILING, GALVNAIZED HDSB/FASCIA MOUNTED/STEEL TUBING)	900.640			
								96			96	LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x36")	900.640			
								240			240	LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NON-VOIDED SLABS)(18"x48")	900.640			

PROJECT NAME: **BRATTLEBORO**

PROJECT NUMBER: **BRO 1442(35)**

FILE NAME: z10J062qs.dgn

PROJECT LEADER: **S.E. BURBANK**

DESIGNED BY: **E.A. FIALA**

BRIDGE QUANTITY SHEET #1

PLOT DATE: 11/11/2013

DRAWN BY: **A.J. GOUDREAU**

CHECKED BY: **S.E. BURBANK**

SHEET 10 OF 68



GPS CONTROL POINTS

HVCTRL #2

MAG NAIL SET
 NORTH = 135124.4650
 EAST = 1607422.7270
 ELEV. = 541.0500





VCTRL #106

B 14 RESET 1988
 NORTH = 134276.6160
 EAST = 1608361.3210
 ELEV. = 522.7390

GENERAL LOCATION, WEST BRATTLEBORO, VT. FROM THE INTERSECTION OF VT ROUTE 9 AND SUNSET LAKE ROAD (T.H. 12), PROCEED NORTH ON SUNSET LAKE ROAD (T.H. 12) FOR 0.2 MI (0.3 KM) TO THE SOUTHWEST CORNER OF BRIDGE 7 OVER HALLADAY BROOK AND THE MARK ON THE LEFT. THE MARK IS SET IN THE PAVEMENT. SEE TRAVERSE TIES BELOW FOR TIE DISTANCES.

GENERAL LOCATION, BRATTLEBORO, VT., ABOUT 3.5 MI (5.6 KM) WEST OF BRATTLEBORO, ABOUT 13 MI (20.9 KM) EAST OF WILMINGTON, AND ABOUT 9.5 MI (15.3 KM) NORTH OF THE MASSACHUSETTS/VERMONT STATE LINE. TO REACH FROM THE EAST END OF THE VT ROUTE 9 BRIDGE OVER I-91 IN BRATTLEBORO GO WEST ALONG VT ROUTE 9 FOR 2.6 MI (4.2 KM) TO THE INTERSECTION OF WESTGATE DRIVE LEFT AND WINDING HILL ROAD RIGHT. TURN RIGHT AND GO NORTH ALONG WINDING HILL ROAD FOR 0.1 MI (0.2 KM) TO THE SOUTH END OF THE BRIDGE OVER HALLADAY BROOK AND THE MARK ON THE LEFT, SET IN THE TOP OF THE WINGWALL AT THE SOUTHWEST CORNER OF THE BRIDGE. THE MARK IS A STATE OF VERMONT SURVEY MARK AND IS 18.4 FT (5.6 M) WEST OF AND ABOUT 1.6 FT (0.5 M) LOWER THAN THE CENTERLINE OF WINDING HILL ROAD, 78.1 FT (23.8 M) EAST OF POLE NO. 7-0-27/7-0/3/3, 99.1 FT (30.2 M) NORTH OF POLE NO. 2A (WITH LUMEN), AND 18.0 FT (5.5 M) NORTHEAST OF A WATER METER MANHOLE.

TRAVERSE TIES




* Main Traverse Completed 11/15/10 by T.J.Gaudet and B.M.Klinefelter

DATUM	
VERTICAL	NAVD 88
HORIZONTAL	NAD 83 (07)

PROJECT NAME: BRATTLEBORO	
PROJECT NUMBER: BRO 1442(35)	
FILE NAME: z10j062t1.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: B.M. KLINEFELTER
DESIGNED BY: B.M. KLINEFELTER	CHECKED BY: J.W. GOLEK
TIE SHEET	SHEET 12 OF 68





DETOUR (T.H. 12)
CURVE NO. 1 DATA
 $\Delta = 19^\circ 05' 20.51''$
 $D = 43^\circ 04' 46.32''$
 $R = 133.00'$
 $T = 22.36'$
 $L = 44.31'$
 $E = 1.87'$
 BANK = NONE


DETOUR (T.H. 12)
CURVE NO. 2 DATA
 $\Delta = 60^\circ 21' 44.73''$
 $D = 127^\circ 19' 26.24''$
 $R = 45.00'$
 $T = 26.17'$
 $L = 47.41'$
 $E = 7.06'$
 BANK = NONE

DETOUR (T.H. 12)
CURVE NO. 3 DATA
 $\Delta = 38^\circ 31' 27.38''$
 $D = 57^\circ 17' 44.81''$
 $R = 100.00'$
 $T = 34.95'$
 $L = 67.24'$
 $E = 5.93'$
 BANK = NONE


MAINLINE ALIGNMENT

Horizontal Alignment Name: TH 12 Proposed

Element:	STATION	NORTHING	EASTING
Element: Linear			
POB (24)	100+00.00	134840.8468	1607485.0762
PC (25)	100+95.56	134934.4914	1607466.0249
Tangent Direction:	N 11°29'58.03" W		
Tangent Length:	95.56		
Element: Circular			
PC (25)	100+95.56	134934.4914	1607466.0249
PI	101+78.38	135015.6414	1607449.5155
CC (26)		135580.4132	1610640.9871
PT (27)	102+61.15	135097.5289	1607437.1733
Radius:	3240.00		
Delta:	2°55'41.70" Right		
Degree of Curvature:	1°46'06.20"		
Length:	165.59		
Tangent:	82.81		
Chord:	165.57		
Middle Ordinate:	1.06		
External:	1.06		
Tangent Direction:	N 11°29'58.03" W		
Radial Direction:	N 78°30'01.97" E		
Chord Direction:	N 10°02'07.18" W		
Radial Direction:	N 81°25'43.67" E		
Tangent Direction:	N 8°34'16.33" W		
Element: Linear			
PT (27)	102+61.15	135097.5289	1607437.1733
PC (28)	103+35.54	135171.0912	1607426.0859
Tangent Direction:	N 8°34'16.33" W		
Tangent Length:	74.39		
Element: Circular			
PC (28)	103+35.54	135171.0912	1607426.0859
PI	104+20.88	135255.4781	1607413.3669
CC (30)		134817.8702	1605082.5554
PT (31)	105+06.15	135338.7317	1607394.6115
Radius:	2370.00		
Delta:	4°07'28.14" Left		
Degree of Curvature:	2°25'03.16"		
Length:	170.61		
Tangent:	85.34		
Chord:	170.57		
Middle Ordinate:	1.53		
External:	1.54		
Tangent Direction:	N 8°34'16.33" W		
Radial Direction:	N 81°25'43.67" E		
Chord Direction:	N 10°38'00.40" W		
Radial Direction:	N 77°18'15.52" E		
Tangent Direction:	N 12°41'44.48" W		
Element: Linear			
PT (31)	105+06.15	135338.7317	1607394.6115
POE (29)	106+00.00	135430.2829	1607373.9868
Tangent Direction:	N 12°41'44.48" W		
Tangent Length:	93.85		



SUNSET LAKE ROAD (T.H. 12)
CURVE NO. 1 DATA
 $\Delta = 2^\circ 55' 41.70''$
 $D = 1^\circ 46' 06.20''$
 $R = 3240.00'$
 $T = 82.81'$
 $L = 165.59'$
 $E = 1.06'$
 BANK = NONE



SUNSET LAKE ROAD (T.H. 12)
CURVE NO. 2 DATA
 $\Delta = 4^\circ 07' 28.14''$
 $D = 2^\circ 25' 03.16''$
 $R = 2370.00'$
 $T = 85.34'$
 $L = 170.61'$
 $E = 1.54'$
 BANK = NONE

DETOUR ALIGNMENT

Horizontal Alignment Name:	STATION	NORTHING	EASTING
Element: Linear			
POB (13)	1+00.00	135027.5412	1607448.5065
PC (14)	1+12.42	135039.5643	1607445.3982
Tangent Direction:	N 14°29'41.61" W		
Tangent Length:	12.42		
Element: Circular			
PC (14)	1+12.42	135039.5643	1607445.3982
PI	1+34.78	135061.2153	1607439.8010
CC (15)		135006.2752	1607316.6316
PT (39)	1+56.73	135079.8452	1607427.4308
Radius:	133.00		
Delta:	19°05'20.51" Left		
Degree of Curvature (Arc):	43°04'46.32"		
Length:	44.31		
Tangent:	22.36		
Chord:	44.11		
Middle Ordinate:	1.84		
External:	1.87		
Tangent Direction:	N 14°29'41.61" W		
Radial Direction:	N 75°30'18.39" E		
Chord Direction:	N 24°02'21.87" W		
Radial Direction:	N 56°24'57.88" E		
Tangent Direction:	N 33°35'02.12" W		

Horizontal Alignment Name:	STATION	NORTHING	EASTING
Element: Linear			
PT (39)	1+56.73	135079.8452	1607427.4308
PC (36)	2+63.79	135169.0338	1607368.2101
Tangent Direction:	N 33°35'02.12" W		
Tangent Length:	107.06		
Element: Circular			
PC (36)	2+63.79	135169.0338	1607368.2101
PI	2+89.96	135190.8362	1607353.7335
CC (37)		135193.9259	1607405.6985
PT (38)	3+11.20	135214.2004	1607365.5246
Radius:	45.00		
Delta:	60°21'44.73" Right		
Degree of Curvature (Arc):	127°19'26.24"		
Length:	47.41		
Tangent:	26.17		
Chord:	45.25		
Middle Ordinate:	6.10		
External:	7.06		
Tangent Direction:	N 33°35'02.12" W		
Radial Direction:	N 56°24'57.88" E		
Chord Direction:	N 3°24'09.76" W		
Radial Direction:	S 63°13'17.40" E		
Tangent Direction:	N 26°46'42.60" E		
Element: Linear			
PT (38)	3+11.20	135214.2004	1607365.5246
PC (21)	3+62.83	135260.2927	1607388.7858
Tangent Direction:	N 26°46'42.60" E		
Tangent Length:	51.63		

Horizontal Alignment Name:	STATION	NORTHING	EASTING
Element: Circular			
PC (21)	3+62.83	135260.2927	1607388.7858
PI	3+97.77	135291.4903	1607404.5301
CC (22)		135305.3469	1607299.5103
PT (23)	4+30.06	135325.7039	1607397.4163
Radius:	100.00		
Delta:	38°31'27.38" Left		
Degree of Curvature (Arc):	57°17'44.81"		
Length:	67.24		
Tangent:	34.95		
Chord:	65.98		
Middle Ordinate:	5.60		
External:	5.93		
Tangent Direction:	N 26°46'42.60" E		
Radial Direction:	S 63°13'17.40" E		
Chord Direction:	N 7°30'58.91" E		
Radial Direction:	N 78°15'15.22" E		
Tangent Direction:	N 11°44'44.78" W		
Element: Linear			
PT (23)	4+30.06	135325.7039	1607397.4163
POE (35)	4+37.24	135332.7293	1607395.9556
Tangent Direction:	N 11°44'44.78" W		
Tangent Length:	7.18		


DATUM	
VERTICAL	NAVD 88
HORIZONTAL	NAD 83 (07)



PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062alg layout.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: J.W. GOLEK
ALIGNMENT LAYOUT SHEET

PLOT DATE: 10/14/2013
DRAWN BY: J.W. GOLEK
CHECKED BY: S.E. BURBANK
SHEET 13 OF 68




TH 12 PROFILE
 SCALE 1" = 20' HORIZONTAL
 1" = 10' VERTICAL

THE GRADES SHOWN TO THE NEAREST TENTH ARE THE ORIGINAL GROUND ELEVATIONS ALONG THE PROPOSED ALIGNMENT. THE GRADES SHOWN TO THE NEAREST HUNDREDTH ARE THE PROPOSED GRADES FOR THE NEW ALIGNMENT.

PROJECT NAME: BRATTLEBORO	PLOT DATE: 10/14/2013
PROJECT NUMBER: BRO 1442(35)	DRAWN BY: E.A. FIALA
FILE NAME: z10j062pro.dgn	DESIGNED BY: E.A. FIALA
PROJECT LEADER: S.E. BURBANK	CHECKED BY: S.E. BURBANK
PROFILE SHEET	SHEET 15 OF 68






DETOUR (T.H. 12)
CURVE NO. 1 DATA
 $\Delta = 19^{\circ}05'20.51''$
 $D = 43^{\circ}04'46.32''$
 $R = 133.00'$
 $T = 22.36'$
 $L = 44.31'$
 $E = 1.87'$
 BANK = NONE


DETOUR (T.H. 12)
CURVE NO. 2 DATA
 $\Delta = 60^{\circ}21'44.73''$
 $D = 127^{\circ}19'26.24''$
 $R = 45.00'$
 $T = 26.17'$
 $L = 47.41'$
 $E = 7.06'$
 BANK = NONE

DETOUR (T.H. 12)
CURVE NO. 3 DATA
 $\Delta = 38^{\circ}31'27.38''$
 $D = 57^{\circ}17'44.81''$
 $R = 100.00'$
 $T = 34.95'$
 $L = 67.24'$
 $E = 5.93'$
 BANK = NONE





EDGE OF DETOUR PAVEMENT WIDTH TRANSITION

STA. 1+12.42	=	8'-0"	LT & RT
STA. 2+15.42	=	8'-0"	LT
STA. 2+59.66	=	8'-0"	RT
STA. 2+63.79	=	9'-5"	LT
STA. 3+11.20	=	10'-0"	LT
STA. 3+12.95	=	10'-0"	RT
STA. 4+37.22	=	10'-0"	LT & RT



PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062+cp1.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	S.E. BURBANK
TRAFFIC CONTROL PLAN (1 OF 3)	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	16 OF 68





ALTERNATING ONE-WAY TRAFFIC CONTROL PLAN
NOT TO SCALE


NOTES:

1. THE NUMBER OF TYPE III BARRICADES AND OTHER TRAFFIC CONTROL DEVICES SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. THE ACTUAL NUMBER REQUIRED ARE TO BE DETERMINED BASED ON INDIVIDUAL ROADWAY CLOSURE REQUIREMENTS.
2. THE EXISTING SPEED LIMIT IS 35 MPH. THE SPEED LIMIT WILL BE REDUCED TO 25 MPH THROUGH THE DETOUR FOR THIS PROJECT.
3. ALL SIGNS AND OTHER TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) AND THE "STANDARD HIGHWAY SIGNS AND MARKINGS" BOOK (SHSM) PUBLISHED BY THE FEDERAL HIGHWAY ADMINISTRATION (FHWA).
4. SOLID SUBSTRATE CONSTRUCTION SIGNS SHALL HAVE RETRO-REFLECTIVE SHEETING EQUAL TO OR EXCEEDING "AMERICAN SOCIETY FOR TESTING AND MATERIALS" (ASTM D 4956) TYPE VII, VIII, OR IX REQUIREMENTS, UNLESS OTHERWISE NOTED. SOLID SUBSTRATE REGULATORY SIGNS (WHITE BACKGROUND) SHALL HAVE RETRO-REFLECTIVE SHEETING EQUAL TO OR EXCEEDING ASTM D 4956 TYPE III.
5. SIGNS SHALL BE ERECTED BEFORE THE START OF ANY WORK AND SHALL BE COVERED UNTIL WORK COMMENCES. DURING PERIODS OF INACTIVITY OR UPON COMPLETION OF THE WORK, EACH SIGN SHALL BE ERECTED IN A NEAT AND WORKMANLIKE MANNER. SIGNS SHALL BE REMOVED UPON COMPLETION OF THE WORK AT THE DISCRETION OF THE ENGINEER.
6. FIXED SIGNS SHALL BE SET SECURELY IN THE GROUND. THE BOTTOM OF A SIGN SHALL BE AT LEAST SEVEN FEET ABOVE THE EDGE OF PAVEMENT.
7. DURING NON-WORK PERIODS, ALL EQUIPMENT SHALL BE MOVED TO A LOCATION OFF PAVED SHOULDERS AND OUTSIDE THE CLEAR ZONE, OR PROTECTED BY TEMPORARY TRAFFIC BARRIER OR GUARDRAIL.
8. AN ENERGY ABSORPTION ATTENUATOR RATED FOR 35 MPH SHALL BE LOCATED AT THE END OF THE BARRIER.
9. PAYMENT FOR ALL ON AND OFF-PROJECT SIGNING AND TRAFFIC CONTROL DEVICES, WITH THE EXCEPTION OF TEMPORARY TRAFFIC BARRIER, WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 641.10. PAYMENT FOR TEMPORARY TRAFFIC BARRIER WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 528.10.


LEGEND

- PORTABLE TRAFFIC LIGHTS
- PORTABLE LUMINAIRE (LIGHT TOWER)
- REFLECTIVE PLASTIC DRUM
- FLOW OF TRAFFIC
- TYPE III BARRICADE
- TYPE III BARRICADE (MOD.)
- ENERGY ABSORPTION ATTENUATOR
- CONCRETE MEDIAN BARRIER
- SPECIAL PROVISION (FABRIC SCREENING FENCE) (SEE TCP 3 OF 3)

PROJECT NAME:	BRATTLEBORO	FILE NAME:	z10j062tcp2.dgn	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	PROJECT LEADER:	M.A. COLGAN	DRAWN BY:	E.A. FIALA
		DESIGNED BY:	E.A. FIALA	CHECKED BY:	S.E. BURBANK
		TRAFFIC CONTROL PLAN (2 OF 3)		SHEET	17 OF 68

IDENTIFICATION NUMBER	SIZE OF SIGN		TEXT	NUMBER OF SIGNS REQ'D	AREA (SQ FT)	TOTAL AREA (SQ FT)	REMARKS
	WIDTH (IN)	HEIGHT (IN)					
G20-2	48	24		2	8.00	16.00	
G20-5aP	24	18		2	3.00	12.00	MOUNT ABOVE R2-1(25)
R1-1	24	24		1	4.00	4.00	---
R2-1 (25)	18	24		2	3.00	12.00	---
R2-1 (35)	18	24		2	3.00	6.00	---
R2-6aP	18	24		2	3.00	6.00	MOUNT BELOW R2-1 (25)
R3-2	24	24		1	4.00	4.00	---
R6-1R	36	18		1	4.00	4.00	---
R10-6	24	36		4	6.00	24.00	---
VC-812	36	36		2	9.00	18.00	MOUNT ON TWO POSTS
W1-1L	36	36		1	9.00	9.00	MOUNT ON TWO POSTS
W1-1R	36	36		1	9.00	9.00	MOUNT ON TWO POSTS
W1-6L	36	18		2	3.00	6.00	MOUNT ON TWO POSTS
W1-6R	36	18		2	3.00	6.00	MOUNT ON TWO POSTS

IDENTIFICATION NUMBER	SIZE OF SIGN		TEXT	NUMBER OF SIGNS REQ'D	AREA (SQ FT)	TOTAL AREA (SQ FT)	REMARKS
	WIDTH (IN)	HEIGHT (IN)					
W3-3	36	36		2	9.00	18.00	MOUNT ON TWO POSTS
W3-5	36	36		2	9.00	18.00	MOUNT ON TWO POSTS
W13-1 (10)	18	18		2	2.25	4.5	MOUNT BELOW W1-1L OR W1-1R
W20-1	36	36		2	9.00	18.00	MOUNT ON TWO POSTS




NOTES:

- SEE EPSC CONSTRUCTION CONDITIONS PLAN AND TRAFFIC CONTROL PLAN (2 OF 3) FOR LOCATION OF FABRIC SCREENING FENCE.
- ALL COSTS ASSOCIATED WITH CONSTRUCTING, INSTALLING, MAINTAINING, AND REMOVING THE FABRIC SCREENING FENCE SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 900.640, "SPECIAL PROVISION (FABRIC SCREENING FENCE)".

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062tcp3.dgn
PROJECT LEADER: M.A. COLGAN
DESIGNED BY: E.A. FIALA
TRAFFIC CONTROL PLAN (3 OF 3)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 18 OF 68



DRIVEWAY (GRAVEL)

REGINA VISTA (PRIVATE ROAD)

PLANTING AREA 1 (SEE PLANTING AREA 1 PLAN AND SCHEDULE)

HALLADAY BROOK

DETOUR

PLANTING AREA 2 (SEE PLANTING AREA 2 PLAN AND SCHEDULE)

SAVE (M. ELM)

SAVE (M. MAPLE)

SAVE (S. ASH)

TOWN R.O.W.

SUNSET LAKE ROAD (TH I2)

2+00

103+00

104+00

4+00

105+00
4+37

TOWN R.O.W.

DRIVEWAY (PAVED)


LEGEND

- M. = MEDIUM TREE
- S. = SMALL TREE

SCALE 1" = 10'-0"



PROJECT NAME: BRATTLEBORO	
PROJECT NUMBER: BRO 1442(35)	
FILE NAME: z10j062plnt.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: D.A. GINGRAS
DESIGNED BY: P.B. WERTS	CHECKED BY: S.E. BURBANK
PLANTING PLAN	SHEET 19 OF 68



Trees				
Planting Plan Code	Common Name	Scientific Name	Total Number of Trees	Planting Stock Size
1	Red Maple	<i>Acer rubrum</i>	3	2.5"-3" (dia)
2	Silver Maple	<i>Acer saccharinum</i>	4	2"-2.5" (dia)

☐ - TOTAL NUMBER OF TREES IN PLANTING AREA 1

Shrubs				
Planting Plan Code	Common Name	Scientific Name	Total Number of Shrubs	Size of Stock (Height)
A	Red-Osier Dogwood	<i>Cornus Sericea</i>	37	36"-48"

☐☐ - TOTAL NUMBER OF SHRUBS IN PLANTING AREA 1

LEGEND

- - TREE
- * - SHRUB


SCALE 1" = 5'-0"




PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062p1nt_schl.dgn
 PROJECT LEADER: S.E. BURBANK
 DESIGNED BY: P.B. WERTS
 PLANTING AREA 1 PLAN AND SCHEDULE

PLOT DATE: 10/14/2013
 DRAWN BY: D.A. GINGRAS
 CHECKED BY: S.E. BURBANK
 SHEET 20 OF 68



HALLADAY BROOK



Trees				
Planting Plan Code	Common Name	Scientific Name	Total Number of Trees 	Planting Stock Size
1	Red Maple	<i>Acer rubrum</i>	4	2.5"-3" (dia)
2	Silver Maple	<i>Acer saccharinum</i>	2	2"-2.5" (dia)


Shrubs				
Planting Plan Code	Common Name	Scientific Name	Total Number of Shrubs 	Size of Stock (Height)
A	Red-Osier Dogwood	<i>Cornus Sericea</i>	21	36"-48"

 - TOTAL NUMBER OF TREES IN PLANTING AREA 2


 - TOTAL NUMBER OF SHRUBS IN PLANTING AREA 2

LEGEND


-  - TREE
-  - SHRUB



PROJECT NAME: BRATTLEBORO	PLOT DATE: 10/14/2013
PROJECT NUMBER: BRO 1442(35)	DRAWN BY: D.A. GINGRAS
FILE NAME: z10j062plnt_sch2.dgn	CHECKED BY: S.E. BURBANK
PROJECT LEADER: S.E. BURBANK	SHEET 21 OF 68
DESIGNED BY: P.B. WERTS	
PLANTING AREA 2 PLAN AND SCHEDULE	




SHRUB PLANTING POCKET CROSS-SECTION IN
"GRUBBING" MATERIAL OVER STONE FILL
NOT TO SCALE



SHRUB PLANTING ON SLOPES DETAIL
NOT TO SCALE

LANDSCAPE NOTES:



1. ALL PLANTING LOCATIONS SHALL BE STAKED OUT PRIOR TO PLANTING. THE ENGINEER IN CONSULTATION WITH THE AGENCY'S CONSULTANT FIELD NATURALIST MAY ADJUST THE STAKES AS NEEDED PRIOR TO INSTALLATION. ADJUSTMENTS TO THE PLANTING DESIGN AND LAYOUT MAY BE REQUIRED BASED UPON ACTUAL FIELD CONDITIONS.
2. ALL LANDSCAPE CONSTRUCTION ACTIVITIES SHALL BE CONFINED TO WITHIN THE LIMITS OF DISTURBANCE AS IDENTIFIED ON THE PLANS OR AS OTHERWISE DIRECTED BY THE ENGINEER.
3. LANDSCAPE BACKFILL SHALL CONSIST OF ONE HALF SCREENED TOPSOIL, ONE QUARTER COMPOST, AND ONE QUARTER NATIVE MATERIAL AS APPROVED BY THE ENGINEER. TAMP TO REMOVE AIR POCKETS AND WATER THOROUGHLY IMMEDIATELY AFTER PLANTING. TREES TO RECEIVE A MINIMUM OF 10 GALLONS AT EACH WATERING, TWICE WEEKLY DURING THE ESTABLISHMENT PERIOD. SHRUBS TO RECEIVE A MINIMUM OF 5 GALLONS AT EACH WATERING, TWICE WEEKLY DURING THE ESTABLISHMENT PERIOD. UNSUITABLE NATIVE MATERIAL SHALL BE REPLACED WITH IMPORTED APPROVED TOPSOIL AS DIRECTED BY ENGINEER.
4. MYCORRHIZA SHALL BE APPLIED TO ALL TREE AND SHRUB PLANTINGS PER MANUFACTURER'S INSTRUCTION AND FURNISHED IN ACCORDANCE WITH SUBSECTION 755.07.
5. A 3-4" LAYER OF BARK MULCH AROUND PLANTINGS SHALL BE AGED, DOUBLE SHREDDED AND IN ITS NATURAL UNDYED STATE. EXTEND MULCH LAYER 6" BEYOND PLANT PIT TO PREVENT DRYING AIR FROM REACHING ROOT BALL. TAPER MULCH TO BASE OF TRUNK FLARE AS WELL. AVOID STOCKPILING MULCH FOR LONG PERIODS TO PREVENT ANAEROBIC CONDITION AND BUILD UP OF TOXINS.
6. ALL TREES SHALL BE GROWN AS TREE FORMS AND TRAINED IN THE NURSERY TO A SINGLE STRAIGHT TRUNK.
7. SIDE SLOPE PLANTING IN STONE FILL: DIG INDIVIDUAL 3' DIA. PLANTING POCKETS, ONE FOR EACH SHRUB AS LOCATED ON THE PLANTING PLANS.
8. LANDSCAPE BACKFILL SHALL BE PLACED FOR TREES AT TIME OF FINAL GRADING SO TREES CAN BE PLANTED AT A LATER DATE AND MATERIAL WILL BE IN PLACE.
9. PLACE TREE IN HOLE SO THAT MAIN ORDER ROOTS ARE AT OR SLIGHTLY ABOVE FINISHED GRADE. REMOVE ALL EXCESS SOIL ON TOP OF THE ROOT FLARE AND ABOVE MAIN ORDER ROOTS. AVOID PLANTING TOO DEEP. ONCE IN THE PLANTING HOLE, REMOVE TWINE AND BURLAP FROM TOP 1/2 OF BALL; IF SYNTHETIC, REMOVE COMPLETELY. CUT WIRE BASKETS AND REMOVE ENTIRE SIDES.



TREE PLANTING ON SLOPES DETAIL
NOT TO SCALE

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062details-plants.dgn PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA CHECKED BY: S.E. BURBANK
PLANTING DETAILS SHEET 22 OF 68



- REMOVING SIGNS**
 STA. 102+19, RT
 STA. 102+49, RT
 STA. 102+96, LT
 STA. 102+97, LT (5)
 STA. 102+98, LT
 STA. 103+56, RT
 STA. 104+10, LT
- ERECTING SALVAGED SIGNS**
 STA. 103+11, LT
- TRAFFIC SIGNS, TYPE A**
 STA. 102+97, LT (2)

- SIGNING LEGEND**
 N = NEW
 R&S = REMOVE AND SALVAGE
 RET = RETAIN
 S = SALVAGE



SCALE 1" = 20'-0"
 20 0 20



PROJECT NAME:	BRATTLEBORO	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	DRAWN BY:	J.L. LEMIEUX
FILE NAME:	z10j062+sl.dgn	DESIGNED BY:	S.E. BURBANK
PROJECT LEADER:	S.E. BURBANK	TRAFFIC SIGNS & LINE STRIPING SHEET	CHECKED BY: S.E. BURBANK
			SHEET 23 OF 68

SOIL CLASSIFICATION

AASHTO

- A1 Gravel and Sand
- A3 Fine Sand
- A2 Silty or Clayey Gravel and Sand
- A4 Silty Soil - Low Compressibility
- A5 Silty Soil - Highly Compressible
- A6 Clayey Soil - Low Compressibility
- A7 Clayey Soil - Highly Compressible

ROCK QUALITY DESIGNATION

R.Q.D. (%)	ROCK DESCRIPTION
<25	Very Poor
25 to 50	Poor
51 to 75	Fair
76 to 90	Good
>90	Excellent

SHEAR STRENGTH

UNDRAINED SHEAR STRENGTH IN P.S.F.	CONSISTENCY
<250	Very Soft
250-500	Soft
500-1000	Med. Stiff
1000-2000	Stiff
2000-4000	Very Stiff
>4000	Hard

CORRELATION GUIDE OF "N" TO DENSITY/CONSISTENCY



DENSITY (GRANULAR SOILS)		CONSISTENCY (COHESIVE SOILS)	
N	DESCRIPTIVE TERM	N	DESCRIPTIVE TERM
<5	Very Loose	<2	Very Soft
5-10	Loose	2-4	Soft
11-24	Med. Dense	5-8	Med. Stiff
25-50	Dense	9-15	Stiff
>50	Very Dense	16-30	Very Stiff
		31-60	Hard
		>60	Very Hard

COMMONLY USED SYMBOLS

- ▼ Water Elevation
- ⊕ Standard Penetration Boring
- ⊗ Auger Boring
- ⊙ Rod Sounding
- S Sample
- N Standard Penetration Test
Blow Count Per Foot For:
2" O.D. Sampler
1 3/8" I.D. Sampler
Hammer Weight Of 140 Lbs.
Hammer Fall Of 30"
- VS Field Vane Shear Test
- US Undisturbed Soil Sample
- B Blast
- DC Diamond Core
- MD Mud Drill
- WA Wash Ahead
- HSA Hollow Stem Auger
- AX Core Size 1 1/8"
- BX Core Size 1 7/8"
- NX Core Size 2 1/8"
- M Double Tube Core Barrel Used
- LL Liquid Limit
- PL Plastic Limit
- PI Plasticity Index
- NP Non Plastic
- w Moisture Content (Dry Wgt. Basis)
- D Dry
- M Moist
- MTW Moist To Wet
- W Wet
- Sat Saturated
- Bo Boulder
- Gr Gravel
- Sa Sand
- Si Silt
- Cl Clay
- HP Hardpan
- Le Ledge
- NLTD No Ledge To Depth
- CNPF Can Not Penetrate Further
- TLOB Top of Ledge Or Boulder
- NR No Recovery
- Rec. Recovery
- 1/2 Rec. Percent Recovery
- ROD Rock Quality Designation
- CBR California Bearing Ratio
- < Less Than
- > Greater Than
- R Refusal (N > 100)
- VTSPG NAD83 - See Note 7

COLOR

- blk Black
- bl Blue
- brn Brown
- dk Dark
- gr'y Gray
- gn Green
- lt Light
- or Orange
- pnk Pink
- pu Purple
- rd Red
- tn Tan
- wh White
- yel Yellow
- mltc Multicolored



BORING CHART

HOLE NO.	SURV. STATION	OFFSET	GROUND ELEV.	ELEV. TLOB
B-1	103+50.31	5.78 LT	N/A	N/A
B-2	102+59.04	4.22 RT	N/A	N/A
B-3	102+77.63	2.54 RT	540.0	521.0
B-4	103+30.82	5.89 LT	541.0	528.0
B-5	103+61.93	10.87 LT	541.0	532.8
B-5A	103+69.87	9.57 LT	N/A	N/A

BORING LAYOUT

SCALE 1" = 10' - 0"

GENERAL NOTES

- The subsurface explorations shown herein were made between in February, 2004 by Mikes Boring and Coring and November, 2011 by the Agency.
- Soil and rock classifications, properties and descriptions are based on engineering interpretation from available subsurface information by Mikes Coring and Boring and the Agency, and may not necessarily reflect actual variations in subsurface conditions that may be encountered between individual boring or sample locations.
- Observed water levels and/or conditions indicated are as recorded at the time of exploration and may vary according to the prevailing rainfall, methods of exploration and other factors.
- Engineering judgment was exercised in preparing the subsurface information presented herein. Analysis and interpretation of subsurface data was performed and interpreted for Agency design and estimating purposes. Presentation of the information in the Contract is intended to provide the Contractor access to the same data available to the Agency. The subsurface information is presented in good faith and is not intended as a substitute for personal investigation, independent interpretation, independent analysis or judgment by the Contractor.
- Pictorial structure details shown on the boring plan layout or soils profile are for illustrative purposes only and may not accurately portray final contract details.
- Terminology used on boring logs to describe the hardness, degree of weathering, and spacing of fractures, joints and other discontinuities in the bedrock is defined in the AASHTO Manual on Subsurface Investigations, 1988.
- Northing and Easting coordinates are shown in Vermont State Plane Grid North American Datum 1983 in survey feet.

DEFINITIONS (AASHTO)

- BEDROCK (LEDGE)** - Rock in its native location of indefinite thickness.
- BOULDER** - A rock fragment with an average dimension > 12 inches.
- COBBLE** - Rock fragments with an average dimension between 3 and 12 inches.
- GRAVEL** - Rounded particles of rock < 3" and > 0.075" (#10 sieve).
- SAND** - Particles of rock < 0.075" (#10 sieve) and > 0.0029" (#200 sieve).
- SLT** - Soil < 0.0029" (#200 sieve), non or slightly plastic and exhibits no strength when air-dried.
- CLAY** - Fine grained soil, exhibits plasticity when moist and considerable strength when air-dried.
- VARVED** - Alternate layers of silt and clay.
- HARDPAN** - Extremely dense soil, cemented layer, not softened when wet.
- MUCK** - Soft organic soil (containing > 10% organic material).
- MOISTURE CONTENT** - Weight of water divided by dry weight of soil.
- FLOWING SAND** - Granular soil so saturated (loose) that it flows into drill casing during extraction of wash rod.
- STRIKE** - Angle from magnetic north to line of intersection of bed with a horizontal plane.
- DIP** - Inclination of bed with a horizontal plane.

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062bor.dgn
PROJECT LEADER: M.A. COLGAN
DESIGNED BY: S.E. BURBANK
BORING INFORMATION SHEET

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 25 OF 68



MIKE'S BORING & CORING
PO Box 75 • East Barre, Vermont 05649 • 802 476-5073

TO: Brian Austin DuBois and King, Inc. P.O. Box 339 Randolph, VT 05060-0339	PROJECT NAME: Brattleboro Bridge LOCATION: Brattleboro, VT MBC JOB #: 05001	SHEET: 1 DATE: 2-7-04 HOLE #: B-1 LINE & STA. OFFSET:
--	---	---

Ground Water Observations Not measurable at 0 hrs	Augers-Size I.D. 3.25" Split Spoon 2" Hammer Wt. 140# Hammer Fall 30"	Surface Elevation: Date Started: 2-7-04 Date Completed: 2-7-04 Boring Foreman: Michael McGinley Inspector: Soils Engineer:
--	--	---

LOCATION OF BORING: As marked

Sample Depths From/To (Feet)	Type of Sample	Blows per 6" on Sampler	Moisture Density or Consist.	Strata Change Elev.	Soil Identification	Sample		
						No.	Pen. Inches	Rec. Inches
5'-7'	D	13/9/13/20	Damp		Sand and gravel	1	24	5
9'-11'	D	44/45/28/100 for 3"	Wet		Sand, gravel and rock	2	21	8
					Set up to core			
11'-12'	C	11:15-11:23						
12'-13'	C	11:23-11:27						
13'-14'	C	11:27-11:30						
14'-15'	C	11:31-11:36						
15'-16'	C	11:36-11:40						

Ground Surface to 9' Used 3.25" augers; Then S.S. to 11' set up to core

Earth Borings 11'
Rock Coring 5'
Samples: 2
HOLE NUMBER B-1

MIKE'S BORING & CORING
PO Box 75 • East Barre, Vermont 05649 • 802 476-5073

TO: Brian Austin DuBois and King, Inc. P.O. Box 339 Randolph, VT 05060-0339	PROJECT NAME: Brattleboro Bridge LOCATION: Brattleboro, VT MBC JOB #: 05001	SHEET: 2 DATE: 2-4-04 HOLE #: B-2 LINE & STA. OFFSET:
--	---	---

Ground Water Observations Not measurable at 0 hrs	Augers-Size I.D. 3.25" Split Spoon 2" Hammer Wt. 140# Hammer Fall 30"	Surface Elevation: Date Started: 2-4-04 Date Completed: 2-7-04 Boring Foreman: Michael McGinley Inspector: Soils Engineer:
--	--	---

LOCATION OF BORING: As marked

Sample Depths From/To (Feet)	Type of Sample	Blows per 6" on Sampler	Moisture Density or Consist.	Strata Change Elev.	Soil Identification	Sample		
						No.	Pen. Inches	Rec. Inches
5'-7'	D	51/25/31/7	Damp		Sand and stones	1	24	6
10'-12'	D	100 for 4"	Wet	8'	Auger refusal at 8' end of split spoon wet sand rock	2	20	18
15'-17'	D	77/100 for 4"	Wet		Sand and rock	3	10	10
					Set up to core			
13'-14'	C	12:05-12:15						
14'-15'	C	12:15-12:20						
15'-16'	C	12:00-12:24						
16'-17'	C	12:32-12:40						
17'-18'	C	12:40-12:46						
18'-19'	C	12:46-12:55						
19'-20'	C	12:55-1:00						
20'-21'	C	1:00-1:06						
21'-22'	C	1:06-1:13						
22'-23'	C	1:13-1:19						

Ground Surface to 15" Used 3.25" augers; Then S.S. to 17' set up to core

Earth Borings 17'
Rock Coring 10'
Samples: 3
HOLE NUMBER B-2

MIKE'S BORING & CORING
P.O. Box 75
East Barre, VT 05649

To: Brian Austin
DuBois and King, Inc.
P.O. Box 339
Randolph, VT 05060-0339

Date	1-5-05
Job Name/Site	Brattleboro Bridge
Job Number	05001
Crew	Mike and Roland
Inspector	Aaron

HOLE #	OFFSET	STATIC LEVEL	SOILS	AUGER REFUSAL (Feet)	DEPTH (Feet)
P-1	N/A	10'	4" asphalt into medium sand, gravel and cobbles	13'	13'
P-2	N/A	N/A	4" asphalt into medium sand, gravel and cobbles	12'	12'

TOTAL FOOTAGE: 25'
AUGERS USED: Solid

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z:\0\062bor\logs.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: MIKE'S BORING & CORING
BORING LOGS (1 OF 3)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 26 OF 68



VT Trans		STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH SECTION SUBSURFACE INFORMATION		BORING LOG		Boring No.: B-3				
Brattleboro Bridge Replacement		23275.1001.32000		Page No.: 1 of 2		Pin No.: BRO 1442(35)				
Checked By: JACM		Casing Sampler		Groundwater Observations						
Boring Crew: S. Clavette, K. Owens		Type: WASH BORE SS		Date	Depth (ft)	Notes				
Date Started: 11/15/11 Date Finished: 11/15/11		I.D.: 4 in 1.25 in		11/15/11	6.5					
VTSPG NAD83: N 135114.20 ft E 1607437.23 ft		Hammer Wt: 300 lb 140 lb								
Station: 102+77.63 Offset: 2.54 FT		Hammer Fall: 30 in. 30 in.								
Ground Elevation: 540.0 ft		Hammer/Rod Type: Safety								
		Rig: B53 Mobile								
		C _r = 1.0								
Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (ROD %)	Drill Rate minutes/ft	Blows/ft (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
0.0 - 0.5	ASPHALT PAVEMENT, 0.0 ft - 0.5 ft									
0.5 - 2.5	(FILL), f.m.c. SAND, little silt, little f.c. gravel, compact, gray - light brown, moist, Rec. = 1.0 ft					27-23-14-10 (37)				
2.5 - 5.0	(FILL), Similar Soil, medium compact, Rec. = 0.9 ft (FILL), f.m. SAND, Some Silt, little f.c. gravel, medium compact, dark brown, moist					9-5-9-14 (14)				
5.0 - 7.5	(FILL), f.c. GRAVEL, Some f.m.c. Sand, little silt, loose, light brown, moist, Rec. = 0.5 ft					9-9-8-5 (17)				
7.5 - 10.0	(SM), f.m.c. SAND, Some Silt, little f.c. gravel, trace organics, loose, brown, wet, Rec. = 1.2 ft (SP), f.m.c. SAND, Some f.c. Gravel, trace silt, trace organics, loose, brown, wet					2-1-6-4 (7)	20.7	39.9	45.3	14.8
10.0 - 12.5	(SP), Similar Soil, no organics, very compact, light brown, wet, Rec. = 0.7 ft (SP), grades to Some f.c. Gravel, light brown, wet, Rec. = 0.6 ft					28-87-42-35 (>100)				
12.5 - 15.0	(Completely Weathered Bedrock), SILT, Some f.c. Gravel, little f.m.c. sand, very compact, black - gray - brown, moist, Rec. = 0.7 ft					38-42-34-41 (76)				
15.0 - 17.5	(Completely Weathered Bedrock), f.c. GRAVEL, f.m.c. SAND, little silt, very compact, light brown - gray - white, moist, Rec. = 1.2 ft (Completely Weathered Bedrock), C. Gravel, little silt, trace f.m.c. sand, very compact, gray - orange, moist, Rec. = 0.1 ft					56-48-48-51 (96)	9.5	44.4	39.4	16.2
17.5 - 19.0	(Completely Weathered Bedrock), C. Gravel, little silt, trace f.m.c. sand, very compact, gray - orange, moist, Rec. = 0.1 ft					64-73-66-82 (>100)				
19.0 - 24.0	19.0 ft - 24.0 ft, Gneiss, hard, slightly to moderately weathered, very close fractures, gray, Poor rock, NXDC		R-1 (?)	100 (32)	0.15					
Top of Bedrock @ 19.0 ft										

VT Trans		STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH SECTION SUBSURFACE INFORMATION		BORING LOG		Boring No.: B-3				
Brattleboro Bridge Replacement		23275.1001.32000		Page No.: 2 of 2		Pin No.: BRO 1442(35)				
Checked By: JACM		Casing Sampler		Groundwater Observations						
Boring Crew: S. Clavette, K. Owens		Type: WASH BORE SS		Date	Depth (ft)	Notes				
Date Started: 11/15/11 Date Finished: 11/15/11		I.D.: 4 in 1.25 in		11/15/11	6.5					
VTSPG NAD83: N 135114.20 ft E 1607437.23 ft		Hammer Wt: 300 lb 140 lb								
Station: 102+77.63 Offset: 2.54 FT		Hammer Fall: 30 in. 30 in.								
Ground Elevation: 540.0 ft		Hammer/Rod Type: Safety								
		Rig: B53 Mobile								
		C _r = 1.0								
Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (ROD %)	Drill Rate minutes/ft	Blows/ft (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
22.5 - 25.0	24.0 ft - 29.0 ft, Gneiss, hard, moderately weathered, gray, Poor rock, NXDC		R-2 (?)	100 (57)	0.16					
Hole stopped @ 29.0 ft										
Remarks: 1. Casing driven through asphalt to obtain first sample. 2. Casing and spoon refusal at 16.5'. Top of rock estimated at 16.5'. Roller bit advanced to refusal at 19' to obtain competent rock information. 3. Boring backfilled with cuttings and bituminous cold patch.										

VT Trans		STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH SECTION SUBSURFACE INFORMATION		BORING LOG		Boring No.: B-4				
Brattleboro Bridge Replacement		23275.1001.32000		Page No.: 1 of 2		Pin No.: BRO 1442(35)				
Checked By: JACM		Casing Sampler		Groundwater Observations						
Boring Crew: S. Clavette, K. Owens		Type: WASH BORE SS		Date	Depth (ft)	Notes				
Date Started: 11/15/11 Date Finished: 11/16/11		I.D.: 4 in 1.25 in		11/16/11	7.0					
VTSPG NAD83: N 135165.55 ft E 1607420.96 ft		Hammer Wt: 300 lb 140 lb								
Station: 103+30.82 Offset: -5.89 FT		Hammer Fall: 30 in. 30 in.								
Ground Elevation: 541.0 ft		Hammer/Rod Type: Safety								
		Rig: B53 Mobile								
		C _r = 1.0								
Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (ROD %)	Drill Rate minutes/ft	Blows/ft (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
0.0 - 0.5	ASPHALT PAVEMENT, 0.0 ft - 0.5 ft									
0.5 - 2.5	(FILL), f.m. SAND, little silt, trace f.c. gravel, medium compact, brown/gray, moist, Rec. = 1.0 ft (FILL), grades to Some Silt, little f.c. gravel, medium compact, brown/gray, moist, Rec. = 0.5 ft					12-7-6-5 (13)				
2.5 - 5.0	(FILL), f.c. GRAVEL, Some f.m.c. Sand, trace silt, medium compact, gray, moist, Rec. = 0.4 ft (FILL), Similar Soil, very compact, brown/gray, moist, Rec. = 0.5 ft					5-3-12-14 (15)				
5.0 - 7.5	(SM), f.m. SAND, little f.c. gravel, little silt, medium compact, brown, wet, Rec. = 0.3 ft					7-5-18-17 (23)	7.1	59.6	30.7	9.7
7.5 - 10.0	(Completely Weathered Bedrock), f.m.c. SAND, little f.c. gravel, trace silt, brown/orange, moist, Rec. = 0.5 ft					23-23-41-18 (64)				
10.0 - 12.5	(Completely Weathered Bedrock), f.m.c. SAND, little f.c. gravel, trace silt, brown/orange, moist, Rec. = 0.5 ft					17-10-3-5 (13)				
12.5 - 15.0	(Completely Weathered Bedrock), f.m.c. SAND, little f.c. gravel, trace silt, brown/orange, moist, Rec. = 0.5 ft					27-46-100/5 (>100)				
15.0 - 17.5	13.0 ft - 13.7 ft, Gneiss, hard, moderately weathered, gray, Not competent NXDC 14.0 ft - 19.0 ft, Gneiss, hard, moderately weathered, close fractures, gray, Good rock, NXDC		R-1 (?)	43 (0)	0.11					
17.5 - 19.0	19.0 ft - 24.0 ft, Gneiss, hard, slightly weathered, gray, Good rock, NXDC		R-2 (?)	100 (88)	0.086					
Top of Bedrock @ 13.0 ft										

ABUTMENT NO. 1
TOP OF FOOTING
EL = 523.5

ABUTMENT NO. 2
TOP OF FOOTING
EL = 530.0

Notes:
1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C_r is the hammer energy correction factor.
3. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

Notes:
1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C_r is the hammer energy correction factor.
3. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.



Notes:
1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C_r is the hammer energy correction factor.
3. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)


FILE NAME: z10j062borlogs.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: VTRANS
BORING LOGS (2 OF 3)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 27 OF 68





WINGWALL NO. 3
TOP OF FOOTING
EL = 530.0



WINGWALL NO. 3
TOP OF FOOTING
EL = 534.0



BORING LOG 23275.BRO1442(35).BORINGS.CHM.STYLE.GPJ VERMONT AOT.GDT 12/6/11

BORING LOG 23275.BRO1442(35).BORINGS.CHM.STYLE.GPJ VERMONT AOT.GDT 12/6/11

BORING LOG 23275.BRO1442(35).BORINGS.CHM.STYLE.GPJ VERMONT AOT.GDT 12/6/11



PROJECT NAME:	BRATTLEBORO	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	DRAWN BY:	E.A. FIALA
FILE NAME:	z10j062borlogs.dgn	DESIGNED BY:	VTRANS
PROJECT LEADER:	S.E. BURBANK	BORING LOGS (3 OF 3)	CHECKED BY: S.E. BURBANK
			SHEET 28 OF 68





PROJECT NAME: BRATTLEBORO	
PROJECT NUMBER: BRO 1442(35)	
FILE NAME: z10j062pe.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA	CHECKED BY: S.E. BURBANK
PLAN AND ELEVATION	SHEET 29 OF 68





FRAMING PLAN FOR NON-VOIDED SLABS


SCALE 1/4" = 1'-0"

PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup.dgn
 PROJECT LEADER: S.E. BURBANK
 DESIGNED BY: E.A. FIALA
 FRAMING PLAN


PLOT DATE: 10/14/2013
 DRAWN BY: J.L. LEMIEUX
 CHECKED BY: S.E. BURBANK
 SHEET 30 OF 68






NON-VOIDED SLAB PLAN - TYPE I
 BEAM NO. 1 (BEAM NO. 7 SAME BY 180° ROTATION)
 SCALE 1/2" = 1'-0"

DRIP NOTCH
 SEE SD-502.00 FOR
 DETAILS AND LOCATIONS




▲ - (2) SHIELDED AT ENDS FOR 4'-0"

PRESTRESSED S11-36 BEAM
 TYPICAL SECTION - STRAND LAYOUT
 SCALE 1 1/2" = 1'-0"




* - BARS PLACED AT
 BEGINNING OF CURB ON BEAM
 NO. 1 SHALL BE TURNED AS
 REQUIRED TO FIT FLARED
 END OF CURB


PRESTRESSED S11-36 BEAM
 TYPICAL SECTION - REINFORCING
 SCALE 1 1/2" = 1'-0"



PRESTRESSED S11-36 BEAM
 TYPICAL SECTION - END REINFORCEMENT
 SCALE 1 1/2" = 1'-0"



CURB BAR
 SCALE 1 1/2" = 1'-0"



"M" BAR **
 SCALE 1 1/2" = 1'-0"

** - FIRST "M" - BAR SHALL BE PARALLEL WITH END OF S11-36 BEAM,
 2ND SHALL BE FLARED AND THIRD SHALL BE PERPENDICULAR WITH
 THE SIDES OF THE S11-36 BEAM. FIRST "M" - BAR SHALL BE LOCATED
 SO AS TO BE 3" CLEAR FROM THE ASPHALTIC PLUG JOINT. CONTRACTOR
 SHALL COORDINATE BETWEEN ASPHALTIC PLUG MANUFACTURER, INSTALLER
 AND NON-VOIDED SLAB FABRICATOR TO LOCATE "M" - BAR PROPERLY.


NOTES:

- REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507, LEVEL II.
- SEE NEXT SHEET FOR END OF BEAM REINFORCING AND STIRRUP SPACING.


PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup01.dgn PLOT DATE: 10/14/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: B.M. KLINEFELTER CHECKED BY: S.E. BURBANK
 NON-VOIDED SLAB DETAILS TYPE I (1 OF 2) SHEET 31 OF 68





SOUTH END OF BEAM NO. 1 - REINFORCING
 PLAN TYPE I NON-VOIDED SLAB
 (NORTH END OF BEAM NO. 7 SAME BY 180° ROTATION)
 SCALE 1" = 1'-0"



NORTH END OF BEAM NO. 1 - REINFORCING
 PLAN TYPE I NON-VOIDED SLAB
 (SOUTH END OF BEAM NO. 7 SAME BY 180° ROTATION)
 SCALE 1" = 1'-0"


NOTES:

- REINFORCING STEEL SHALL MEET WITH THE REQUIREMENTS OF SECTION 507, LEVEL II.


PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup01.dgn PLOT DATE: 10/14/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: B.M. KLINEFELTER CHECKED BY: S.E. BURBANK
 NON-VOIDED SLAB DETAILS TYPE I (2 OF 2) SHEET 32 OF 68






NON-VOIDED SLAB PLAN - TYPE II
 BEAM NO. 2 (BEAM NO. 6 SAME BY 180° ROTATION)
 SCALE 1/2" = 1'-0"




- ▲ - (2) SHIELDED AT ENDS FOR 10'-0"
- - (2) SHIELDED AT ENDS FOR 12'-0"
- - (2) SHIELDED AT ENDS FOR 14'-0"


PRESTRESSED S11-48 BEAM
 TYPICAL SECTION - STRAND LAYOUT
 SCALE 1/2" = 1'-0"



PRESTRESSED S11-48 BEAM
 TYPICAL SECTION - REINFORCING
 SCALE 1/2" = 1'-0"



PRESTRESSED S11-48 BEAM
 TYPICAL SECTION - END REINFORCING
 SCALE 1/2" = 1'-0"



"M" BAR **
 SCALE 1/2" = 1'-0"


** - FIRST "M" - BAR SHALL BE PARALLEL WITH END OF S11-48 BEAM, 2ND SHALL BE FLARED AND THIRD SHALL BE PERPENDICULAR WITH THE SIDES OF THE S11-48 BEAM. FIRST "M" - BAR SHALL BE LOCATED SO AS TO BE 3" CLEAR FROM THE ASPHALTIC PLUG JOINT. CONTRACTOR SHALL COORDINATE BETWEEN ASPHALTIC PLUG MANUFACTURER, INSTALLER AND NON-VOIDED SLAB FABRICATOR TO LOCATE "M" - BAR PROPERLY.

NOTES:


1. REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507, LEVEL II.
2. SEE NEXT SHEET FOR END OF BEAM REINFORCING AND STIRRUP SPACING.

PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup02.dgn PLOT DATE: 10/14/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: B.M. KLINEFELTER CHECKED BY: S.E. BURBANK
 NON-VOIDED SLAB DETAILS TYPE II (1 OF 2) SHEET 33 OF 68



SOUTH END OF BEAM NO. 2 - REINFORCING
 PLAN TYPE II NON-VOIDED SLAB
 (NORTH END OF BEAM NO. 6 SAME BY 180° ROTATION)
 SCALE 1" = 1'-0"



NORTH END OF BEAM NO. 2 - REINFORCING
 PLAN TYPE II NON-VOIDED SLAB
 (NORTH END OF BEAM NO. 6 SAME BY 180° ROTATION)
 SCALE 1" = 1'-0"

NOTES:


- REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507, LEVEL II.

PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup02.dgn
 PROJECT LEADER: S.E. BURBANK
 DESIGNED BY: B.M. KLINEFELTER
 NON-VOIDED SLAB DETAILS TYPE II (2 OF 2) SHEET 34 OF 68


PLOT DATE: 10/14/2013
 DRAWN BY: E.A. FIALA
 CHECKED BY: S.E. BURBANK






VOIDED SLAB PLAN - TYPE III

BEAM NO. 3, 4 AND 5
SCALE 1/2" = 1'-0"




- ▲ - (2) SHIELDED AT ENDS FOR 10'-0"
- - (2) SHIELDED AT ENDS FOR 12'-0"
- - (2) SHIELDED AT ENDS FOR 14'-0"


**PRESTRESSED S11-48 BEAM
TYPICAL SECTION - STRAND LAYOUT**
SCALE 1/2" = 1'-0"



**PRESTRESSED S11-48 BEAM
TYPICAL SECTION - REINFORCING**
SCALE 1/2" = 1'-0"



**PRESTRESSED S11-48 BEAM
TYPICAL SECTION - END REINFORCING**
SCALE 1/2" = 1'-0"



"M" BAR **
SCALE 1/2" = 1'-0"


** - FIRST "M" - BAR SHALL BE PARALLEL WITH END OF S11-48 BEAM, 2ND SHALL BE FLARED AND THIRD SHALL BE PERPENDICULAR WITH THE SIDES OF THE S11-48 BEAM. FIRST "M" - BAR SHALL BE LOCATED SO AS TO BE 3" CLEAR FROM THE ASPHALTIC PLUG JOINT. CONTRACTOR SHALL COORDINATE BETWEEN ASPHALTIC PLUG MANUFACTURER, INSTALLER AND NON-VOIDED SLAB FABRICATOR TO LOCATE "M" - BAR PROPERLY.

NOTES:


1. REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507, LEVEL 11.
2. SEE NEXT SHEET FOR END OF BEAM REINFORCING AND STIRRUP SPACING.

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062sup03.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	B.M. KLINEFELTER
NON-VOIDED SLAB DETAILS TYPE III(1 OF 2)	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	35 OF 68





SOUTH END OF BEAM NO. 3, 4, & 5 -
 REINFORCING PLAN TYPE III NON-VOIDED SLAB
 SCALE 1" = 1'-0"




SOUTH END OF BEAM NO. 3, 4, & 5 -
 REINFORCING PLAN TYPE III NON-VOIDED SLAB
 SCALE 1" = 1'-0"

- NOTES:
- REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF SECTION 507, LEVEL II.

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062sup03.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	B.M. KLINEFELTER
NON-VOIDED SLAB DETAILS TYPE III(2 OF 2)	SHEET 36 OF 68
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK






**SHEAR KEY DETAIL
@ POST-TENSIONING SLEEVE**


SCALE 1/2" = 1'-0"

** NOTE: INSTALL OAKUM AFTER UNITS HAVE BEEN PLACED



0.6" Ø TRANSVERSE TENDON DETAIL
NOT TO SCALE

* TRANSVERSE TIES SHALL BE COVERED BY SEAMLESS POLYPROPYLENE SHEATH (WITH CORROSION INHIBITER GREASE BETWEEN SHEATH AND STRAND) FOR THE LENGTH OF STRAND, EXCEPT AT ANCHORAGE LOCATIONS. TIES SHALL BE TENSIONED TO 47 KIPS.




**PRESTRESSED BEAM
ANCHOR DETAIL**
NOT TO SCALE

1. CONTRACTOR SHALL SUPPLY A SELF-ADHESIVE COMPRESSIBLE SEALER BETWEEN THE BOTTOM OF THE UNITS AND THE BRIDGE SEAT. THIS COMPRESSIBLE SEALER SHALL SURROUND THE 2 1/2" DIA SLEEVE IN THE UNIT. THE PURPOSE OF THE SEALER IS TO FACILITATE PLACEMENT OF THE GROUT AROUND THE ANCHOR BOLTS.
2. GROUT ANCHOR BOLTS INTO THE SLEEVES. BEFORE THE GROUT CURES, PLACE THE WASHER PLATE AND INSTALL THE NUT ON TOP AND TIGHTEN.
3. PAYMENT FOR BEAM ANCHORAGE, INCLUDING ALL MATERIALS, LABOR, AND INCIDENTALS WILL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE NON-VOIDED SLABS.


PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062reinfg.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: B.M. KLINEFELTER
PRESTRESSED BEAM DETAILS

PLOT DATE: 10/14/2013
DRAWN BY: J.L. LEMIEUX
CHECKED BY: S.E. BURBANK
SHEET 37 OF 68




OVERLAY REINFORCING PLAN
SCALE 1/4" = 1'-0"



FLARED END DETAIL FOR 1'-3" CURB

CURB REINFORCING STIRRUP BARS SHALL BE TURNED AS REQUIRED TO FIT FLARED ENDS.



TYPICAL OVERLAY REINFORCEMENT
SCALE 1/2" = 1'-0"

NOTE:


- NF = NEAR FACE
- FF = FAR FACE
- EF = EACH FACE
- ▲ = CUT TO FIT IN FIELD
- 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
- 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)


FILE NAME: z10j062deck.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: B.M. KLINEFELTER
OVERLAY REINFORCING DETAILS

PLOT DATE: 10/14/2013
DRAWN BY: J.L. LEMIEUX
CHECKED BY: S.E. BURBANK
SHEET 38 OF 68







ELASTOMERIC BEARING
SIDE ELEVATION
SCALE 3" = 1'-0"




ELASTOMERIC BEARING
FRONT ELEVATION
SCALE 3" = 1'-0"



ELASTOMERIC BEARING SIDE VIEW
SCALE 3" = 1'-0"



TAPERED TOP PLATE DETAIL
SCALE 6" = 1'-0"



ELASTOMERIC BEARING
PLAN VIEW
SCALE 3" = 1'-0"

BEARING NOTES

1. BEARINGS SHALL CONFORM TO THE APPLICABLE SUBSECTIONS OF SECTIONS 531 AND 731.
2. THE BEARINGS, INCLUDING ANCHOR BOLTS, DRILLING AND GROUTING, AND WASHERS AND NUTS SHALL BE PAID FOR UNDER ITEM 531.17 "BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMER PAD."
3. ALL PLATES, NUTS, WASHERS AND ANCHOR BOLTS SHALL BE GALVANIZED OR METALIZED AS PER SUBSECTIONS 726.08 AND 726.09. AREAS OF GALVANIZING OR METALIZING DAMAGED BY FIELD WELDING OR HANDLING SHALL BE REPAIRED IN CONFORMANCE WITH SUBSECTIONS 726.08 AND 726.09.
4. ALL REINFORCEMENT BETWEEN LAYERS OF ELASTOMER SHALL BE STEEL, MEETING THE REQUIREMENTS OF SUBSECTION 714.02. ALL INTERNAL STEEL PLATES SHALL BE SAND BLASTED AND FREE OF COATINGS, RUST AND MILL SCALE. THE PLATES SHALL BE FREE OF SHARP EDGES AND BURRS.
5. ANCHOR BOLTS SHALL BE ASTM F1554, GRADE 55 AND MEET THE REQUIREMENTS OF SUBSECTION 714.08.
6. STEEL REINFORCED ELASTOMERIC BEARINGS SHALL HAVE A MINIMUM 1/4" EDGE SEAL OF ELASTOMER INTEGRAL WITH BEARING OVER ALL INTERNAL PLATES.

7. THE ELASTOMER WAS DESIGNED USING METHOD A WITH A SHEAR MODULUS OF 100 PSI.
8. THE ELASTOMER SHALL MEET THE REQUIREMENTS OF LOW TEMPERATURE ZONE D, GRADE 4.
9. THE CONCRETE UNDER THE BEARING DEVICE SHALL BE LEVEL IN THE LONGITUDINAL DIRECTION
10. ALL DESIGNS DONE FOR THE BEARINGS SHALL BE PER THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS 6TH EDITION AND ITS LATEST REVISIONS.
11. ALTERNATIVE CONFIGURATIONS FOR BEARINGS MAY BE SUBMITTED FOR APPROVAL. ANY ALTERNATE SUBMITTED SHALL BE DESIGNED AND CERTIFIED TO MEET THE DESIGN LOADS AND CRITERIA SHOWN ON THE PLANS.
12. BRIDGE SEAT ELEVATIONS MAY BE REVISED TO ACCOMMODATE AN ALTERNATIVE CONFIGURATION.
13. DESIGN CRITERIA:
 - A.) HORIZONTAL CAPACITY SHALL BE A MINIMUM OF 15% VERTICAL LOAD IN ANY UNRESTRAINED DIRECTION.
 - B.) DESIGN LOAD PER BEARING
 - DL = 15 KIPS
 - LL = 25 KIPS W/O IMPACT





- * (2) 1/4" EXTERIOR LAYERS OF ELASTOMER
- (3) 1/2" INTERIOR LAYERS OF ELASTOMER
- (3) 1/8" STEEL REINFORCING PLATES
- (1) TAPERED STEEL REINFORCING TOP PLATE (SEE DETAIL)

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sup.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: E.A. FIALA
BEARING DETAILS

PLOT DATE: 10/14/2013
DRAWN BY: J.L. LEMIEUX
CHECKED BY: S.E. BURBANK
SHEET 39 OF 68







NOTE:
NF = NEAR FACE
FF = FAR FACE
EF = EACH FACE
▲ = CUT TO FIT IN FIELD
3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
2'-2" BAR LAP UNLESS OTHERWISE SPECIFIED ON THE PLANS.

*** JOINT IS TO BE LOCATED ACCURATELY BY STRING LINING, OR OTHER MEANS, PRIOR TO PAVING, SO THAT THE SAW CUTS WILL BE MADE DIRECTLY OVER THE END OF THE APPROACH SLAB. JOINT SHALL BE CUT DRY IN A SINGLE PASS AND BE SEALED WITHIN 24 HOURS OR PRIOR TO EXPOSURE TO TRAFFIC. JOINT SHALL BE CLEANED PRIOR TO APPLYING THE JOINT SEALER.


PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062sup04.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	S.E. BURBANK
APPROACH SLAB DETAILS	
PLOT DATE:	10/14/2013
DRAWN BY:	J.L. LEMIEUX
CHECKED BY:	S.E. BURBANK
SHEET	40 OF 68



ABUTMENT NO. 1 PLAN VIEW
SCALE 1/4" = 1'-0"



ABUTMENT NO. 1 ELEVATION
SCALE 1/4" = 1'-0"





ABUTMENT NO. 1 TYPICAL
SCALE 1/2" = 1'-0"

NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME:	BRATTLEBORO	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	DRAWN BY:	D.A. GINGRAS
FILE NAME:	z10j062sub1.dgn	DESIGNED BY:	C.J. HAKEY
PROJECT LEADER:	S.E. BURBANK	ABUTMENT NO. 1 PLAN & ELEVATION	CHECKED BY: S.E. BURBANK
			SHEET 41 OF 68






NOTE:


- NF = NEAR FACE
- FF = FAR FACE
- EF = EACH FACE
- ▲ = CUT TO FIT IN FIELD

3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.


2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.



WINGWALL NO. 2 CORNER
DETAIL BELOW SEAT
SCALE 1/2" = 1'-0"



WW2 ELEVATION
SCALE 1/4" = 1'-0"




WINGWALL NO. 2 TYPICAL
SCALE 1/2" = 1'-0"

NOTE:

NF = NEAR FACE
FF = FAR FACE
EF = EACH FACE
▲ = CUT TO FIT IN FIELD

3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.

2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.




ABUTMENT NO. 1 FOOTING REINFORCING PLAN VIEW
SCALE 1/4" = 1'-0"


NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062sub1.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	C.J. HAKEY
ABUTMENT NO. 1 FOOTING PLAN	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	44 OF 68






ABUTMENT NO. 2 PLAN VIEW
SCALE 1/4" = 1'-0"



ABUTMENT NO. 2 TYPICAL
SCALE 1/2" = 1'-0"




ABUTMENT NO. 2 ELEVATION
SCALE 1/4" = 1'-0"

NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME:	BRATTLEBORO	FILE NAME:	z10j062sub2.dgn	PLOT DATE:	10/14/2013
PROJECT NUMBER:	BRO 1442(35)	PROJECT LEADER:	S.E. BURBANK	DRAWN BY:	E.A. FIALA
		DESIGNED BY:	C.J. HAKY	CHECKED BY:	S.E. BURBANK
		ABUTMENT NO. 2 PLAN & ELEVATION		SHEET	45 OF 68





NOTE: FOR INFORMATION NOT SHOWN SEE WW3 ELEVATION AND WINGWALL NO. 3 TYPICAL SECTION B-B.


TYPICAL STEP FOOTING REBAR
SCALE 1/2" = 1'-0"

NOTE:

- NF = NEAR FACE
- FF = FAR FACE
- EF = EACH FACE
- ▲ = CUT TO FIT IN FIELD


3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.

2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.




WINGWALL NO. 3
TYPICAL SECTION A-A
SCALE 1/2" = 1'-0"

SEE WINGWALL NO. 4 ELEVATION AND DETAILS SHEET FOR SECTION B-B.



NOTE: SEE TYPICAL STEP FOOTING REBAR AND WINGWALL NO. 3 TYPICAL SECTION A-A AND B-B FOR DETAILS NOT SHOWN.

WW3 ELEVATION
SCALE 1/4" = 1'-0"




WINGWALL NO. 3 CORNER DETAIL BELOW SEAT
SCALE 1/2" = 1'-0"


PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062sub2.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: C.J. HAKEY
WINGWALL NO. 3 ELEVATION & DETAILS


PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 46 OF 68




WINGWALL NO. 3
TYPICAL SECTION B-B
 SCALE 1/2" = 1'-0"



WINGWALL NO. 4 CORNER
DETAIL BELOW SEAT
 SCALE 1/2" = 1'-0"



WW4 ELEVATION
 SCALE 1/4" = 1'-0"




WINGWALL NO. 4 TYPICAL
 SCALE 1/2" = 1'-0"

NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062sub2.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	C.J. HAKEY
WINGWALL NO. 4 ELEVATION & DETAILS	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	47 OF 68





ABUTMENT NO. 2 FOOTING REINFORCING PLAN VIEW
 SCALE 1/4" = 1'-0"

NOTE:
 NF = NEAR FACE
 FF = FAR FACE
 EF = EACH FACE
 ▲ = CUT TO FIT IN FIELD
 3" CLEAR, UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 2'-2" BAR LAP UNLESS SPECIFIED ON THE PLANS.

PROJECT NAME: BRATTLEBORO	
PROJECT NUMBER: BRO 1442(35)	
FILE NAME: z10j062sub2.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: E.A. FIALA
DESIGNED BY: C.J. HAKEY	CHECKED BY: S.E. BURBANK
ABUTMENT NO. 2 FOOTING PLAN	SHEET 48 OF 68




REINFORCING STEEL SCHEDULE

ITEM	EACH	SIZE	LENGTH	MARK	TYPE	A	B	C	D	E	F	G	H	J	K	R	O	ITEM	EACH	SIZE	LENGTH	MARK	TYPE	A	B	C	D	E	F	G	H	J	K	R	O
APPROACH SLAB NO. 2																																			
*	7	5	32'- 5"	2AS501.2	STR																														
	6	5	32'- 7"	2AS502.2	STR																														
	6	5	32'- 9"	2AS503.2	STR																														
	33	9	25'- 6"	2AS901.2	1	1'- 3"	24'- 3"							0'- 11"																					

~ NOTES ~

- UNLESS OTHERWISE DESIGNATED, ALL BAR REINFORCEMENT FOR CONCRETE IN SIZES UP TO AND INCLUDING NO. 18 SHALL CONFORM TO THE REQUIREMENTS OF THE "SPECIFICATIONS FOR DEFORMED BILLET-STEEL BARS FOR CONCRETE REINFORCEMENT", AASHTO M31 (ASTM A 615-S1). ALL BARS SHALL BE GRADE 60, UNLESS OTHERWISE DESIGNATED.
- FOR TYPICAL BENDING DETAILS, RECOMMENDED PIN DIAMETER "D" OF BENDS AND HOOKS, AND OTHER STANDARD PRACTICE, SEE CURRENT CONCRETE REINFORCING STEEL INSTITUTE "MANUAL OF STANDARD PRACTICE".
- BARS WHICH REQUIRE MORE ACCURATE BENDING THAN STANDARD PRACTICES SHOULD HAVE LIMITS INDICATED.
- ALL DIMENSIONS ARE OUT TO OUT OF BAR EXCEPT "A" AND "G" ON STANDARD 180 DEGREE AND 135 DEGREE HOOKS.
- "J" DIMENSION ON 180 DEGREE HOOKS TO BE SHOWN ONLY WHERE NECESSARY TO RESTRICT HOOK SIZE. OTHERWISE, STANDARD HOOKS ARE TO BE USED.
- "H" DIMENSION ON STIRRUPS TO BE SHOWN ONLY WHEN NECESSARY TO MAINTAIN CLEARANCES.
- WHERE SLOPE DIFFERS FROM 45 DEGREES, DIMENSIONS "H" AND "K" MUST BE SHOWN.
- ▲ DENOTES BARS TO BE CUT IN FIELD.
- * DENOTES ONE EXTRA BAR ADDED FOR TESTING PURPOSES.
- △ DENOTES TWO EXTRA BARS ADDED FOR TESTING PURPOSES.
- E DENOTES EPOXY COATED REINFORCING STEEL.




BAR SIZE DESIGNATION	WEIGHT POUNDS PER FOOT	NOMINAL DIMENSIONS ROUND SECTION		
		DIAMETER INCHES	AREA INCHES ²	PERIMETER INCHES
#3	0.376	0.375	0.11	1.178
#4	0.668	0.500	0.20	1.571
#5	1.043	0.625	0.31	1.963
#6	1.502	0.750	0.44	2.356
#7	2.044	0.875	0.60	2.749
#8	2.670	1.000	0.79	3.142
#9	3.400	1.128	1.00	3.544
#10	4.303	1.270	1.27	3.990
#11	5.313	1.410	1.56	4.430
#14	7.65	1.693	2.25	5.32
#18	13.60	2.257	4.00	7.09

THE REINFORCING STEEL MARKS IN THIS SCHEDULE INDICATE THE REQUIRED BAR CORROSION RESISTANCE LEVEL. CORROSION RESISTANCE LEVEL IS DENOTED WITH A .2 FOR LEVEL TWO SUFFIX OR .3 FOR LEVEL THREE SUFFIX. .1 FOR LEVEL ONE IS TO BE OMITTED. THE BAR MATERIAL TYPE AND BAR STEEL GRADE PROVIDED FOR EACH CORROSION LEVEL WILL BE RECORDED ON THE PLANSET PI SHEET FOR AS-BUILT RECORD PLAN ARCHIVES.




PROJECT NAME:	BRATTLEBORO	PLOT DATE:	6/5/2013
PROJECT NUMBER:	BRO 1442 (35)	DRAWN BY:	E.A FIALA
FILE NAME:	z10j062rss.dgn	CHECKED BY:	S.E. BURBANK
PROJECT MANAGER:	S.E. BURBANK	SHEET	50 OF 68
DESIGNED BY:	E.A FIALA	REINFORCING STEEL SCHEDULE (2 OF 2)	



VIEW A - A

FASCIA MOUNTED WITH CURB



END VIEW

TOP VIEW

SPLICE BAR DETAILS






PLATE WASHER DETAIL



SPECIAL WASHER DETAIL




DETAIL A

Steel Beam Guard Rail Not Shown


NOTES

1. ALL WORK AND MATERIALS SHALL CONFORM TO SECTION 525.
2. PRIOR TO GALVANIZING THE ASSEMBLED POST, GRIND ALL EDGES TO A MINIMUM RADIUS OF 1/16 INCH.
3. ALL POSTS SHALL BE SET NORMAL TO GRADE.
4. SPLICES FOR THE STEEL BEAM GUARDRAIL SHALL LAP IN THE DIRECTION OF TRAFFIC.
5. A RAILING JOINT SPLICE SHALL BE PROVIDED IN ANY RAIL BAY SPANNING THE END OF AN INTEGRAL ABUTMENT BRIDGE AND AT ALL SUPERSTRUCTURE EXPANSION JOINTS.
6. SEE STANDARD DRAWING G-1 FOR DETAILS OF DELINEATORS. A DELINEATOR SHALL BE LOCATED AT EVERY FIFTH POST. WHITE IS TO BE INSTALLED ON THE DRIVER'S RIGHT. FOR ONE WAY BRIDGES, YELLOW IS TO BE INSTALLED ON THE DRIVER'S LEFT.
7. FOR RADIUS LESS THAN 950 FEET, HSS 8x4 TUBES SHALL BE SHOP BENT TO FIT THE APPLICABLE CURVE.
8. HOLES IN RAIL FOR RAIL TUBE ATTACHMENT MAY BE FIELD DRILLED. HOLES SHALL BE COATED WITH AN APPROVED ZINC-RICH PAINT PRIOR TO INSTALLATION.
9. SEE STANDARDS G-1 AND G-1d FOR ADDITIONAL DETAILS CONCERNING GUARDRAIL.





RAILING ELEVATION VIEW
(SHOWN LOOKING FROM CURB WITHOUT CURB)

* 3/4 inch min. These dimensions will vary depending upon the total amount of expansion required



VIEW C - C



BRIDGE RAIL LAYOUT
SCALE 1/8" = 1'-0"


NOTE: SEE VTRANS STD S-367B FOR APPROACH RAILING SPACING.

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)


FILE NAME: z10j062br011.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: E.A. FIALA
BRIDGE RAIL LAYOUT SHEET

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 52 OF 68






101+75




PRIVATE ROAD LT
102+45




101+50

MATCH EXISTING




102+25



101+35

BEGIN APPROACH
STA 101+35.00



102+00

BEGIN PROJECT
STA 101+80.00

ROADWAY CROSS SECTIONS
SCALE 1" = 10'-0"



STA. 101+35 TO STA. 102+45

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)



FILE NAME: z10j062xsl.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: E.A. FIALA
ROADWAY CROSS SECTIONS (1 OF 4)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 53 OF 68







DRIVEWAY RT
103+59



103+50
END BRIDGE
STA 103+27.25




102+50

103+25


ROADWAY CROSS SECTIONS
SCALE 1" = 10'-0"
STA. 102+50 TO STA. 103+59




PROJECT NAME: BRATTLEBORO	
PROJECT NUMBER: BRO 1442(35)	
FILE NAME: z10j062xsl.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA	CHECKED BY: S.E. BURBANK
ROADWAY CROSS SECTIONS (2 OF 4)	SHEET 54 OF 68




104+25




105+00
END PROJECT




104+00



104+75



103+75



104+50


ROADWAY CROSS SECTIONS
SCALE 1" = 10'-0"
STA. 103+75 TO STA. 105+00



PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)


FILE NAME: z10j062xsl.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: E.A. FIALA
ROADWAY CROSS SECTIONS (3 OF 4)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 55 OF 68



105+45
END APPROACH

F.G. = 545.89



105+25


ROADWAY CROSS SECTIONS
SCALE 1" = 10'-0"

STA. 105+25 TO STA. 105+45

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)


FILE NAME: z10j062xsl.dgn PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA CHECKED BY: S.E. BURBANK
ROADWAY CROSS SECTIONS (4 OF 4) SHEET 56 OF 68





STA. 10+35, LT
 BEGIN UNCLASSIFIED CHANNEL EXCAVATION
 GEOTEXTILE UNDER STONE FILL
 STONE FILL, TYPE III
 GRUBBING MATERIAL


10+50




STA. 11+28, LT
 END GRUBBING MATERIAL

STA. 11+16, RT
 BEGIN UNCLASSIFIED CHANNEL EXCAVATION
 GEOTEXTILE UNDER STONE FILL
 STONE FILL, TYPE III
 GRUBBING MATERIAL


11+25




10+25



11+00



10+00



10+75

CHANNEL CROSS SECTIONS

SCALE 1" = 10'-0"


STA. 10+00 TO STA. 11+25



PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062xsl.dgn
 PROJECT LEADER: S.E. BURBANK
 DESIGNED BY: E.A. FIALA
 CHANNEL CROSS SECTIONS (1 OF 3)


PLOT DATE: 10/14/2013
 DRAWN BY: E.A. FIALA
 CHECKED BY: S.E. BURBANK
 SHEET 57 OF 68



STA. 12+00, LT
 END UNCLASSIFIED CHANNEL EXCAVATION
 GEOTEXTILE UNDER STONE FILL
 STONE FILL, TYPE III
 GRUBBING MATERIAL

12+00


STA. 11+96, RT
 BEGIN GRUBBING MATERIAL




STA. 11+60, LT
 BEGIN GRUBBING MATERIAL

11+75


STA. 11+55, RT
 END GRUBBING MATERIAL



11+50




12+75



12+50

STA. 12+28, RT
 END UNCLASSIFIED CHANNEL EXCAVATION
 GEOTEXTILE UNDER STONE FILL
 STONE FILL, TYPE III
 GRUBBING MATERIAL



12+25

CHANNEL CROSS SECTIONS

SCALE 1" = 10'-0"


STA. 11+50 TO STA. 12+75



PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062xsl.dgn
 PROJECT LEADER: S.E. BURBANK
 DESIGNED BY: E.A. FIALA
 CHANNEL CROSS SECTIONS (2 OF 3)

PLOT DATE: 10/14/2013
 DRAWN BY: E.A. FIALA
 CHECKED BY: S.E. BURBANK
 SHEET 58 OF 68



13+00

CHANNEL CROSS SECTIONS

SCALE 1" = 10'-0"

STA. 13+00



PROJECT NAME: BRATTLEBORO
 PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062xsl.dgn	PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK	DRAWN BY: E.A. FIALA
DESIGNED BY: E.A. FIALA	CHECKED BY: S.E. BURBANK
CHANNEL CROSS SECTIONS (3 OF 3)	SHEET 59 OF 68

EPSC PLAN NARRATIVE

1.1 PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE REMOVAL AND REPLACEMENT OF THE EXISTING CONCRETE SUPERSTRUCTURE AND ABUTMENTS WITH RELATED APPROACH AND CHANNEL WORK. DURING CONSTRUCTION, TRAFFIC WILL BE DETOURED OVER A TEMPORARY BRIDGE PLACED UPSTREAM. THIS PROJECT IS LOCATED ON A LOCAL ROAD LOCATED NORTH OF ROUTE 9 OVER HALLADAY BROOK IN THE TOWN OF BRATTLEBORO. THE EXISTING BRIDGE IS APPROXIMATELY 25 FEET LONG AND HAS A 20 FOOT WIDE CONCRETE DECK. THE EXISTING SUBSTRUCTURE CONSISTS OF STONE ABUTMENTS AND WINGWALLS.

THE BRIDGE REPLACEMENT INCLUDES THE REMOVAL OF THE EXISTING STRUCTURE IN ITS ENTIRETY AND THE CONSTRUCTION OF A NEW 45 FOOT SINGLE SPAN BRIDGE WITH PRECAST CONCRETE NON-VOIDED SLABS TO CREATE A NEW BRIDGE WIDTH OF 26 FEET. NEW CONCRETE ABUTMENTS AND WINGWALLS WILL BE FORMED IN PLACE AND ASSOCIATED APPROACH WORK INCLUDES BRIDGE APPROACH SLABS AND NEW GUARDRAIL. ONCE THE BRIDGE IS COMPLETED, THE TEMPORARY BRIDGE AND ITS APPROACHES WILL BE REMOVED AND THE PROJECT AREA WILL BE RESTORED TO THE PREVIOUS CONDITIONS.

NOTE: AREA OF DISTURBANCE INCLUDES LIMITS OF EARTH DISTURBANCE WITHIN THE PROJECT AREA, AS WELL AS WASTE, BORROW AND STAGING AREAS, AND OTHER EARTH DISTURBING ACTIVITIES WITHIN OR DIRECTLY ADJACENT TO THE PROJECT LIMITS AS SHOWN ON THE ATTACHED EPSC PLAN.

TOTAL AREA OF DISTURBANCE AS SHOWN ON THE ATTACHED EPSC PLAN IS APPROXIMATELY 0.55 ACRES.

IT IS ANTICIPATED THAT THIS PROJECT WILL LAST ONE CONSTRUCTION SEASON.

1.2 SITE INVENTORY

1.2.1 TOPOGRAPHY

THE ROAD IN THIS PROJECT AREA IS GENERALLY FLAT AND FOLLOWS THE LAY OF THE SURROUNDING TOPOGRAPHY. THERE IS A PRIVATE GRAVEL ROAD (REGINA VISTA) THAT RUNS ALONG THE SOUTHWEST SIDE OF THE RIVER. THERE ARE 2 RESIDENCES ON EITHER END OF THE BRIDGE WITH PROPERTY THAT WILL BE WITHIN THE PROJECT AREA.

1.2.2 DRAINAGE, WATERWAYS, BODIES OF WATER, AND PROXIMITY TO NATURAL OR MAN-MADE WATER FEATURES

HALLADAY BROOK IS LOCATED IN THE PROJECT AREA AND RUNS BETWEEN SUNSET LAKE AND REGINA VISTA ROAD BEFORE PASSING UNDER SUNSET LAKE ROAD. TWO MAINTAINED ORNAMENTAL PONDS ARE LOCATED WITHIN THE PROJECT INVESTIGATION AREA ON A RESIDENTIAL PROPERTY; EACH ARE MAPPED BY THE VERMONT STATE WETLAND INVENTORY AS CLASS II WETLANDS. HALLADAY BROOK GENERALLY CONSISTS OF COBBLES AND GRAVEL WITH OCCASIONAL BOULDERS. ON THE UPSTREAM SIDE OF SUNSET LAKE ROAD BRIDGE, THE EAST BANK OF THE STREAM IS VEGETATED AND RELATIVELY FLAT PROVIDING ADJACENT FLOOD STORAGE, WHILE THE WESTERN BANK IS PARTIALLY CUT AND STEEP BEFORE TRANSITIONING INTO A FORESTED BUFFER. DOWNSTREAM FROM SUNSET LAKE ROAD BRIDGE, THE EASTERN BANK IS VEGETATED FOR APPROXIMATELY 20 FEET BEFORE TRANSITIONING INTO A MAINTAINED FIELD, AND THE WESTERN BANK CONSISTS OF A MAINTAINED RESIDENTIAL LAWN WITH STRUCTURES LOCATED NEAR THE STREAM.

1.2.3 VEGETATION

THE VEGETATION IN THE PROJECT AREA CONSISTS OF SPECKLED ALDER, YELLOW BIRCH, REED CANARY GRASS, AND GRASSED LAWN AREAS. UPON PROJECT COMPLETION, THE CHANNEL WILL BE ARMORED WITH STONE FILL TYPE III AS SPECIFIED ON THE PLANS. DISTURBED VEGETATION WILL BE REESTABLISHED WITH STANDARD SEED AND MULCH PRACTICES.

1.2.4 SOILS

ALL SOIL DATA CAME FROM THE U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE FOR THE COUNTY OF WINDSOR, VERMONT. SOILS ON THE PROJECT SITE ARE PODUNK FINE SANDY LOAM AND DEERFIELD FINE SANDY LOAM, 2% TO 8% SLOPES, "K FACTOR" = 0.24. THE SOIL IS CONSIDERED MODERATELY ERODIBLE.

NOTE: K-VALUES GENERALLY INDICATE THE FOLLOWING:

0.0-0.23 = LOW EROSION POTENTIAL
0.24-0.36 = MODERATE EROSION POTENTIAL
0.37 AND HIGHER = HIGH EROSION POTENTIAL

1.2.5 SENSITIVE RESOURCE AREAS

CRITICAL HABITATS: NO
HISTORICAL OR ARCHEOLOGICAL AREAS: NO
PRIME AGRICULTURAL LAND: NO
THREATENED AND ENDANGERED SPECIES: NO
WATER RESOURCE: HALLADAY BROOK
WETLANDS: THERE ARE TWO CLASS II WETLAND FEATURES MAPPED BY THE VERMONT STATE WETLAND INVENTORY WITHIN THE PROJECT INVESTIGATION AREA. A FIELD INVESTIGATION DETERMINED THAT THESE WERE ORNAMENTAL PONDS.

1.3 RISK EVALUATION

THIS PROJECT DOES NOT FALL UNDER THE JURISDICTION OF GENERAL PERMIT 3-9020 FOR STORM-WATER RUNOFF FROM CONSTRUCTION SITES. SHOULD CHANGES PRIOR TO OR DURING CONSTRUCTION RESULT IN ONE OR MORE ACRES OF EARTH DISTURBANCE OR SHOULD THE PROJECT BECOME PART OF A LARGER PLAN OF DEVELOPMENT, THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY ADDITIONAL PERMITTING.

1.4 EROSION PREVENTION AND SEDIMENT CONTROL

THE EROSION CONTROL PLANS ARE MEANT AS A GUIDELINE FOR PREVENTING EROSION AND CONTROLLING SEDIMENT TRANSPORT. THE PRINCIPLES OUTLINED IN THIS NARRATIVE CONSIST OF APPLYING MEASURES THROUGHOUT CONSTRUCTION OF THE PROJECT IN ORDER TO MINIMIZE SEDIMENT TRANSPORT TO THE RECEIVING WATERS. THE MEASURES INCLUDE STABILIZATION AND STRUCTURAL PRACTICES, STORM WATER CONTROLS AND OTHER POLLUTION PREVENTION PRACTICES. THEY HAVE BEEN PROPOSED BY THE DESIGNER AS A BASIS FOR PROTECTING RESOURCES AND WILL NEED TO BE BUILT UPON BASED ON THE SPECIFIC MEANS AND METHODS OF THE CONTRACTOR. REFER TO THE LOW RISK SITE HANDBOOK AND APPROPRIATE DETAIL SHEETS FOR SPECIFIC GUIDANCE AND CONSTRUCTION DETAILING.

ALL MEASURES SHALL BE REGULARLY MAINTAINED AND SHALL BE CHECKED FOR SEDIMENT BUILD-UP. SEDIMENT SHALL BE DISPOSED OF AT AN APPROVED SITE WHERE IT WILL NOT BE SUBJECT TO EROSION.

1.4.1 MARK SITE BOUNDARIES

SITE BOUNDARIES AND AREAS CONSTRUCTION EQUIPMENT CAN ACCESS SHALL BE DELINEATED.

PROJECT DEMARCATION FENCING (PDF) SHALL BE USED TO PHYSICALLY MARK SITE BOUNDARIES.

1.4.2 LIMIT DISTURBANCE AREA

PREVENTING INITIAL SOIL EROSION BY MINIMIZING THE EXPOSED AREA IS MUCH MORE EFFECTIVE THAN TREATING ERODED SEDIMENT. EARTH DISTURBANCE CAN BE MINIMIZED THROUGH CONSTRUCTION PHASING BY ONLY OPENING UP EARTH AS NECESSARY. THIS CAN LIMIT THE AREA THAT WILL BE DISTURBED AND EXPOSED TO EROSION. EMPLOY TEMPORARY CONSTRUCTION STABILIZATION PRACTICES IN INCREMENTAL STAGES AS PHASES CHANGE. FOR PROJECTS WHICH FALL UNDER THE CONSTRUCTION GENERAL PERMIT, ONLY THE ACREAGE LISTED ON THE PERMIT AUTHORIZATION MAY BE EXPOSED AT ANY GIVEN TIME.

MAINTAINING VEGETATED BUFFERS ALONG STREAM BANKS, WETLANDS OR OTHER SENSITIVE AREAS IS A CRUCIAL EROSION AND SEDIMENT CONTROL MEASURE THAT SHOULD BE ESTABLISHED WHEREVER POSSIBLE.

1.4.3 SITE ENTRANCE/EXIT STABILIZATION

TRACKING OF SEDIMENT ONTO PUBLIC HIGHWAYS SHALL BE MINIMIZED TO REDUCE THE POTENTIAL FOR RUNOFF ENTERING RECEIVING WATERS. INSTALLATION SHALL COINCIDE WITH THE PROGRESS SCHEDULE.

STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AS PROPOSED ON THE EPSC PLAN AND ANYWHERE EQUIPMENT WILL BE GOING FROM AREAS OF EXPOSED SOILS TO PAVED SURFACES.

1.4.4 INSTALL SEDIMENT BARRIERS

SEDIMENT BARRIERS SHALL BE UTILIZED TO INTERCEPT RUNOFF AND ALLOW SUSPENDED SEDIMENT TO SETTLE OUT. THEY SHALL BE INSTALLED PRIOR TO ANY UP SLOPE WORK.

SILT FENCE SHALL BE INSTALLED AS PROPOSED ON THE EPSC PLAN.

FILTER CURTAIN SHALL BE INSTALLED WHERE WORK MUST TAKE PLACE WITHIN THE LIMITS OF HALLADAY BROOK AS PROPOSED ON THE EPSC PLAN.

1.4.5 DIVERT UPLAND RUNOFF

DIVERSIONARY MEASURES SHALL BE USED TO INTERCEPT RUNOFF FROM ABOVE THE CONSTRUCTION AND DIRECT IT AROUND THE DISTURBED AREA SO THAT CLEAN WATER DOES NOT BECOME MUDDIED WHILE TRAVELING OVER EXPOSED SOILS ON THE CONSTRUCTION SITE.

THE PROJECT AREA IS RELATIVELY FLAT. THEREFORE IT IS NOT ANTICIPATED THAT DIVERSION MEASURES WILL BE NECESSARY.

1.4.6 SLOW DOWN CHANNELIZED RUNOFF

CHECK STRUCTURES SHALL BE UTILIZED TO REDUCE THE VELOCITY, AND THUS THE EROSION POTENTIAL, OF CONCENTRATED FLOW IN CHANNELS.

CHECK STRUCTURES SHALL BE INSTALLED AS SHOWN ON THE PLANS.

1.4.7 CONSTRUCT PERMANENT CONTROLS

PERMANENT STORM-WATER TREATMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH PERMIT CONDITIONS.

PERMANENT EROSION CONTROL STRUCTURES ARE NOT ANTICIPATED FOR THIS PROJECT.

1.4.8 STABILIZE EXPOSED SOILS DURING CONSTRUCTION

ALL AREAS OF DISTURBANCE MUST HAVE TEMPORARY STABILIZATION IN PLACE WITHIN 48 HOURS OF DISTURBANCE OR IN ACCORDANCE WITH THE CONSTRUCTION GENERAL PERMIT 3-9020 AUTHORIZATION.

SURFACE ROUGHENING OF ALL EXPOSED SLOPES, COMBINED WITH TEMPORARY MULCHING, SHALL BE UTILIZED ON A REGULAR BASIS. BIODEGRADABLE EROSION CONTROL MATTING OR AN EQUIVALENT SHALL BE USED TO STABILIZE ALL SLOPES STEEPER THAN 1:3.

THE FORECAST OF RAINFALL EVENTS SHALL TRIGGER IMMEDIATE PROTECTION OF EXPOSED SOILS.

1.4.9 WINTER STABILIZATION

VARIOUS MEASURES SPECIFIC TO WINTER MAY BE NECESSARY SHOULD THE PROJECT EXTEND INTO WINTER (OCTOBER 15 THROUGH APRIL 15). REFER TO THE LOW RISK SITE HANDBOOK FOR GUIDANCE.

1.4.10 STABILIZE SOIL AT FINAL GRADE

EXPOSED SOIL MUST BE STABILIZED WITHIN 48 HOURS OF REACHING FINAL GRADE.

SEED, MULCH, FERTILIZER AND LIME SHALL BE USED TO ESTABLISH PERMANENT VEGETATION. FOR SLOPES STEEPER THAN 1:3, BIODEGRADABLE EROSION CONTROL MATTING OR AN EQUIVALENT SHALL BE USED INSTEAD OF MULCH.

1.4.11 DE-WATERING ACTIVITIES

DISCHARGE FROM DEWATERING ACTIVITIES THAT FLOWS OFF OF THE CONSTRUCTION SITE MUST NOT CAUSE OR CONTRIBUTE TO A VIOLATION OF THE VERMONT WATER QUALITY STANDARDS.

TREATMENT OF DEWATERING COFFERDAM IS ANTICIPATED. A LOCATION FOR TREATMENT HAS BEEN PROPOSED AND IS SHOWN ON THE PLANS. HOWEVER THE SPECIFIC MEANS FOR TREATMENT OF DISCHARGE SHALL BE PROVIDED BY THE CONTRACTOR.

1.4.12 INSPECT YOUR SITE

INSPECT THE PROJECT SITE BASED ON SPECIAL PROVISION REQUIREMENTS OR CONSTRUCTION GENERAL PERMIT AUTHORIZATION STIPULATIONS.



1.5 SEQUENCE AND STAGING

THIS SECTION WILL BE DEVELOPED BY THE CONTRACTOR USING THE GUIDANCE OUTLINED IN THE VTRANS EPSC PLAN CONTRACTOR CHECKLIST.

1.5.1 CONSTRUCTION SEQUENCE

1.5.2 OFF-SITE ACTIVITIES

IN ADDITION TO THE CONTRACTOR CHECKLIST ANY ACTIVITIES OUTSIDE THE CONSTRUCTION LIMITS SHALL FOLLOW SUBSECTIONS 105.25- 105.29 OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION.



BEGIN APPROACH
STA. 101+35.00
MATCH EXISTING

BEGIN PROJECT
STA. 101+80.00

BEGIN BRIDGE
STA. 102+79.42
F.G. = 541.09

END PROJECT
STA. 105+00.00

END APPROACH
STA. 105+45.00
MATCH EXISTING

BM #1
NAIL IN POLE
EL. = 539.39'

END BRIDGE
STA. 103+27.25
F.G. = 542.12
TH 12 STA. 103+14.37 =
CHANNEL STA. 11+51.06



BM #2
NAIL IN POLE
EL. = 544.63'

SOIL CLASSIFICATION
PODUNK FINE SANDY LOAM
DEERFIELD FINE SANDY LOAM
2% TO 8% SLOPES
"K" FACTOR 0.24
CLASSIFIED MODERATE EROSION POTENTIAL

SCALE 1" = 20'-0"
20 0 20




PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062bdr_ero.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	E.A. FIALA
EPSC EXISTING CONDITIONS PLAN	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	61 OF 68





SOIL CLASSIFICATION
 PODUNK FINE SANDY LOAM
 DEERFIELD FINE SANDY LOAM
 2% TO 8% SLOPES
 K FACTOR 0.24
 CLASSIFIED MODERATE EROSION POTENTIAL

NOTE: SEE SHEET 11 FOR EPSC LAYOUT SYMBOLOGY LEGEND.



PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062bdr_ero.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	E.A. FIALA
EPSC CONSTRUCTION CONDITIONS PLAN	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	62 OF 68



BEGIN APPROACH
STA. 101+35.00
MATCH EXISTING

BEGIN PROJECT
STA. 101+80.00

BEGIN BRIDGE
STA. 102+79.42
F.G. = 541.09

END PROJECT
STA. 105+00.00

END APPROACH
STA. 105+45.00
MATCH EXISTING

BM #1
NAIL IN POLE
EL. = 539.39'


END BRIDGE
STA. 103+27.25
F.G. = 542.12

TH 12 STA. 103+14.37 =
CHANNEL STA. 11+51.06


BM #2
NAIL IN POLE
EL. = 544.63'

SOIL CLASSIFICATION
PODUNK FINE SANDY LOAM
DEERFIELD FINE SANDY LOAM
2% TO 8% SLOPES
"K FACTOR" 0.24
CLASSIFIED MODERATE EROSION POTENTIAL

NOTE: SEE SHEET 11 FOR EPSC LAYOUT SYMBOLGY LEGEND.



PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRO 1442(35)
FILE NAME:	z10j062bdr_ero.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	E.A. FIALA
EPSC FINAL CONDITIONS PLAN	
PLOT DATE:	10/14/2013
DRAWN BY:	E.A. FIALA
CHECKED BY:	S.E. BURBANK
SHEET	63 OF 68



SYMBOL	
	SILT FENCE
	SILT FENCE WOVEN WIRE

CONSTRUCTION SPECIFICATIONS

- WOVEN WIRE REINFORCED FENCE IS REQUIRED WITHIN 100' UPSLOPE OF RECEIVING WATERS WHEN THE PROJECT FALLS UNDER A CONSTRUCTION STORMWATER PERMIT. WOVEN WIRE SHALL BE A MIN. 14 GAUGE WITH A 6" MAX. MESH OPENING.
- FILTER CLOTH SHALL BE EITHER FILTER X, MIRAF1100X, STABILINKA T140N OR APPROVED EQUIVALENT.
- POST SPACING FOR WIRE-BACKED FENCE SHALL BE 10' MAXIMUM. FOR FILTER-CLOTH FENCE, WHEN ELONGATION IS >50%, POST SPACING SHALL NOT EXCEED 4' AND WHEN ELONGATION IS <50%, POST SPACING SHALL NOT EXCEED 6'.
- WOVEN WIRE FENCE IS TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES. FILTER CLOTH IS TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY 6" AND FOLDED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT.

ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC
ORIGINALLY DEVELOPED BY USDA-NRCS
VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION

SILT FENCE

NOTES:
REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006-" FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 649 AND AS SHOWN IN THE PLANS FOR GEOTEXTILE FOR SILT FENCE (PAY ITEM 649.51) OR GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED (PAY ITEM 649.515).

REVISIONS	
MARCH 21, 2008	WHF
DECEMBER 11, 2008	WHF
JANUARY 13, 2009	WHF

VAOT RURAL AREA MIX						
% WEIGHT	LBS/AC		NAME	GERM %	PURITY %	
	BROADCAST	HYDROSEED				
37.5%	22.5	45	CREeping RED FESCUE	85%	98%	
37.5%	22.5	45	TALL FESCUE	90%	95%	
5.0%	3	6	RED TOP	90%	95%	
15.0%	9	18	BIRDSFOOT TREFOIL	85%	98%	
5.0%	3	6	ANNUAL RYE GRASS	85%	95%	
100%	60	120				

VAOT URBAN AREA MIX						
% WEIGHT	LBS/AC		NAME	GERM %	PURITY %	
	BROADCAST	HYDROSEED				
42.5%	34	68	CREeping RED FESCUE	85%	98%	
10.0%	8	16	PERENNIAL RYE GRASS	90%	95%	
42.5%	34	68	KENTUCKY BLUE GRASS	85%	85%	
5.0%	4	8	ANNUAL RYE GRASS	85%	95%	
100%	80	160				

SOIL AMENDMENT GUIDANCE			
FERTILIZER		LIME	
BROADCAST	HYDROSEED	BROADCAST	HYDROSEED
10-20-10	FOLLOW	PELLETIZED	FOLLOW
500 LBS/AC	MANUFACTURER	2 TONS/AC	MANUFACTURER


CONSTRUCTION GUIDANCE

- RURAL SEED MIX: USE AS INDICATED IN THE PLANS AND/OR FOR ALL ESTABLISHED UPLAND (NON WETLAND) AREAS DISTURBED BY THE CONTRACTOR.
- URBAN SEED MIX: USE AS INDICATED IN THE PLANS AND/OR FOR ALL ESTABLISHED LAWN AREAS DISTURBED BY THE CONTRACTOR.
- ALL SEED MIXTURES: SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS SEED.
- FERTILIZER AND LIMESTONE: SHALL FOLLOW RATES SHOWN ON PLAN OR AS DIRECTED BY THE ENGINEER
- HAY MULCH: TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS/ACRE, ACHIEVE 90% GROUND COVER OR AS DIRECTED BY THE ENGINEER.
- TOPSOIL: TO BE USED WITH SEED AS INDICATED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.
- HYDROSEEDING: ALTHOUGH GUIDANCE IS GIVEN ABOVE THE SITE CONDITIONS AND THE TYPE OF HYDROSEED WILL ULTIMATELY DICTATE THE AMOUNTS AND TYPES OF SOIL AMENDMENTS TO BE APPLIED
- TURF ESTABLISHMENT: PLACING SEED, FERTILIZER, LIME AND MULCH PRIOR TO SEPTEMBER 15 AND AFTER APRIL 15 CAN BETTER ENSURE A VIGOROUS GROWTH OF GRASS.

ADAPTED FROM VTRANS TECHNICAL LANDSCAPE MANUAL FOR ROADWAYS AND TRANSPORTATION FACILITIES

TURF ESTABLISHMENT

REVISIONS	
JUNE 23, 2009	WHF
JANUARY 15, 2010	WHF
FEBRUARY 16, 2011	WHF



SYMBOL	
	NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

- APPLY TO SLOPES GREATER THAN 3H:1V OR WHERE NECESSARY TO AID IN ESTABLISHING VEGETATION.
- APPLY FERTILIZER, LIME SEED PRIOR TO PLACING MATTING.
- STAPLES ARE TO BE PLACED ALTERNATELY, IN COLUMNS APPROXIMATELY 2' APART AND IN ROWS APPROXIMATELY 3' APART. APPROXIMATELY 175 STAPLES ARE REQUIRED PER 4' X 225' ROLL OF MATERIAL AND 125 STAPLES ARE REQUIRED PER 4' X 150' ROLL OF MATERIAL.
- DISTURBED AREAS SHALL BE SMOOTHLY GRADED. EROSION CONTROL MATERIAL SHALL BE PLACED LOOSELY OVER GROUND SURFACE. DO NOT STRETCH.
- ALL TERMINAL ENDS AND TRANSVERSE LAPS SHALL BE STAPLED AT APPROXIMATELY 12" INTERVALS.

ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC
ORIGINALLY DEVELOPED BY USDA-NRCS
VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION

ROLLED EROSION CONTROL PRODUCT (RECP) SIDE SLOPE




NOTES:
REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006-" FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.
THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 653 AND AS SHOWN IN THE PLANS FOR TEMPORARY EROSION MATTING (PAY ITEM 653.20) OR PERMANENT EROSION MATTING (PAY ITEM 653.21).

REVISIONS	
APRIL 16, 2007	JMF
JANUARY 13, 2009	WHF

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062details_ero.dgn PLOT DATE: 10/14/2013
PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
DESIGNED BY: VTRANS CHECKED BY: S.E. BURBANK
EROSION CONTROL DETAILS (1 OF 3) SHEET 64 OF 68






PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)

FILE NAME: z10j062details_ero.dgn
PROJECT LEADER: S.E. BURBANK
DESIGNED BY: VTRANS
EROSION CONTROL DETAILS (2 OF 3)

PLOT DATE: 10/14/2013
DRAWN BY: E.A. FIALA
CHECKED BY: S.E. BURBANK
SHEET 65 OF 68



CONSTRUCTION SPECIFICATIONS

1. STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION.
2. CHECK DAMS SHALL BE SPACED SO THAT THE ELEVATION OF THE CREST OF THE DOWNSTREAM DAM IS AT THE SAME ELEVATION AS THE TOE OF THE UPSTREAM DAM.
3. 3/4" FILTERING STONE MAY BE ADDED TO THE FACE OF THE CHECK DAM AS NECESSARY.
4. EXTEND THE STONE A MINIMUM OF 1.5' BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
5. PROTECT CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS APPROPRIATE.
6. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE.
7. MAXIMUM DRAINAGE AREA 2 ACRES.


ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC ORIGINALLY DEVELOPED BY USDA-NRCS VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION	CHECK DAM
---	------------------

NOTES:
 REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006-" FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 653 FOR TEMPORARY STONE CHECK DAM, TYPE 1(PAY ITEM 653.25)

REVISIONS	
MARCH 21, 2008	WHF
JANUARY 8, 2009	WHF

PROJECT NAME: BRATTLEBORO	PLOT DATE: 10/14/2013
PROJECT NUMBER: BRO 1442(35)	DRAWN BY: E.A. FIALA
FILE NAME: z10j062details_ero.dgn	DESIGNED BY: VTRANS
PROJECT LEADER: S.E. BURBANK	CHECKED BY: S.E. BURBANK
EROSION CONTROL DETAILS (3 OF 3)	SHEET 66 OF 68



CONSTRUCT 11.5' PAVED APRON
STA. 102+69, LT - 41.5' WIDE

CONSTRUCT 12' PAVED DRIVE
STA. 103+59, RT - 12' WIDE

REMOVAL AND DISPOSAL OF GUARDRAIL
STA. 102+43 - 102+73, RT
STA. 102+92 - 102+96, LT
STA. 103+03 - 103+27, RT
STA. 103+31 - 104+46, LT

COLD PLANING, BITUMINOUS PAVEMENT
STA. 101+35 - 101+55, LT & RT
STA. 105+25 - 105+45, LT & RT

SPECIAL PROVISION (BRIDGE
RAILING, GALVANIZED HDSB/FASCIA
MOUNTED/STEEL TUBING)
STA. 102+43 - 103+25, RT
STA. 102+88 +3904908, ET

GUARDRAIL APPROACH SECTION, GALVANIZED
HD STEEL BEAM W/8 FEET POSTS
STA. 102+18 - 102+43, RT
STA. 102+92, 24.58' LT - 102+88, LT
STA. 104+08 - 104+33, LT

RELOCATE MAILBOX, MULTIPLE SUPPORT
STA. 102+39, RT

RELOCATE MAILBOX, SINGLE SUPPORT
STA. 103+83, RT

STEEL BEAM GUARDRAIL,
GALVANIZED W/8 FEET POSTS
STA. 102+12 - 102+18, RT
STA. 102+92, 24.58' LT - 103+20, 38.4' LT
STA. 104+33 - 104+63, LT

ANCHOR FOR STEEL BEAM RAIL
STA. 102+06, RT
STA. 103+25, 40.75' LT
STA. 103+30, RT
STA. 104+69, LT

STEEL BEAM GUARDRAIL, GALV.
STA. 102+00 - 102+12, RT
STA. 103+20, 38.4' LT - 103+34, 44.5' LT
STA. 103+25 - 103+36, RT
STA. 104+63 - 104+76, LT

N 134835.91 FT
E 1607460.82 FT
STA 100+00.00
24.75' LT.

BEGIN PROJECT
STA. 101+80.00

BEGIN APPROACH
STA. 101+35.00
MATCH EXISTING


STA 100+95.56
24.75' LT.

BEGIN BRIDGE
STA. 102+79.42
F.G. = 541.09

STA 102+61.15
24.75' LT.

END PROJECT
STA. 105+00.00

END APPROACH
STA. 105+45.00
MATCH EXISTING



EXISTING TOWN ROW
PER HGWY. BOOK 2/34-38
N 134845.78 FT
E 1607509.33 FT
STA 100+00.00
24.75' RT.

ANGELL, SAMUEL H. &
ANGELL, NANCIE SCHWARTZ

BEGIN R.O.W. PROJECT
BRO 1442 (35)
STA. 100+96.02
24.75' RT.

EDGE OF PAVEMENT WIDTH TRANSITION
STA. 101+55 = MATCH EXISTING LT & RT
STA. 101+80 = 12'-2" LT & RT
STA. 104+72 = 12'-2" RT
STA. 104+97 = 12'-2" LT
STA. 105+05 = MATCH EXISTING LT & RT

SCALE 1" = 20'-0"
20 0 20

**FOR R.O.W.
USE ONLY**

LINES SHOWN ON THIS PLAN AS EXISTING
PROPERTY LINES P/L ARE BELIEVED TO
BE ACCURATE BUT SHOULD NOT BE RELIED
UPON FOR PURPOSES UNRELATED TO THE
STATE OF VERMONT'S ACQUISITION OF LAND
AND RIGHTS FOR THIS PROJECT.

NOTE:
1. EXISTING BOULDER ALONG REGINA VISTA (T.H. 12
STA. 103+02, 23.83' LT) SHALL BE REMOVED AND
RESET. BOULDER SHALL BE LOCATED BEHIND THE
GUARDRAIL SO AS TO PROVIDE A MINIMUM OF 4'-0"
CLEAR ZONE BETWEEN THE BOULDER AND THE FRONT
OF GUARDRAIL. ALL COSTS FOR PROPERLY
REMOVING, STORING AND RESETTING THE BOULDER
WILL BE INCIDENTAL TO ALL CONTRACT ITEMS.


PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRO 1442(35)
FILE NAME: NAME\$DGN
PROJECT LEADER: M. CHANETTE
DESIGNED BY: S.E. BURBANK
ROW LAYOUT SHEET 1 OF 1
PLOT DATE: 10/14/2013
DRAWN BY: B. FERLAZO
CHECKED BY: H. PETROVS
SHEET 68 OF 68

END R.O.W. PROJECT
BRO 1442 (35)
STA. 104+89.02
25.83' RT.

N/F MCCARTHY, ROBERT P.
& ROSE-ANNE


CONCRETE GENERAL NOTES

- ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 1" x 1"




TYPICAL HORIZONTAL CONSTRUCTION JOINT
(NOT TO SCALE)


- THE SURFACE OF THE CONCRETE CONSTRUCTION JOINTS SHALL BE CLEANED AND FREE OF LAITANCE.
- IMMEDIATELY BEFORE NEW CONCRETE IS PLACED, ALL CONSTRUCTION JOINTS SHALL BE WETTED AND STANDING WATER REMOVED.




TYPICAL CONCRETE CONSTRUCTION JOINT
(NOT TO SCALE)




SCORE MARK DETAIL
(NOT TO SCALE)



TYPICAL CONCRETE EXPANSION JOINT
(NOT TO SCALE)




TRANSVERSE BRIDGE SLAB CONSTRUCTION JOINT DETAILS
(NOT TO SCALE)



P.V.C. WATERSTOP FOR CONSTRUCTION JOINTS
(NOT TO SCALE)

PAYMENT FOR THE P.V.C. WATERSTOP SHALL BE INCIDENTAL TO THE UNIT BID PRICE FOR THE ADJACENT CONCRETE.


OTHER CONFIGURATIONS OF WATERSTOP MAY BE USED UPON APPROVAL OF THE ENGINEER.



P.V.C. WATERSTOP FOR EXPANSION JOINTS
(NOT TO SCALE)

PAYMENT FOR THE P.V.C. WATERSTOP SHALL BE INCIDENTAL TO THE UNIT BID PRICE FOR THE ADJACENT CONCRETE.


OTHER CONFIGURATIONS OF WATERSTOP MAY BE USED UPON APPROVAL OF THE ENGINEER.




JOINT BETWEEN FASCIA AND WINGWALL
(NOT TO SCALE)

REVISIONS	
MAY 7, 2010	APPROVED FOR USE BY VAOT STRUCTURES SECTION


**CONCRETE
DETAILS AND NOTES**



**STRUCTURES
DETAIL
SD-5 01.00**




DETAIL "B"
(NOT TO SCALE)




CONCRETE CURB JOINT SECTION
(NOT TO SCALE)

1. SEE TYPICAL HORIZONTAL CONSTRUCTION JOINT DETAIL FOR ADDITIONAL INFORMATION




SECTION B - B
(NOT TO SCALE)




ACUTE ANGLE
CLIP DETAIL
(NOT TO SCALE)

CONCRETE CURB JOINT NOTES


1. CONCRETE CURBS MAY BE PLACED IN ONE CONTINUOUS OPERATION IF AN APPROVED SHRINKAGE REDUCING ADMIXTURE LISTED IN THE SPECIAL PROVISIONS IS USED WITH THE CONCRETE MIX DESIGN. PAYMENT FOR THE SHRINKAGE REDUCING ADMIXTURE WILL BE INCIDENTAL TO THE BRIDGE CURB CONCRETE ITEM.
2. IF THE CONTRACTOR CHOOSES NOT TO USE AN APPROVED SHRINKAGE REDUCING ADMIXTURE, THE CURBS SHALL BE CONSTRUCTED WITH CONSTRUCTION JOINTS SPACED AT A MAXIMUM OF 15'-0" CENTER TO CENTER AND 2'-0" MINIMUM FROM THE CENTER OF NEAREST BRIDGE RAILING POST.
3. ON MULTI-SPAN CONTINUOUS SUPERSTRUCTURES, REGARDLESS OF WHETHER APPROVED SHRINKAGE REDUCING ADMIXTURE IS USED, CURB JOINTS SHALL BE LOCATED OVER THE CENTERLINE OF PIERS AND 7'-0" EACH SIDE OF THE CENTERLINE OF EACH PIER.
4. WHEN CURB JOINTS ARE USED THE CURBS SHALL BE PLACED IN ALTERNATE SECTIONS WITH A MINIMUM OF 48 HOUR DELAY BETWEEN ADJACENT PLACEMENTS.
5. LONGITUDINAL REINFORCING SHALL BE CONTINUOUS THROUGH CURB CONSTRUCTION JOINTS. CURB STIRRUP BARS SHALL BE TURNED AS NECESSARY TO MAINTAIN COVER IN THE FLARED CURB ENDS.
6. THE JOINT SPACING AND DETAILS SHOWN SHALL APPLY TO SIDEWALKS WHEN SHOWN IN THE PLANS.




HORIZONTAL WINGWALL
CONSTRUCTION JOINT
(NOT TO SCALE)



DRIP NOTCH DETAIL
(NOT TO SCALE)



PLAN



VIEW "A - A"

BRIDGE PLAQUE
(NOT TO SCALE)


THE BRIDGE PLAQUE WILL BE SUPPLIED BY THE AGENCY OF TRANSPORTATION AND SHALL BE INSTALLED BY THE CONTRACTOR AT ABUTMENT #1 ON THE RIGHT SIDE AS SHOWN OR AS DIRECTED BY THE ENGINEER.

PAYMENT FOR INSTALLATION OF THE BRIDGE PLAQUE SHALL BE INCIDENTAL TO THE ADJACENT CONCRETE.

REVISIONS

MAY 7, 2010	APPROVED FOR USE BY VAOT STRUCTURES SECTION
JUNE 4, 2010	MODIFIED AND ADDED TWO DETAILS
OCTOBER 10, 2012	MODIFIED HORZ. JOINT WINGWALL ADD 6" MIN. DIMENSION

CONCRETE
DETAILS AND NOTES



STRUCTURES
DETAIL
SD-502.00

ASPHALTIC PLUG JOINT NOTES


INSTALLATION:

1. LOCATE THE JOINT CENTRALLY OVER THE DECK OVERLAY EXPANSION GAP OR FIXED JOINT, MARKED OUT TO THE MANUFACTURER'S RECOMMENDED WIDTH.
2. REMOVE THE BITUMINOUS CONCRETE PAVEMENT FULL DEPTH AS SHOWN ON THE PLANS. THE PAVEMENT SHALL BE DRY AND SAW CUT TO THE LIMITS REQUIRED TO PLACE THE JOINT. A PNEUMATIC HAMMER AND CHISEL MAY BE USED ADJACENT TO THE CURB ONLY WHEN SAW CUTTING IS NOT POSSIBLE.
3. BLAST CLEAN THE JOINT AREA OF DEBRIS, ASPHALT AND SHEET MEMBRANE. THOROUGHLY DRY THE JOINT AREA WITH COMPRESSED AIR PRIOR TO APPLYING BINDER MATERIAL.
4. REPAIR MATERIAL GREATER THAN 4 INCHES FROM FINISHED GRADE WITH RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE MEETING THE REQUIREMENTS OF SUBSECTION 780.04.
5. PLACE PROPERLY SIZED HEAT RESISTANT BACKER ROD IN THE MOVEMENT GAP ALLOWING FOR 1" +/- OF BINDER ABOVE THE ROD.
6. HEAT AND PLACE THE BINDER MATERIAL AS RECOMMENDED BY THE MANUFACTURER.
7. PLACE 1/4" THICK BY 8" WIDE SECTIONS OF STEEL PLATE OVER THE CENTER OF THE MOVEMENT GAP. SECURE THE PLATES FROM MOVING BY INSERTING LOCATING PINS THROUGH THE PRE-STAMPED HOLES INTO BACKER ROD AND COVER WITH HOT BINDER. THE STEEL PLATES MAY BE OMITTED WHERE THE ENGINEER DETERMINES THAT THE APPROACH SLAB OR BRIDGE DECK WILL PROVIDE INADEQUATE SUPPORT AND WHERE VERTICAL MOVEMENT OF THE PLATES MIGHT OCCUR.
8. HEAT AND MIX THE BINDER MATERIAL AND AGGREGATE AS RECOMMENDED BY THE MANUFACTURER.
9. INSTALLATION OF MATERIAL, COMPACTION, AND TOP COATING SHALL BE AS RECOMMENDED BY THE MANUFACTURER.
10. IMMEDIATELY AFTER TOP COATING, CAST AN ANTI-SKID MATERIAL OVER THE JOINT TO REDUCE THE RISK OF TRACKING.
11. ONCE THE JOINT REACHES 82 DEG C (180 DEG F) +/-, WATER MAY BE USED TO EXPEDITE THE COOLING PROCESS.
12. PROTECT JOINT FROM TRAFFIC UNTIL THE MATERIAL HAS COOLED TO 51 DEG C (125 DEG F) +/-.

WEATHER LIMITATIONS

APPLY BINDER MATERIAL ONLY WHEN THE FOLLOWING CONDITIONS PREVAIL OR AS RECOMMENDED BY THE MANUFACTURER:


1. THE AMBIENT AIR TEMPERATURE IS AT LEAST 10 DEG C (50 DEG F) AND RISING.
2. THE ROAD SURFACE IS DRY.
3. WEATHER CONDITIONS OR OTHER CONDITIONS ARE FAVORABLE AND ARE EXPECTED TO REMAIN SO FOR THE PERFORMANCE OF SATISFACTORY WORK.



ASPHALTIC PLUG-TYPE JOINT DETAIL - REHAB

NOTES: (NOT TO SCALE)

1. THE CONTRACTOR SHALL REMOVE ALL ASPHALTIC PLUG JOINT MATERIAL AND DETERIORATED CONCRETE AS DIRECTED BY THE ENGINEER. REMOVAL OF THE FIRST 4 INCHES OF MATERIAL SHALL BE INCLUDED IN THE BID PRICE FOR ITEM 516.10 BRIDGE EXPANSION JOINT, ASPHALTIC PLUG. ANY REMOVAL OF MATERIAL GREATER THAN 4 INCHES SHALL BE INCLUDED IN THE BID PRICE OF ITEM 580.20 RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE.
2. THE CONTRACTOR SHALL REPLACE REMOVED MATERIAL THAT IS LESS THAN 4" FROM FINISHED GRADE WITH ASPHALTIC PLUG JOINT MATERIAL MEETING THE REQUIREMENTS OF SUBSECTION 707.15. ALL REMOVED MATERIAL THAT IS GREATER THAN 4 INCHES FROM FINISHED GRADE SHALL BE REPLACED WITH RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE MEETING THE REQUIREMENTS OF SUBSECTION 780.04.
3. REINFORCING STEEL NOT SHOWN FOR CLARITY.




ASPHALTIC PLUG-TYPE JOINT DETAIL - NEW
(NOT TO SCALE)

REVISIONS

MAY 7, 2010	APPROVED FOR USE BY VAOT STRUCTURES SECTION

BRIDGE JOINT
ASPHALTIC PLUG



STRUCTURES
DETAIL
SD-516.10