



# Rockingham

## Interstate 91 Bridges 24N and 24S

Rockingham Bridges 24N and 24S — IM 091-1(66)

**Project Location: Town of Rockingham in Windham County on Interstate 91 over the Williams River and Green Mountain Railroad. The bridge is located approximately 1/4 mile north of Exit 6 on Interstate 91.**


### PROJECT MILESTONES

- Request For Proposals (RFP) Released  
November 2015
- Technical Proposals Received  
March 2016
- Price Proposals Open  
May 2016
- Contract Award  
July 2016
- Construction Schedule  
April 2017-June 2020

The Rockingham Bridge 24N and 24S project will replace the existing bridges, which are in poor condition, with two new bridges on the same alignment. The existing bridges are twin four span, two lane structures which were constructed in 1960-61 and rehabilitated in 1988. The bridges are 850-feet in length. The existing bridge superstructure (deck and beams) is composed of a steel deck truss, as well as a concrete slab, and are in poor condition with areas of significant concrete spalling and exposed rebar on the underside of the deck as well as areas of section loss in structural steel. Additionally, the existing bridges are narrow, only 30 FT wide, compared to the required 38 FT width of the standard Interstate.


This project is being contracted as a Design-Build project meaning a method of project delivery whereby a single entity is contractually responsible to perform design, construction, and related services. Design-Build teams will each submit Technical and Price Proposals which will then be scored by Vtrans based on the quality of the bridge concept. The team with the best combination of concept and bid price will be awarded the contract.

Vtrans has developed a Base Technical Concept (BTC) for this project consisting of two new Cast-in-Place Segmental Concrete Box Girder bridges, each 880 FT long. The two separate structures, while a similar construction method to the one currently being build in Brattleboro, will be two distinct bridges as shown below.



BRIDGE TERMINOLOGY


Existing Steel Deck Truss





Construction Schedule: Spring 2017 thru 2020.
Design Build Team: Reed & Reed, Inc./HDR Engineering Inc.
Cost: \$44,300,000
VTrans Resident Engineer: Daryl Bassett
VTrans Project Manager: Douglas Bonneau, P.E.
Public Outreach Contact: Stephanie Barrett (802) 862-6085

Accommodations for Traffic During Construction: The bridges will be constructed in two phases with traffic being maintained on crossovers and one lane of traffic in each direction.



Location Map



Similar Bridge under construction



TYPICAL CONCRETE DECK DETERIORATION



Typical Pier Deterioration



https://www.facebook.com



https://twitter.com/511VT

For more details, click here.

