

RELOCATE AND REMOVE EXISTING TEMPORARY BRIDGE

****From Canaan ER ST 0271(16)**

xx. DESCRIPTION. This work shall consist of relocating, maintaining, removing, loading, and delivering to a designated location an existing temporary bridge and designing, constructing, maintaining, and removing temporary bridge substructures and approaches in accordance with the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 528 of the Standard Specifications.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Relocate and Remove Existing Temporary Bridge) to be measured for payment will be on a lump sum basis in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Relocate and Remove Existing Temporary Bridge) will be paid for at the Contract lump sum price. Payment will be full compensation for relocating, maintaining, and removing the bridge; loading and delivering the bridge components to a designated location; designing, detailing, constructing, and maintaining temporary bridge substructures and approaches; placing and removing geotextile; and placing and removing pavement and pavement markings when paved approaches are required.

Partial payments will be made as follows:

- (a) An initial payment of 40% of the lump sum price will be paid upon the satisfactory relocation of the existing temporary bridge to its new location on the project.
- (b) A second payment of 40% of the lump sum price will be paid upon the satisfactory transition of traffic to the detour.
- (c) The remaining 20% of the lump sum price will be paid upon the removal of the temporary bridge, its substructures, and approaches; loading and delivery of the temporary bridge components to a designated site; cleaning up of the project site; and establishment of vegetation, all to the satisfaction of the Engineer.

Payment will be made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|---|-----------------|
| 900.645 Special Provision (Relocate and Remove Existing Temporary Bridge) | Lump Sum |