

REMOVE AND RELOCATE TIMBER STRUCTURES

****From Brownington BRO 1449(28)**

- xx. DESCRIPTION. This work shall consist of removing and relocating timber structures at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 522 of the Standard Specifications, with the exception that the requirements of Subsection 522.04 shall not apply.

- xx. MATERIALS.

(a) Lumber and Hardware. New lumber and hardware shall meet the requirements of Section 522 for Structural Lumber and Timber, Treated. The lumber shall be a commercially available material matching the existing deck, stairway, and railing.

(b) Concrete. Concrete shall meet the requirements of Section 501 for Concrete, High Performance Class B.

- xx. GENERAL CONSTRUCTION REQUIREMENTS.

(a) Remove and Relocate Existing Timber Deck and Stairway. The existing timber deck and stairway shall be relocated in kind at a new location outside of the limit of new stone fill as shown in the Plans and as directed by the Engineer.

(b) Remove and Relocate Existing Timber Stairway. The existing timber stairway shall be relocated in kind at a new location away from the existing stockade fence as shown in the Plans and as directed by the Engineer. The stairway and deck railings shall be reconfigured to conform to the new location.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Remove and Relocate Existing Timber Deck and Stairway) and Special Provision (Remove and Relocate Existing Timber Stairway) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantities of Special Provision (Remove and Relocate Existing Timber Deck and Stairway) and Special Provision (Remove and Relocate Existing Timber Stairway) will be paid for at the Contract lump sum price. Payment will be full compensation for removing, relocating, and reconfiguring the timber structures as specified; furnishing all new materials required, including but not limited to lumber, concrete, and hardware; for performing any necessary excavation or other foundation work at the new location; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

10/2/2012

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Remove and Relocate Existing Timber Deck and Stairway)	Lump Sum
900.645 Special Provision (Remove and Relocate Existing Timber Stairway)	Lump Sum