

REMOVE AND REPLACE RESIDENTIAL WALKWAY

****From Readsboro BRO 1441(25)**

xx. DESCRIPTION. This work shall consist of removing an existing concrete walkway with wooden stairs and replacing them with a new concrete sidewalk and treated structural lumber stairway.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Sections 522 and 618 of the Standard Specifications.

xx. MATERIALS.

(a) Sidewalk. Materials for sidewalk shall meet the requirements of Section 618 for Portland Cement Concrete Sidewalk.

(b) Stairway. New lumber and hardware for stairway shall meet the requirements of Section 522 for Structural Lumber and Timber, Treated. The lumber shall be a commercially available material matching the existing stairway and railing.

xx. CONSTRUCTION REQUIREMENTS. The new concrete sidewalk shall be approximately 1.5 m wide x 3.5 m long (5'-0" feet wide x 11'-6" long).

The new timber stairway shall accommodate a rise of approximately 1 m (3 feet). The final width, length, and number of steps will be determined by the Engineer.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Replace Residential Walkway) to be measured for payment will be on a lump sum basis in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Replace Residential Walkway) will be paid for at the Contract lump sum price. Payment will be full compensation for removing and disposing of the existing walkway; for furnishing all new materials required, including but not limited to lumber, concrete, hardware, and timber connectors; for performing any necessary excavation or other foundation work at the new location; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Remove and Replace Residential Walkway)	Lump Sum