

REMOVE AND RESET EXISTING TIMBER DECK

****From Barre City FEGC F 026-1(34) C/2**

- xx. DESCRIPTION. This work shall consist of removing, storing, and resetting an existing timber deck at the location indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 522 of the Standard Specifications, with the exception that the requirements of Subsection 522.04 shall not apply.

- xx. MATERIALS. Any new lumber and hardware that are required to re-attach the existing deck in its original location shall meet the requirements of Section 522 for Structural Lumber and Timber, Treated. The lumber shall be a commercially available material.

- xx. GENERAL CONSTRUCTION REQUIREMENTS. The existing timber deck shall be removed, temporarily stored at the Contractor's staging area, and then relocated back to the original location as shown in the Plans and as directed by the Engineer.

The existing timber deck shall not be removed more than two weeks prior to the time the Contractor needs access to the sidewalk or utilities beneath the deck, and it shall be reset to its original location no more than two weeks after the completed sidewalk has been accepted by the Engineer.

The deck shall be adjusted to properly match the existing building in line and elevation so that it continues to function as currently intended. The Contractor shall repair any damaged pieces in kind and shall touch-up any marred surfaces with the applicable matching finish.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Reset Existing Timber Deck) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Reset Existing Timber Deck) will be paid for at the Contract lump sum price. Payment will be full compensation for removing, relocating, storing, and resetting the existing deck as specified; furnishing any new materials required, including but not limited to lumber and hardware; performing any necessary repairs to damage resulting from the relocation; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Partial payments will be made as follows:

- (a) A payment of 50 percent of the Contract lump sum price will be made upon removal and storage of the timber deck.
- (b) The remaining 50 percent of the Contract lump sum price will be paid upon returning the timber deck to its original condition and location.

Payment will be made under:

Pay Item

Pay Unit

900.645 Special Provision (Remove and Reset
Existing Timber Deck)

Lump Sum