

10/2/2012

REMOVE AND STOCKPILE STONE WALL

****From Bennington AC NH 019-1(52)**

- xx. DESCRIPTION. This work shall consist of removing and stockpiling an existing stone wall at the locations indicated in the Plans and as directed by the Engineer.
- xx. CONSTRUCTION REQUIREMENTS. The stone in the wall within the highway easement shall be removed and stockpiled outside the area of construction to a site mutually agreeable to the property owner and the Contractor. The Contractor shall take precautions to not damage the stone during this work.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Stockpile Stone Wall) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Stockpile Stone Wall) will be paid for at the Contract lump sum price. Payment will be full compensation for removing and stockpiling the stone wall as specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Remove and Stockpile Stone Wall)	Lump Sum