

ROADWAY WEATHER INFORMATION SYSTEM (RWIS) EQUIPMENT AND INSTALLATION

****From Brookfield-Berlin IM SURF(11)**

- xx. DESCRIPTION. This work shall consist of temporarily removing and re-installing existing roadway weather information system (RWIS) equipment in accordance with the Contract Documents and as directed by the Engineer.
- xx. MATERIALS. Materials shall be approved by the Engineer prior to use.
- xx. CONSTRUCTION REQUIREMENTS. Following implementation of the traffic control package, the Contractor, in coordination with the Engineer, shall contact Agency Fiber Optic Project Manager Mark Gerrish [Tel.: (802)828-2834] to coordinate the temporary removal of existing RWIS fiber optic pucks located at Northbound MM 39.4.

When surfacing and pavement marking work is complete, Mr. Gerrish shall be contacted again to coordinate the re-installation of the RWIS fiber optic pucks.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (RWIS Labor and Equipment) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (RWIS Labor and Equipment) will be paid for at the Contract lump sum price. Payment will be full compensation for removing and re-installing the existing RWIS fiber optic pucks; coordinating the work as specified and as required; and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Payment for providing traffic control for performing the work under this Section will be made under Contract item 641.10 Traffic Control (RWIS Installation).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (RWIS Labor and Equipment)	Lump Sum