

REPAIRING STONE MASONRY, JAHN PERMEABLE MORTAR SYSTEM

****From Woodstock BHO 1444(52) & Woodstock ST 1444(58)**

- xx. DESCRIPTION. This work shall consist of repairing existing stone masonry in accordance with the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, Section 602 of the Standard Specifications, and Work Plan for Research Investigation No. WP-2011-5 included in the Contract Documents.

- xx. GENERAL REQUIREMENTS. Manufacturer Cathedral Stone® will provide training and demonstrate a mock-up utilizing the specified permeable mortar system in accordance with the Contract Documents.

Manufacturer Cathedral Stone® will provide the materials required for system application on the substructure units requiring rehabilitation as detailed in the Plans.

The Contractor shall perform the necessary repairs to the indicated substructure units utilizing the Jahn Permeable Mortar System as provided by Cathedral Stone®.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Repairing Stone Masonry, Jahn Permeable Mortar System) and Special Provision (Stone Masonry Repair Material, Jahn Permeable Mortar System) to be measured for payment will be on a lump sum basis in the complete and accepted work.

The quantity of Special Provision (On-site Masonry Mock-up and Training, Jahn Permeable Mortar System) to be measured for payment will be on a lump unit basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Repairing Stone Masonry, Jahn Permeable Mortar System) at the location specified will be paid for at the Contract lump sum price. Payment will be full compensation for removing material specified from the face of the stone masonry; filling cavities; performing the work in full compliance with the Contract Documents and manufacturer's recommendations; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

The accepted quantity of Special Provision (Stone Masonry Repair Material, Jahn Permeable Mortar System) will be paid for at the Contract lump sum price. Payment will be full compensation for the total of all costs associated with providing the specified materials in accordance with the Contract Documents.

The accepted quantity of Special Provision (On-site Masonry Mock-up and Training, Jahn Permeable Mortar System) will be paid for as specified for force account work in Subsection 109.06. Payments will be drawn against the Contract Lump Unit amount. To provide a common proposal for all bidders, the Agency has entered an amount in the proposal to become part of the Contractor's total bid.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Repairing Stone Masonry, Jahn Permeable Mortar System)(East Abutment)	Lump Sum
900.645 Special Provision (Repairing Stone Masonry, Jahn Permeable Mortar System)(Pier)	Lump Sum
900.645 Special Provision (Stone Masonry Repair Material, Jahn Permeable Mortar System)	Lump Sum
900.650 Special Provision (On-site Masonry Mock-up and Training, Jahn Permeable Mortar System)(N.A.B.I)	Lump Unit