

TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT

****These provisions are for use in conjunction with erosion prevention and sediment control performed under the requirements of Section 900 of the Special Provisions.**

****From Hartford-Sharon IM 089-1(55)**

xx. DESCRIPTION. This work shall consist of constructing a temporary access road and associated staging areas for accessing an existing culvert location(s), and restoring the disturbed areas to their original condition in accordance with the Plans and as directed by the Engineer.

xx. MATERIALS. Materials shall meet the requirements of the following Subsections:

Geotextile For Roadbed Separator649.02
Earth Borrow703.02
Aggregate Surface Course704.12
Project Demarcation Fence727.04

xx. GENERAL REQUIREMENTS. Prior to construction, the Contractor shall submit to the Engineer site-specific plans, including necessary traffic control and locations of guardrail removal, and proposed temporary access road, staging area, and maintenance details associated with the work.

These plans shall also include limits for Project Demarcation Fence and locations of erosion prevention and sediment control measures in the project areas affected by temporary access road and staging area construction. All work shall be performed within the Project Demarcation Fence limits.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Temporary Access Road and Staging Areas, Culvert) to be measured for payment will be on a lump sum basis in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Access Road and Staging Areas, Culvert) will be paid for at the Contract lump sum price. Payment will be full compensation for preparing a site plan; constructing and removing the temporary access road and associated staging areas at the location(s) specified; performing any necessary excavation; removing and resetting guardrail; restoring the site to its original condition; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment for erosion prevention and sediment control measures associated with the work will be made under Contract item 900.650 Special Provision (Erosion Prevention and Sediment Control Measures).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Temporary Access Road and	Lump Sum

Staging Areas, Culvert)

For multiple site projects:

900.645 Special Provision (Temporary Access Road and Lump Sum
Staging Areas, Culvert)(I89 - Br. No. 59-2)