

TEMPORARY ACCESS ROAD AND STAGING AREAS, SLIDE

****From Essex STP 030-1(20)**

- xx. DESCRIPTION. This work shall consist of constructing a temporary access road and associated staging areas for accessing an existing slide location(s), and restoring the disturbed areas to their original condition in accordance with the Plans and as directed by the Engineer.
- xx. MATERIALS. Materials shall meet the requirements specified in the Plans.
- xx. GENERAL REQUIREMENTS. Prior to construction, the Contractor shall submit to the Engineer site-specific plans, including necessary traffic control and locations of guardrail removal, and proposed temporary access road, staging area, and maintenance details associated with the work.

These plans shall also include limits for Project Demarcation Fence and locations of erosion prevention and sediment control measures in the project areas affected by temporary access road and staging area construction. All work shall be performed within the Project Demarcation Fence limits.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Temporary Access Road and Staging Areas, Slide) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Access Road and Staging Areas, Slide) will be paid for at the Contract lump sum price. Payment will be full compensation for preparing a site plan; constructing and removing the temporary access road and associated staging areas at the location(s) specified; performing any necessary excavation; removing and resetting guardrail; restoring the site to its original condition; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment for materials, including erosion prevention and sediment control measures, associated with the work and not paid for under a separate Contract item will be considered incidental to Special Provision (Temporary Access Road and Staging Areas, Slide).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Temporary Access Road and Staging Areas, Slide)	Lump Sum