

TEMPORARY STEEL SHEET PILING

**\*\*From Barre-Town STP SCRP(10)**

- xx. DESCRIPTION. This work shall consist of furnishing and driving all necessary temporary steel sheet piling at the locations indicated in the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 505 of the Standard Specifications.

- xx. GENERAL. The Contractor may propose locations for driving temporary steel sheet piling alternate to those shown on the Plans. All locations shall be approved by the Engineer prior to beginning work.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Temporary Steel Sheet Piling) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Steel Sheet Piling) will be paid for at the Contract lump sum price. Payment will be full compensation for designing, furnishing, transporting, storing, handling, and placing the material specified, including reinforcing steel, splices, wales, and braces, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment for this work will be made periodically as determined by the Engineer.

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Temporary Steel Sheet Piling)	Lump Sum