

WATERLINE, MUNICIPAL

****From Barre City BHF 6000(15)S**

- xx. DESCRIPTION. This work shall consist of the installation and testing of a municipal waterline within the limits indicated on the Plans.

The work under this Section shall be performed in accordance with these provisions, the Plans, and the Dufresne & Associates "City of Barre, Vermont Contract Documents for Prospect Street over Stevens Branch".

- xx. MATERIALS. Materials shall meet the requirements of the Dufresne & Associates "City of Barre, Vermont Contract Documents for Prospect Street over Stevens Branch".

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Waterline, Municipal) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Waterline, Municipal) will be paid for at the Contract lump sum price. Payment will be full compensation for all work required for furnishing and installing a municipal waterline and appurtenances, including the heat trace system, in accordance with the Contract Documents; for conducting pressure and leakage tests; disinfecting the system; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made as follows:

A payment of 90% of the Contract lump sum price will be made when the new waterline has been installed, all necessary adjustments have been made, all tests have been successfully completed, and the line has been placed in service to the satisfaction of the Engineer.

The remaining 10% of the Contract lump sum price will be paid once the new waterline has provided continuous trouble-free service for a period of 30 calendar days as determined by the Engineer.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Waterline, Municipal)	Lump Sum