

INSTALL DETECTABLE WARNING SURFACE

****From Burlington-South Burlington NH 2624(1)**

- xx. DESCRIPTION. This work shall consist of installing detectable warning surface(s), provided by the Agency, at the location(s) indicated on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 618 of the Standard Specifications.

- xx. MATERIALS. The Agency will supply the detectable warning surface(s).

The detectable warning surface(s) to be used are located at the Agency's District 5 Maintenance Facility located at 5 Barnes Avenue in Colchester, VT. The Contractor shall load the detectable warning surface(s) onto suitable transport, deliver, unload, stockpile, and install them on the project at the locations indicated in the Plans.

The Contractor shall contact General Maintenance Manager Art Danyow [Tel.: (802)453-3104] or Area Maintenance Supervisor Dan Champney [Tel.: (802)654-1725] a minimum of two (2) weeks in advance to arrange for pick-up of these materials at the designated location.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Install Detectable Warning Surface) to be measured for payment will be the number of square meter (square foot) of detectable warning surface installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Install Detectable Warning Surface) will be paid for at the Contract unit price per square meter (square foot). Payment will be full compensation for loading, transporting, storing, and installing the Agency-supplied materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.670 Special Provision (Install Detectable Warning Surface)	Square Foot
900.675 Special Provision (Install Detectable Warning Surface)	Square Meter