

INSTALLATION OF GRID DECK

****These provisions are for use in installing pre-purchased materials. The Final Pay Quantity (FPQ) designation, if used, requires the inclusion of the associated Section 109 provisions.**

****From North Hero-Grand Isle BHF 028-1(21)**

- xx. DESCRIPTION. This work shall consist of installing grid decking as detailed in the Plans.
- xx. MATERIALS. The required materials for performing the work under this Section will be provided to the Contractor as indicated in the Plans.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Installation of Grid Deck) (FPQ) to be measured for payment will be the number of square meters (square feet) of replacement and new grid decking used in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Installation of Grid Deck) (FPQ) will be paid for at the Contract unit price per square meter (square foot). Payment will be full compensation for unloading the material at delivery, stockpiling, loading the material from stockpile, unloading, and installing the material in its final location as specified in the Contract Documents, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.670 Special Provision (Installation of Grid Deck)(FPQ)	Square Foot
900.675 Special Provision (Installation of Grid Deck)(FPQ)	Square Meter