

REMOVE AND RESET BRICK CROSSWALK

**\*\*From Burlington-South Burlington NH 2624(1)**

xx. DESCRIPTION. This work shall consist of removing and resetting an existing brick crosswalk(s) at the location(s) indicated in the Contract Documents and as directed by the Engineer.

xx. MATERIALS. Materials shall meet the requirements of the following Subsections:

Sand.....703.03  
Subbase of Crushed Gravel, Fine Graded.....704.05

xx. CONSTRUCTION REQUIREMENTS. Removing and resetting of the brick crosswalk shall be performed as indicated in the Plans.

The Contractor shall re-use all existing materials to the greatest extent possible for the resetting of the brick crosswalk.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Reset Brick Crosswalk) to be measured for payment will be the number of square meters (square feet) of brick crosswalk removed and reset in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Reset Brick Crosswalk) will be paid for at the Contract unit price per square meter (square foot). Payment will be full compensation for removing and resetting the existing brick crosswalk in accordance with the Contract Documents and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.670 Special Provision (Remove and Reset Brick Crosswalk)	Square Foot
900.675 Special Provision (Remove and Reset Brick Crosswalk)	Square Meter