

INSTALL GEOTEXTILE UNDER STONE FILL

****From Cambridge STP 0235(9)**

- xx. DESCRIPTION. This work shall consist of installing Geotextile Under Stone Fill, provided by the Agency, at the locations indicated on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 649 of the Standard Specifications.

- xx. MATERIALS. The Agency will supply the Geotextile Under Stone Fill in accordance with the Contract Documents.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Install Geotextile Under Stone Fill) to be measured for payment will be the number of square meters (square yards) placed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Install Geotextile Under Stone Fill) will be paid for at the Contract unit price per square meter (square yard). Payment will be full compensation for loading, transporting, storing, handling, placing, repairing, and removing the Agency-supplied materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Unless otherwise specified in the Contract, payment for the maintenance of geotextile installed will not be paid for directly, but will be considered incidental to Special Provision (Install Geotextile Under Stone Fill).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.675 Special Provision (Install Geotextile Under Stone Fill)	Square Meter (Square Yard)