

CONCRETE OUTLET STRUCTURE WITH CAST IRON GRATE

**\*\*From Morristown STP F 029-1(2)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing a precast concrete outlet structure with cast iron grate and grate valve with non-rising stem, as shown on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 604 of the Standard Specifications.

- xx. MATERIALS. Materials shall be furnished at the sizes and configuration shown in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Concrete Outlet Structure with Cast Iron Grate) to be measured for payment will be for each outlet structure installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Concrete Outlet Structure with Cast Iron Grate) will be paid for at the Contract unit price per each. Payment will be full compensation for furnishing, transporting, handling, assembling, and placing the materials specified, including concrete, concrete risers, top sections, reinforcing steel, steps, mortar, brick, frames, grates, covers, coatings, underdrain connections to gate valve, gate valve with non-rising stem, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Concrete Outlet Structure with Cast Iron Grate)	Each