

REMOVAL OF EXISTING AREA LIGHTING SYSTEM

****From Richmond STP 0284(17) Richmond CMG PARK(31)**

- xx. DESCRIPTION. This work shall consist of removing, and salvaging or disposing of, an existing area lighting system at the location indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 679 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove and salvage or dispose of lighting system components, including but not limited to light pole bases, light poles, luminaires, pull boxes, and wiring. Existing buried conduit shall be abandoned in place or removed if in conflict with proposed improvements.

The existing lighting system shall be removed up to the existing pull box indicated on the Plans. Existing conduit from the existing pull box indicated on the Plans to the existing power cabinet shall remain and be reused. All existing wiring shall be removed to the existing power cabinet.

Salvaging of lighting system components shall be performed in accordance with the Contract Documents. Components to be salvaged that are damaged or lost by the Contractor during removal shall be repaired or replaced to the satisfaction of VTrans and at the Contractor's expense.

Excavated areas shall be backfilled with material acceptable to the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removal of Existing Area Lighting System) to be measured for payment will be for each area lighting system removed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removal of Existing Area Lighting System) will be paid for at the Contract unit price per each. Payment will be full compensation for removing and handling the existing area lighting system components as specified in the Contract Documents; performing any required excavation and backfilling; and for furnishing all labor, materials, tools, equipment, and incidentals necessary to complete the work.

Costs associated with providing traffic control and/or flaggers for performing the work will be paid under the appropriate Contract item(s).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Removal of Existing Area Lighting System)	Each