

REMOVAL OF TEMPORARY BRIDGE

****From Enosburg BRO 1448(40)**

- xx. DESCRIPTION. This work shall consist of removing an existing temporary bridge within the limits indicated in the Plans and as directed by the Engineer.
- xx. REMOVAL OF EXISTING TEMPORARY BRIDGE. Removal shall be performed in accordance with Subsection 529.04. Dismantling and salvaging of the temporary bridge components shall be performed in accordance with the Contract Documents.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removal of Temporary Bridge) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removal of Temporary Bridge) will be paid for at the Contract lump sum price. Payment will be full compensation for removing the temporary bridge, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Removal of Temporary Bridge)	Lump Sum