

GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING

****From Royalton BRS 0147(13)**

xx. DESCRIPTION. This work shall consist of furnishing and erecting guardrail approach sections to concrete or combination bridge railing as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

xx. SUBMITTALS. Fabrication Drawings shall be submitted to the Structures Engineer for approval in accordance with Subsection 105.03.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Guardrail Approach Section To Concrete Combination Bridge Railing) to be measured for payment will be the number of units installed in the complete and accepted work, measured within the pay limits shown on the Plans.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Guardrail Approach Section To Concrete Combination Bridge Railing) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, transporting, handling, and placing the materials specified, including terminal connector, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Guardrail Approach Section To Concrete Combination Bridge Railing)	Each