

LED BLANK OUT SIGNS

****From Rutland City-Proctor STP 2728(1) Rutland City NH 2716(1)
Rutland City STP 019-3(57)**

- xx. DESCRIPTION. This work shall consist of installing light-emitting diode (LED) "No Turn on Red" blank out signs at the locations indicated in the Plans and as directed by the Engineer.
- xx. MATERIALS. Materials shall meet the requirements specified in the Plans and Subsection 752.05.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (LED Blank Out Signs) to be measured for payment will be for each intersection with LED Blank Out Sign(s) installed in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision Special Provision (LED Blank Out Signs) will be paid at the Contract unit price per each. Payment will be full compensation for furnishing, transporting, handling, and installing the materials specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Work to modify the controller assembly for the exclusive pedestrian phase will not be paid separately, but will be considered incidental to Special Provision (LED Blank Out Signs).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (LED Blank Out Signs)	Each