

RAILROAD SIGNAL CABINET

****Rutland City-Proctor STP 2728(1) Rutland City NH 2716(1) Rutland City STP 019-3(57)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing a railroad signal cabinet at the location indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 678 of the Standard Specifications.

- xx. GENERAL REQUIREMENTS. The Contractor shall submit Fabrication Drawings in accordance with Section 105.

All associated electrical work performed and all materials installed shall be subject to inspection and approval of the State or Municipal Electrical Inspector, whichever is applicable. As a minimum, all work must meet the requirements of the National Electrical Code (NEC) and the National Electrical Safety Code (NESC).

- xx. CONSTRUCTION REQUIREMENTS. The signal cabinet shall be installed in accordance with the Plans and directions furnished by the manufacturer. The type of mounting for the cabinet shall be as shown on the Plans. Signal cabinet shall be provided with locks and two keys for each lock.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Railroad Signal Cabinet) to be measured for payment will be the number of each signal cabinet installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Railroad Signal Cabinet) will be paid for at the Contract unit price per each. Payment will be full compensation for furnishing, transporting, handling, and installing the materials and equipment specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Railroad Signal Cabinet)	Each