

REMOVE EXISTING POWER DROP STANCHION

****From Hartland CMG Park(25)**

xx. DESCRIPTION. This work shall consist of removing existing power drop stanchion at the location(s) indicated in the Plans and as directed by the Engineer.

xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove and dispose of the existing power drop stanchion assembly, including the wired conduit, pull box, and concrete base. Existing wires in conduit that is not removed shall be capped.

Excavated areas shall be backfilled with material acceptable to the Engineer.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove Existing Power Drop Stanchion) to be measured for payment will be the number of each power drop stanchion removed in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove Existing Power Drop Stanchion) at the location specified will be paid for at the Contract unit price per each. Payment will be full compensation for removing and disposing of the existing power drop stanchion assembly, wired conduit, pull box, and concrete base; capping existing wired conduit; performing any required excavation and backfilling; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Remove Existing Power Drop Stanchion)	Each