

GUARDRAIL TRANSITION, STEEL BEAM TO BOX BEAM

****From Johnson BRF 030-2(26)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting guardrail transition as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. FABRICATION DRAWINGS. Fabrication Drawings shall be submitted in accordance with Section 105.

- xx. CONSTRUCTION REQUIREMENTS. Guardrail transition shall be provided and erected to the configuration shown in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Guardrail Transition, Steel Beam to Box Beam) to be measured for payment will be the number of meters (linear feet) of transition rail used in the complete and accepted work. Measurement will be made along the face of the rail from end to end or between the pay limits specified.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Guardrail Transition, Steel Beam to Box Beam) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, placing, delineating, and galvanizing the railing components, including W-beam section requiring replacement; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Guardrail Transition, Steel Beam to Box Beam)	Meter (Linear Foot)