

ELECTRIC DEMOLITION

****From Rutland City-Proctor STP 2728(1) Rutland City NH 2716(1)
Rutland City STP 019-3(57)**

- xx. DESCRIPTION. This work shall consist of removing existing lighting system(s), electric cable, connections to or disconnection from existing system(s), and salvaging existing.
- xx. GENERAL. The Contractor shall remove existing lighting systems or fixtures as indicated in the Plans. The Contractor will be responsible for coordinating with Green Mountain Power (GMP) for work in the vicinity of the project and salvaging of existing equipment.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Electric Demolition) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Electric Demolition) will be paid for at the Contract lump sum price. Payment will be full compensation for performing electric demolition as specified in the Contract Documents, utility coordination, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Electric Demolition)	Lump Sum