

REMOVAL OF EXISTING STRUCTURAL RAMP

****From Statewide STP SDWK(11)**

- xx. DESCRIPTION. This work shall consist of removing of an existing reinforced concrete ramp and wall at the location indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Sections 202 and 203 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove the existing reinforced concrete ramp and wall as shown in the Plans.

The removal of the existing ramp and wall shall include the support of the existing reinforced concrete wall to be retained as indicated in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removal of Existing Structural Ramp) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removal of Existing Structural Ramp) will be paid for at the Contract lump sum price. Payment will be full compensation for removing the existing structural ramp as specified and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Removal of Existing Structural Ramp)	Lump Sum