

PRECAST PRESTRESSED CONCRETE DECK PANEL

****From Hyde Park STP CULV(26)**

xx. DESCRIPTION. This work shall consist of manufacturing, transporting, and installing precast prestressed concrete deck panels at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 510 of the Standard Specifications.

xx. FABRICATION AND CONSTRUCTION REQUIREMENTS. Concrete deck panels shall be fabricated and installed to the configuration shown in the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Precast Prestressed Concrete Deck Panel) to be measured for payment will be the number of square meters (square feet) of deck panel used in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Precast Prestressed Concrete Deck Panel) will be paid for at the Contract unit price per square meter (square foot). Payment will be full compensation for detailing, fabricating, repairing, sandblasting, quality control testing, transporting, handling, and installing the materials specified, including concrete, reinforcement, prestressing steel, transverse ties, enclosures for prestressing steel, anchorages, anchor rods, and any other material contained within or attached to the members; for furnishing and implementing the erection plan; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.670 Special Provision (Precast Prestressed Concrete Deck Panel)(3½")	Square Foot
900.675 Special Provision (Precast Prestressed Concrete Deck Panel)(3½")	Square Meter