

BARRIER FOR TEMPORARY TRAFFIC PROTECTION

****From Granville ER STP 013-4(40)**

- xx. DESCRIPTION. This work shall consist of establishing and maintaining temporary traffic protection during construction operations at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. GENERAL CONSTRUCTION REQUIREMENTS. Temporary traffic protection shall be placed to the configuration shown in the Plans.

As applicable as detailed in the Plans, existing guardrail shall be removed and reset, new guardrail shall be installed, or temporary traffic barrier or delineation devices shall be placed, in order that full-width construction may be accomplished.

Removing and resetting existing guardrail, placing new guardrail, and temporary traffic barrier shall meet the requirements of Section 621. Delineation devices shall meet the requirements of Section 641.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Barrier for Temporary Traffic Protection) to be measured for payment will be the number of meters (linear feet) of barrier placed as temporary protection for traffic in the complete and accepted work, measured from end to end of each installation, including terminals.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Barrier for Temporary Traffic Protection) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for providing temporary traffic protection as specified in the Contract Documents, and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

The Contractor will be compensated at the unit price bid for Special Provision (Barrier for Temporary Traffic Protection) for either removing and resetting existing guardrail, placing new guardrail, or placing temporary traffic barrier for the purpose of providing temporary traffic protection. Only the initial removing and resetting of existing guardrail, temporary placement of new guardrail, or placement of temporary traffic barrier will be paid; any other interim such placements prior to installation of final guardrail, either for the convenience of the Contractor or as directed by the Engineer, will be included in the unit price bid for Special Provision (Barrier for Temporary Traffic Protection).

New guardrail installed permanently on the project will be paid separately under the appropriate item(s) in the Contract.

Existing guardrail removed and not reset either temporarily or permanently on the project will be paid separately under Contract item 621.80.

Placement of barrels or other delineation devices for the purpose of providing temporary traffic protection will be paid separately under Contract item 641.10.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Barrier for Temporary Traffic Protection)	Linear Foot