

DRAIN TROUGH

****From Hartford BHF BPNT(12)**

xx. DESCRIPTION. This work shall consist of removing an existing drain trough; fabricating, furnishing, and installing a new drain trough; or restoring an existing drain trough as detailed in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 516 of the Standard Specifications.

xx. MATERIALS. Materials shall meet the requirements of Subsection 516.02 and the following:

Joint Sealer, Polyurethane.....	707.05
Grease Rustproofing Compound.....	708.04
Steel Pipe, Galvanized.....	740.05

xx. CONSTRUCTION REQUIREMENTS. Restored or replacement drain troughs shall be constructed to the configuration shown in the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Replace Drain Trough) or Special Provision (Remove and Restore Drain Trough) to be measure for payment will be the number of meters (linear feet) of drain trough installed in the complete and accepted work.

xx. BASIS OF PAYMENT. The quantity of Special Provision (Remove and Replace Drain Trough) or Special Provision (Remove and Restore Drain Trough) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for removing existing drain trough and component hardware; fabricating, furnishing, handling, and installing new drain trough and component hardware; restoring an existing drain trough; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Remove and Replace Drain Trough)	Meter (Linear Foot)
900.640 Special Provision (Remove and Restore Drain Trough)	Meter (Linear Foot)