

DEMOLITION OF ABOVE GROUND ELECTRIC VAULT

****From Bristol HES 021-1(28)(Re-advertised)**

- xx. DESCRIPTION. This work shall consist of removing an existing vault and reconnecting existing lighting as indicated in the Plans and as directed by the Engineer.

- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove and dispose of the existing vault assembly, including cabinet, disconnects, meter, wire, other internal contents, and concrete base.

Excavated areas shall be backfilled with material acceptable to the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Demolition of Above Ground Electric Vault) at the location specified to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Demolition of Above Ground Electric Vault) at the location specified will be paid for at the Contract lump sum price. Payment will be full compensation for removing and disposing of the existing vault cabinet, disconnects, meter, wire, other internal contents, and concrete base; reconnecting the existing lighting as directed by the Engineer; performing any required excavation and backfilling; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Demolition of Above Ground Electric Vault)	Lump Sum