

GRANULAR BORROW

**\*\*From Granville ER STP 013-4(40)**

- xx. DESCRIPTION. This work shall consist of furnishing and placing granular borrow in embankments as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 203 of the Standard Specifications.

- xx. MATERIALS. Granular borrow shall be uniformly graded from coarse to fine and shall meet the requirements of the following table in accordance with AASHTO T 27:

Sieve Designation	Percentage by Mass (Weight) Passing Square Mesh Sieves
4.75 mm (No. 4)	20 to 80
75 µm (No. 200)	0 to 12

The maximum size of stone particles shall not exceed 67 percent of the thickness of the layer being placed.

- xx. PLACEMENT. Borrow shall be placed in 150 mm (6 inches) maximum (loose measure) layers and compacted against the slope with the excavator bucket.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Granular Borrow) to be measured for payment will be the number of cubic meters (cubic yards) placed in the complete and accepted work, measured within the limits shown on the Plans or as directed by the Engineer.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Granular Borrow) will be paid for at the Contract unit price per cubic meter (cubic yard). Payment will be full compensation for furnishing, transporting, handling, and placing the material specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.608 Special Provision (Granular Borrow)	Cubic Yard