

STEEL BACKED TIMBER GUARDRAIL, FASCIA MOUNTED

**\*\*From Shrewsbury BHO 1443(49)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting fascia mounted steel backed timber guardrail as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. MATERIALS. Materials shall conform to the requirements specified in the Plans and Section 621.

- xx. GENERAL CONSTRUCTION REQUIREMENTS. Fascia mounted steel backed timber guardrail shall be constructed to the configuration detailed in the Plans.

- xx. METHOD MEASUREMENT. The quantity of Special Provision (Steel Backed Timber Guardrail, Fascia Mounted) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, measured within the pay limits shown on the Plans.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Steel Backed Timber Guardrail, Fascia Mounted) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the materials specified, including anchorage assemblies and plates for guardrail posts, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Steel Backed Timber Guardrail, Fascia Mounted)	Meter (Linear Foot)