

LANDSCAPE AREA RESTORATION

**** From Peru STP SCRP(4)**

- xx. DESCRIPTION. This work shall consist of performing landscape area restoration at the location indicated in the Plans and as directed by the Engineer.
- xx. GENERAL REQUIREMENTS. The work includes but is not limited to removing and stockpiling landscape stone, relocating landscape boulders, spreading cedar bark mulch, and restoring landscape stone and existing adjacent lawn area as shown in the Plans and to the satisfaction of the Engineer.
- xx. MATERIALS. Bark Mulch shall be Cedar and shall meet the requirements of Subsection 755.10(c). Bark Mulch shall be spread to a thickness of 2 inches.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Landscape Area Restoration) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Landscape Area Restoration) will be paid for at the Contract lump sum price. Payment will be full compensation for performing the specified restoration and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Landscape plantings and associated work, and removing and resetting existing concrete pavers will be paid for separately under the appropriate Contract items.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Landscape Area Restoration)	Lump Sum