

STAFF GAUGE

**** From Peru STP SCRP(4)**

- xx. DESCRIPTION. This work shall consist of the installation of a staff gauge at the location indicated in the Plans.

The work under this Section shall be performed in accordance with these provisions, the Plans and as directed by the Engineer.

- xx. MATERIALS. The staff gauge shall be constructed of iron and finished with a porcelain enamel to ensure easy reading and resistance to rust or discoloration. The gauge shall be accurately graduated every foot, tenth of a foot, and two-hundredths of a foot. The gauge shall have rubber grommets in the holes for fastening to the walls of the drain manhole.

- xx. CONSTRUCTION REQUIREMENTS. The staff gauge shall be securely mounted to the drain manhole structure using galvanized steel or similar non-rusting hardware, and shall be installed such that the "0" elevation is located at the culvert outlet invert as shown in the Plans. The staff gauge shall have a minimum total height of 8'-0".

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Staff Gauge) to be measured for payment will be on a lump sum basis in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Staff Gauge) will be paid for at the Contract lump sum price. Payment will be full compensation for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Staff Gauge)	Lump sum