

STOP LOG SYSTEM

**** From Peru STP SCR(4)**

xx. DESCRIPTION. This work shall consist of installing a stop log system at the location shown in the Plans and as directed by the Engineer.

xx. MATERIALS. Materials shall meet the requirements detailed in the Plans.

Treated Southern Pine, select structural timber boards shall meet the requirements of Section 522.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Stop Log System) to be measured for payment will be on a lump sum basis in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Stop Log System) will be paid for at the Contract lump sum price. Payment will be full compensation for installing the stop log system as detailed in the Contract Documents, furnishing all materials required, including associated hardware, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.645 Special Provision (Stop Log System)	Lump sum