

INSTALLATION OF STEEL PILINGS, HP 14X89

**\*\*From Lunenburg NH CULV(27)**

- xx. DESCRIPTION. This work shall consist of delivering and installing steel pilings, HP 14X89 as detailed in the Plans.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 506 of the Standard Specifications, except that the provisions of Subsections 506.03, 506.04, 506.05, and 506.06 shall not apply.

- xx. MATERIALS. The required materials for performing the work under this Section will be provided to the Contractor as indicated in the Plans. A total of **xx** HP 14X89 piles, a minimum of **xx** feet in length are available at **(Location)**. The remaining piles required for the project are available at **(Second Location)** and are a minimum of **xx** feet in length.

An on-site meeting at the **(Location)** will be required prior to removing the piles. The contact information is as detailed on the Contract Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Installation of Steel Pilings)(HP 14X89)to be measured for payment will be the number of kilograms (pounds) of steel used in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Installation of Structural Steel) (FPQ) will be paid for at the Contract unit price per kilogram (pound). Payment will be full compensation for loading the material at the District locations, delivering the material to the project site, unloading the material at delivery, stockpiling, loading the material from stockpile, unloading, and installing the material in its final location as specified in the Contract Documents, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.  
Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.635 Special Provision (Installation of Steel Pilings)(HP 14X89)	Kilogram (Pound)