

GRANULAR BACKFILL FOR STRUCTURES

****From Hubbardton ER STP 0161(26) & Hubbardton ER STP 0161(27)**

xx. DESCRIPTION. This work shall consist of furnishing and placing granular backfill for structures as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 204 of the Standard Specifications.

xx. MATERIALS. Material shall meet the requirements of Subsection 704.08.

xx. BACKFILL. Backfill shall be placed in 150 mm (6 inches) maximum (loose measure) horizontal layers and compacted to not less than 95 percent of maximum density.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Granular Backfill for Structures) to be measured for payment will be the number of cubic meters (cubic yards) placed in the complete and accepted work within the confines of the limits shown on the Plans or as directed by the Engineer.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Granular Backfill for Structures) will be paid for at the Contract unit price per cubic meter (cubic yard). Payment will be full compensation for furnishing, transporting, handling, and placing the material specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.608 Special Provision (Granular Backfill for Structures)	Cubic Meter (Cubic Yard)