

GRAVEL BAGS

****From Clarendon BHO 1443(39)**

- xx. DESCRIPTION. This work shall consist of furnishing, installing, maintaining, and removing gravel bags at the locations indicated in the Plans and as directed by the Engineer.
- xx. MATERIALS. Materials for Gravel Bags shall be furnished in accordance with the Plans and shall be approved by the Engineer prior to use.
- xx. CONSTRUCTION REQUIREMENTS. Gravel Bags shall be constructed, maintained, and removed as specified in the Plans and as directed by the Engineer.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Gravel Bags) to be measured for payment will be on a per unit basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Gravel Bags) will be paid for at the Contract unit price for each. Payment will be full compensation for preparing, placing, and removing the gravel bags, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Unless otherwise specified in the Contract, payment for the maintenance of Gravel Bags will be incidental to Special Provision (Grass Outlet Sediment Trap).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Gravel Bags)	Each